

Penrith Gospel Trust



Wastewater Management Plan: Proposed Alterations and Additions – 26 Kingswood Road, Orchard Hills, NSW

ENVIRONMENTAL



WATER



WASTEWATER



GEOTECHNICAL



CIVIL



PROJECT
MANAGEMENT



P1404110JR01V06
October 2016

Copyright Statement

Martens & Associates Pty Ltd (Publisher) is the owner of the copyright subsisting in this publication. Other than as permitted by the Copyright Act and as outlined in the Terms of Engagement, no part of this report may be reprinted or reproduced or used in any form, copied or transmitted, by any electronic, mechanical, or by other means, now known or hereafter invented (including microcopying, photocopying, recording, recording tape or through electronic information storage and retrieval systems or otherwise), without the prior written permission of Martens & Associates Pty Ltd. Legal action will be taken against any breach of its copyright. This report is available only as book form unless specifically distributed by Martens & Associates in electronic form. No part of it is authorised to be copied, sold, distributed or offered in any other form.

The document may only be used for the purposes for which it was commissioned. Unauthorised use of this document in any form whatsoever is prohibited. Martens & Associates Pty Ltd assumes no responsibility where the document is used for purposes other than those for which it was commissioned.

Limitations Statement

The sole purpose of this report and the associated services performed by Martens & Associates Pty Ltd is to provide a Wastewater Management Plan in accordance with the scope of services set out in the contract / quotation between Martens & Associates Pty Ltd and Penrith Gospel Trust (hereafter known as the Client). That scope of works and services were defined by the requests of the Client, by the time and budgetary constraints imposed by the Client, and by the availability of access to the site.

Martens & Associates Pty Ltd derived the data in this report primarily from a number of sources which may include for example site inspections, correspondence regarding the proposal, examination of records in the public domain, interviews with individuals with information about the site or the project, and field explorations conducted on the dates indicated. The passage of time, manifestation of latent conditions or impacts of future events may require further examination / exploration of the site and subsequent data analyses, together with a re-evaluation of the findings, observations and conclusions expressed in this report.


In preparing this report, Martens & Associates Pty Ltd may have relied upon and presumed accurate certain information (or absence thereof) relative to the site. Except as otherwise stated in the report, Martens & Associates Pty Ltd has not attempted to verify the accuracy of completeness of any such information (including for example survey data supplied by others).

The findings, observations and conclusions expressed by Martens & Associates Pty Ltd in this report are not, and should not be considered an opinion concerning the completeness and accuracy of information supplied by others. No warranty or guarantee, whether express or implied, is made with respect to the data reported or to the findings, observations and conclusions expressed in this report. Further, such data, findings and conclusions are based solely upon site conditions, information and drawings supplied by the Client etc. in existence at the time of the investigation.

This report has been prepared on behalf of and for the exclusive use of the Client, and is subject to and issued in connection with the provisions of the agreement between Martens & Associates Pty Ltd and the Client. Martens & Associates Pty Ltd accepts no liability or responsibility whatsoever for or in respect of any use of or reliance upon this report by any third party.

© October 2016
Copyright Martens & Associates Pty Ltd
All Rights Reserved

Head Office
6/37 Leighton Place
Hornsby, NSW 2077, Australia
ACN 070 240 890 ABN 85 070 240 890
Phone: +61-2-9476 9999
Fax: +61-2-9476 8767
Email: mail@martens.com.au
Web: www.martens.com.au

Document and Distribution Status								
Author(s)			Reviewer(s)		Project Manager		Signature	
Megan Kovelis, Michael Dumas			Gray Taylor Andrew Norris		Gray Taylor			
Revision No.	Status	Release Date	Document Location					
			File Copy	Stimson Consulting Services	Penrith Gospel Trust			
1	Draft	10/03/2014	1H,1E, 1P	1P				
2	Final	12/05/2014	1H,1E, 1P	1P				
3	Final	19/05/2014	1H,1E, 1P	1P				
4	Final	24/10/2014	1H,1E, 1P	1P				
5	Final	04/12/2014	1H,1E, 1P	1P				
6	Revised	26/10/2016	1H,1E, 1P	-	1P			

Distribution Types: F = Fax, H = hard copy, P = PDF document, E = Other electronic format. Digits indicate number of document copies.

All enquiries regarding this project are to be directed to the Project Manager.

Contents

1 INTRODUCTION.....	5
1.1 Study Overview	5
1.2 Project Scope and Aims	5
1.3 Proposed Development	5
1.4 Reference Documents	5
2 SITE DESCRIPTION	7
2.1 Location and Site Description	7
2.2 Site Investigations	8
2.3 Soil Profile	8
3 EXISTING WASTEWATER SYSTEM ASSESSMENT.....	9
3.1 Overview	9
3.2 Existing Wastewater System Description	9
3.3 Population and Wastewater Generation	10
3.4 Wastewater System Suitability	11
4 WASTEWATER ASSESSMENT.....	12
4.1 Overview	12
4.2 Design Hydraulic Load	12
4.3 Wet Weather Effluent Storage Tank	12
4.4 Pump Out Frequency	12
4.5 Effluent Pump-out Location	12
4.6 Specific System Requirements	13
4.7 System Monitoring, Inspections and Maintenance	14
4.8 Summary	14
4.9 Further Approvals	14
5 REFERENCES	15
6 ATTACHMENT A – SITE PLAN	16
7 ATTACHMENT B – FIGURES	17
8 ATTACHMENT C – BOREHOLE LOGS.....	19
10 ATTACHMENT D - WASTEWATER MANAGEMENT PLAN.....	23
11 ATTACHMENT E – SYDNEY WATER USAGE RATES	25
12 ATTACHMENT F – EXISTING WASTEWATER TREATMENT SYSTEM DESIGN (GEBEL, 2014)	28
13 ATTACHMENT G – PUMP-OUT CONTRACTOR INVOICE.....	30

1 Introduction

1.1 Study Overview

This wastewater management plan (WMP) is prepared to support a development application (DA) for approval of alterations and additions to an existing church at 26 Kingswood Road, Orchard Hills, NSW.

1.2 Project Scope and Aims

This WMP provides:

1. Detailed site description including: soils; vegetation; slope; drainage; and landuse.
2. Details of site investigations.
3. Description of the existing onsite wastewater management system (OSWMS).
4. Calculation of existing wastewater generation rates and loads.
5. Assessment of suitability of existing OSWMS and identification of any required system modification.
6. Specification of existing system modifications and a final wastewater management solution for the site.

1.3 Proposed Development

We understand the proposed development is for alterations and additions to the existing main building. Works specifically include:

- Construction of a new foyer area on the eastern side of the existing meeting hall.
- A new amenities block (current amenities block to be retained).
- Replacement of existing meeting building.

1.4 Reference Documents

This assessment is prepared in general accordance with the following guidelines:

- Penrith City Council (2010), *Development Control Plan: Section 13.3 Onsite Sewage Management*.

- Penrith City Council (2014) On-site Sewage Management and Greywater Reuse Policy.
- Department of Environment and Conservation (2004). *Environmental Guidelines-Use of effluent by Irrigation*.
- Australian / New Zealand Standard 1547 (2012), *Onsite domestic wastewater management*.

2 Site Description

2.1 Location and Site Description

Site information is summarised in Table 1.

Table 1: Site background information.

Site address	26 Kingswood Road, Orchard Hills
Lot and DP (title information)	Lot 43 DP 811320
Area (ha)	2.26 ha
Local Government Area (LGA)	Penrith City Council
Zoning	RU4 Rural Small Holdings
Current land use	Currently utilised by the Penrith United Church. Site comprised of: bitumen surfaced car parking areas and access driveways from Kingswood Road and Castle Road; an existing brick meeting hall building with amenities block; 2 sheds and a pump house; and lawn and landscaped areas (Attachment A).
Proposed land use	Continued use as church.
Surrounding land uses	Rural residential land to the north and east, Kingswood Road to the west and Castle Road to the south.
Geology and soil landscapes	<p>The Penrith 1:100,000 Soil Landscapes Sheet (1989) indicates the site lies on the Luddenham soil landscapes consisting of moderately deep red podzolic soils on upper slopes and moderately deep yellow podzolic soils and prairie soils on lower slopes and drainage lines.</p> <p>The Penrith 1:100,000 Geological Series (1987) indicates the site is formed on Bringelly Shale consisting of carbonaceous claystone, claystone, laminate, fine to medium grained lithic sandstone, rare coal and tuff.</p>
Drainage	According to the topographic map, a drainage depression traverses the north eastern corner of the site in a south easterly direction. A second drainage line is located to the south of the site and Castle Road. Both drainage lines contain several online farm dams.

An existing site plan is provided in Attachment A with survey details provided in Attachment D.

2.2 Site Investigations

Site investigations were undertaken on January 30, 2014 and included the following:

- Walkover inspection of the site to assess existing site conditions and local topography, geology, soil conditions and vegetation.
- Inspection of the existing OSWMS.
- Intrusive investigations (3 boreholes) for soil characterisation in area of existing and proposed effluent irrigation.

Plates of the site are provided in Attachment B.

2.3 Soil Profile

Intrusive soil investigations found the soil profile consisted of silt loam and clay loam to 0.6m below ground level (bgl) overlying light to medium clays to depths of 1.5 – 3.0m bgl.

Borehole logs are provided in Attachment C with borehole locations provided in Attachment A.

3 Existing Wastewater System Assessment

3.1 Overview

An assessment of the site's existing wastewater system has been undertaken to determine if upgrades are required in light of the proposed development. This assessment includes:

1. A description of the existing system's condition and treatment capacity.
2. An assessment of wastewater generation rates for the site.
3. Determination of suitability of the continued use of the system.

3.2 Existing Wastewater System Description

3.2.1 Treatment System

Wastewater generated onsite is from toilet flushing only as no kitchen or canteen facilities are provided. It is pumped to an onsite sewage treatment plant (STP) via a lift well with 2 macerator pumps located to the north east of the main building in the existing carpark (Attachment A).

The STP is located south of the main building (Attachment A). According to the manufacturer (J Pridham, February 13, 2014) the system is a Gebe! Aquasafe extended aeration unit with a capacity of 15 KL/day plus an additional 60KL wet weather storage tank (Attachment F). The treatment system includes tertiary filtration, UV sterilisation and chlorine dosing.

Site inspection of the STP showed it to be in good working order and well maintained. No leaks or odours were noted. Servicing records (April 2012 – October 2013) supplied by the client indicate the system is maintained quarterly by the manufacturer. No issues or incidents are noted on supplied servicing records.

3.2.2 Disposal System

Treated effluent was applied to a grassed irrigation field in the site's south (Attachment A) from 4 pop-up sprinklers. An alternative disposal system has since been installed as follows:

- A diverter was installed to direct all effluent to a new absorption trench.

- Absorption trench is approximately 6.0 m long and 0.5 m wide, constructed into medium clay beneath an earth bund (2.0 – 2.5 m wide and 1.0 – 1.5 m high) along the southern boundary.

We understand that no Council approval for the absorption system has been obtained and the system has not been sized and designed in accordance with AS/NZS 1547 (2012). General location of the absorption trench is provided in Attachment A.

3.3 Population and Wastewater Generation

Site population varies on a daily basis with Table 3 summarising population data provided by the client for a typical month. Data is also provided for occasions when conferences are held at the site (once every 3-6 months) and Sunday attendance increases to 1250 people.

Table 2: Site population summary.

Week	Mon	Tues	Wed	Thur	Fri	Sat	Sun	Average/day
1	50	300	450	0	0	0	500	186
2	50	300	0	400	0	450	50	179
3	50	300	450	0	0	0	850	186
4	50	300	450	0	300	450	500	293
Every 3-6 months	50	300	450	0	0	0	1250	293

A maximum daily average (based on a week) site population of 293 is adopted for this wastewater assessment. The proposed development does not intend to increase the site population – only the amenities available to them.

Given population fluctuation water usage rates were reviewed. According to the August 2013 – November 2013 quarter bill (Attachment E), average daily usage was 5.07 KL. This includes water which passes to the wastewater system (i.e. toilet flushing) and that used for landscape irrigation.

We understand that landscaped areas are irrigated using an automatic watering system running for 20 minutes, 4 days/week from a single tap. At an assumed irrigation rate of 20 L/min, irrigation uses 1.6 KL/week (0.23 KL/day). When subtracted from the total site water usage of 5.07 KL/day, the wastewater generation rate is calculated as 4.84 KL/day. This equates to a per person generation rate of 16.5 L/person/day using an average population of 293 people (Table 2). This rate is generally consistent with Table H4 of AS/NZS 1547 (2012) which provides a typical wastewater generation rate of 15 L/person/day for community meeting halls on reticulated water supply.

3.4 Wastewater System Suitability

3.4.1 Treatment System

The existing STP is, based on inspection by Martens, in good working order and well maintained. No leaks or odours were noted. Maintenance records from the last 18 months indicate no significant or ongoing issues with the system.

3.4.2 Disposal System

It is recommended that the existing disposal system be decommissioned and replaced with a new pump-out system (Section 4).

4 Wastewater Assessment

4.1 Overview

This assessment determines existing system modifications and requirements to ensure wastewater generated is appropriately treated and disposed. The existing STP is to be retained and treated effluent disposed via pump-out.

Our understanding is that Sydney Water intends to provide reticulated sewer to the area within the next 2 – 3 years. Our Client's preference is to pump-out wastewater effluent until a reticulated sewerage connection becomes available. This is considered to be in accordance with Penrith City Council (2014) and is also the most economical solution.

4.2 Design Hydraulic Load

The current wastewater generation rate is 4.84 KL/day (Section 3.3). This is not proposed to increase as a result of the proposed development.

4.3 Wet Weather Effluent Storage Tank

The existing effluent storage tank has a capacity of 60 kL. The system also contains a float switch and alarm system which automatically alerts site management when the system reaches 70% capacity.

4.4 Pump Out Frequency

Advice obtained from the Client indicates that the existing system pump-out contractor has a tanker capable of holding up to 22 kL of effluent. At projected wastewater generation rates, this means that the pump-out tanker will be required to pump-out the effluent wet weather storage tank every 4.8 days on average (twice a week).

A copy of a recent invoice from the current pump-out Contractor to the Client for previous system pump-out is provided in Attachment G.

4.5 Effluent Pump-out Location

Proposed pump-out system shall be located as shown in Attachment D. Advice from the Client indicates that the local pump-out Contractor currently servicing the site, stands the pump-out tanker adjacent to the existing STP (partially over the wet weather effluent storage tank) when pumping out the STP and wet weather storage tanks (when required).

We recommend that the tanker stand on the existing gravel driveway near to the STP and wet weather storage tank and that the pump-out

tanker be connected to a new 50 mm Camlock fitting adjacent to the gravel driveway.

4.6 Specific System Requirements

4.6.1 Secondary Treatment System

The existing STP is considered suitable for ongoing use as part of the proposed development.

4.6.2 Wet Weather Storage

The existing wet weather effluent storage tank is considered suitable for ongoing use as part of the proposed development. It provides 12 days storage at average flow. The existing float switch and alarm are to be maintained as per existing site operations.

4.6.3 Pump-out System

A new pump-out system is considered appropriate for the site as a temporary wastewater management solution, until such time as a reticulated sewer connection becomes available to the site. The pump-out system will require the following as a minimum:

- 50 mm Camlock fitting is to be installed as shown on the site plan in Attachment D. This is to allow the tanker to stand on the existing gravel driveway during pump-out.
- The Camlock fitting is to have a timber bollard installed adjacent for support and to prevent vehicles from colliding with and damaging the Camlock fitting.
- Supporting bollard is to have a "Cat's Eye" reflective marker on both sides of the bollard to prevent accidental collision during low light conditions.
- A new length of 50 mm diameter transfer main is to be fitted from the effluent wet weather storage tank to the Camlock fitting. Main may be UPVC or PE below the ground. Main is to be stainless steel above ground. Sub-surface pipe to be laid with minimum 450 mm cover in accordance with AS3500.2 (2003). Where this cannot be achieved, 50 mm of 10 -20 mm aggregate and then 75 mm of concrete is to be placed over the top of the main.
- A concrete thrust block shall be provided under the Camlock fitting as shown on the plan in Attachment D.

4.6.4 On-site Effluent Disposal Systems

All existing effluent disposal systems on the site are to be decommissioned. The existing irrigation system may be retained as an emergency system.

4.7 System Monitoring, Inspections and Maintenance

The pump-out system will require weekly visual inspection by the site owner / operator to identify any leaks within the transfer system or any issues with the Camlock fitting.

4.8 Summary

The system requirements for the proposed development is summarised as follows:

- Continued operation of existing STP.
- Continued operation of existing wet weather effluent storage tank located downstream of the STP.
- Existing absorption trench to be decommissioned.
- Pump-out system including new 50 mm Camlock fitting to be constructed adjacent to gravel driveway to allow tanker to stand on driveway during pump-out.
- Detailed design of the proposed system shall be completed at construction certificate stage.

4.9 Further Approvals

Prior to the construction of any new or modified site sewage management infrastructure, an approval under Section 68A of the Local Government Act (1993) will be required where final design specifications for the STP, effluent storage system and pump-out systems shall be submitted for approval to Council.

5 References

Australian / New Zealand Standard 1547 (2012), *Onsite domestic wastewater management*.

Australian / New Zealand Standard 3500.2 (2003) *Plumbing and Drainage Part 2: Sanitary plumbing and drainage*.

Department of Environment and Conservation (2004). *Environmental Guidelines-Use of effluent by Irrigation*.

Penrith City Council (2010), *Development Control Plan: Section 13.3 Onsite Sewage Management*.

Penrith City Council (2014) *On-site Sewage Management and Greywater Reuse Policy*.



N6

Attachment A – Site Plan

martens



● Borehole location

□ Site boundary

Martens & Associates Pty Ltd ABN 85 070 240 890		Environment Water Wastewater Geotechnical Civil Management	
Drawn:	MLK	Site Plan and Existing Wastewater System Layout	Drawing No:
Approved:	GT		ATTACHMENT A
Date:	15/04/2014		
Scale:	NA		Job No: P1404110

7 Attachment B – Figures



Plate 1: Lift station



Plate 2: STP tank and control shed



Plate 3: STP



Plate 4: Proposed irrigation field location. View facing north west.



Plate 5: Existing earth bund along southern boundary and absorption trench location. View facing east.



Plate 6: Existing earth bund along southern boundary. View facing west.

Martens & Associates Pty Ltd ABN 85 070 240 890		Environment Water Wastewater Geotechnical Civil Management	
Drawn:	MLK	Plates	Drawing No:
Approved:	GT		FIGURE 1
Date:	20/02/2014		
Scale:	NA		Job No: P1404110

8 Attachment C – Borehole Logs

CLIENT	Stimson Consultant Services			COMMENCED	30/01/14		COMPLETED	30/01/14		REF BH101							
PROJECT	Wastewater Assessment			LOGGED	GT		CHECKED	AN		Sheet 1 of 1							
SITE	26 Kingswood Road, Orchard Hills, NSW			GEOLOGY	Shale		VEGETATION	Grasses		PROJECT NO. P1404110							
EQUIPMENT		Hydraulic Auger			EASTING	NA		RL SURFACE		NA							
EXCAVATION DIMENSIONS		Ø100mm X 2.25m depth			NORTHING	NA		ASPECT		South East							
SLOPE									5-10%								
EXCAVATION DATA				MATERIAL DATA				SAMPLING & TESTING									
METHOD	SUPPORT	WATER	MOISTURE	DEPTH (M)	PENETRATION RESISTANCE	GRAPHIC LOG	CLASSIFICATION	DESCRIPTION OF STRATA Soil type, texture, structure, mottling, colour, plasticity, rocks, oxidation, particle characteristics, organics, secondary and minor components, fill, contamination, odour.		CONSISTENCY	DENSITY INDEX	TYPE	DEPTH (M)	RESULTS AND ADDITIONAL OBSERVATIONS			
V	Nil	N	D	0.25			SiL	SILT LOAM - Brown/red, smooth.				A	0.15	4110/101/ 0.15			
V	Nil	N	D	0.65			CL	CLAY LOAM - Orange/brown.				A	0.4	4110/101/ 0.4			
V	Nil	N	D	1.0			MC	MEDIUM CLAY - Gold/brown/grey, very hard drilling. - Slow V bit progression because possibly very low strength shale.				A	0.8	4110/101/ 0.8			
V	Nil	N	D	1.5								B	1.3	4110/101/ 1.3			
V	Nil	N	D	2.0			SC	SANDY CLAY - Brown/light brown, medium grained sands.				A	2.0	4110/101/ 2.0			
				2.25				V bit Auger refusal at 2.25m on bedrock.									
				3.0													
				4.0													
				4.5													
EQUIPMENT / METHOD		SUPPORT		WATER		MOISTURE		PENETRATION		CONSISTENCY		DENSITY		SAMPLING & TESTING		CLASSIFICATION SYMBOLS AND SOIL DESCRIPTION	
N Natural exposure		SH Shoring		N None observed		D Dry		L Low		VS Very Soft		VL Very Loose		A Auger sample		pp Pocket penetrometer	
X Existing excavation		SC Shotcrete		X Not measured		M Moist		M Moderate		S Soft		L Loose		B Bulk sample		S Standard penetration test	
BH Backhoe bucket		RB Rock Bolts		Water level		W Wet		H High		F Firm		MD Medium Dense		U Undisturbed sample		VS Vane shear	
E Excavator		Nil No support		Water outflow		Wp Plastic limit		R Refusal		St Stiff		D Dense		D Disturbed sample		DCP Dynamic cone	
HA Hand auger				Water inflow		Wl Liquid limit				VSt Very Stiff		VD Very Dense		M Moisture content		FD Field density	
S Hand spade										H Hard				Ux Tube sample (x mm)		WS Water sample	
A Auger										F Friable				G Gas			
TC Tungsten Carbide Bit																	
V V-Bit																	
EXCAVATION LOG TO BE READ IN CONJUNCTION WITH ACCOMPANYING REPORT NOTES AND ABBREVIATIONS																	
MARTENS & ASSOCIATES PTY LTD 6/37 Leighton Place Hornsby, NSW 2077 Australia Phone: (02) 9476 9999 Fax: (02) 9476 8767 mail@martens.com.au WEB: http://www.martens.com.au																	
Engineering Log - Borehole																	

CLIENT	Stimson Consultant Services			COMMENCED	30/01/14	COMPLETED	30/01/14		REF BH102				
PROJECT	Wastewater Assessment			LOGGED	GT	CHECKED	AN		Sheet 1 of 1				
SITE	26 Kingswood Road, Orchard Hills, NSW			GEOLOGY	Shale	VEGETATION	Grasses		PROJECT NO. P1404110				
EQUIPMENT	Hydraulic Auger			EASTING	NA	RL SURFACE	NA						
EXCAVATION DIMENSIONS	Ø100mm X 2.5m depth			NORTHING	NA	ASPECT	South West		SLOPE	5-10%			
EXCAVATION DATA				MATERIAL DATA				SAMPLING & TESTING					
METHOD	SUPPORT	WATER	MOISTURE	DEPTH (M)	PENETRATION RESISTANCE	GRAPHIC LOG	CLASSIFICATION	DESCRIPTION OF STRATA	CONSISTENCY	DENSITY INDEX	TYPE	DEPTH (M)	RESULTS AND ADDITIONAL OBSERVATIONS
Soil type, texture, structure, mottling, colour, plasticity, rocks, oxidation, particle characteristics, organics, secondary and minor components, fill, contamination, odour.													
V	Nil	N	D	0.2			SiL	SILT LOAM - Brown/red, smooth.					
V	Nil	N	D	0.6			CL	CLAY LOAM - Brown/red, minor gravels (1-5mm, ≈5%).			A	0.5	4110/102/ 0.5
V	Nil	N	D	1.0			LMC	LIGHT MEDIUM CLAY - Grey/brown/gold mottled, moderately plastic.			A	1.5	4110/102/ 1.5
V	Nil	N	D	1.5			MC	MEDIUM CLAY - Brown/gold, with minor gravels (1-5mm, ≈10%), possibly very low strength shale.			A	2.3	4110/102/ 2.3
				2.0				Borehole refusal at 2.5m on bedrock.					
				2.5									
				3.0									
				4.0									
				4.5									
EQUIPMENT / METHOD N Natural exposure X Existing excavation BH Backhoe bucket E Excavator HA Hand auger S Hand spade A Auger TC Tungsten Carbide Bit V V-Bit													
SUPPORT SH Shoring SC Shotcrete RB Rock Bolts Nil No support													
WATER N None observed X Not measured Water level Water outflow Water inflow													
MOISTURE D Dry M Moist W Wet Wp Plastic limit Wl Liquid limit													
PENETRATION L Low M Moderate H High R Refusal													
CONSISTENCY VS Very Soft S Soft F Firm St Stiff VSt Very Stiff H Hard F Friable													
DENSITY VL Very Loose L Loose MD Medium Dense D Dense VD Very Dense													
SAMPLING & TESTING A Auger sample B Bulk sample U Undisturbed sample D Disturbed sample M Moisture content Ux Tube sample (x mm) G Gas													
CLASSIFICATION SYMBOLS AND SOIL DESCRIPTION N USCS Y Agricultural													
EXCAVATION LOG TO BE READ IN CONJUNCTION WITH ACCOMPANYING REPORT NOTES AND ABBREVIATIONS													
MARTENS & ASSOCIATES PTY LTD 6/37 Leighton Place Hornsby, NSW 2077 Australia Phone: (02) 9476 9999 Fax: (02) 9476 8767 mail@martens.com.au WEB: http://www.martens.com.au													
Engineering Log - Borehole													

CLIENT		Stimson Consultant Services		COMMENCED	30/01/14	COMPLETED	30/01/14	REF BH103	
PROJECT		Wastewater Assessment		LOGGED	GT	CHECKED	AN	Sheet 1 of 1	
SITE		26 Kingswood Road, Orchard Hills, NSW		GEOLOGY	Shale	VEGETATION	Grasses	PROJECT NO. P1404110	
EQUIPMENT		Hydraulic Auger		EASTING	NA	RL SURFACE	NA		
EXCAVATION DIMENSIONS		Ø100mm X 3.0m depth		NORTHING	NA	ASPECT	South West	SLOPE	3-5%

EXCAVATION DATA				MATERIAL DATA				SAMPLING & TESTING					
METHOD	SUPPORT	WATER	MOISTURE	DEPTH (M)	PENETRATION RESISTANCE	GRAPHIC LOG	CLASSIFICATION	DESCRIPTION OF STRATA	CONSISTENCY	DENSITY INDEX	TYPE	DEPTH (M)	RESULTS AND ADDITIONAL OBSERVATIONS
V	Nil	N	D	0.2			SiL	SILT LOAM - Brown/red, smooth.			A	0.1	4110/103/ 0.1
V	Nil	N	D	0.7			CL	CLAY LOAM - Orange/brown.					
V	Nil	N	M	1.0			LMC	LIGHT MEDIUM CLAY - Grey with minor brown mottled, moderately plastic.			A	1.0	4110/103/ 1.0
V	Nil	N	D	2.0			MC	MEDIUM CLAY - Grey/orange/gold mottled, moderately plastic.			A	2.0	4110/103/ 2.0
				3.0				Borehole terminated at 3.0m on medium clays.					
				4.0									
				4.5									

EQUIPMENT / METHOD
N Natural exposure
X Existing excavation
BH Backhoe bucket
E Excavator
HA Hand auger
S Hand spade
A Auger
TC Tungsten Carbide Bit
V V-Bit

SUPPORT
SH Shoring
SC Shotcrete
RB Rock Bolts
Nil No support

WATER
N None observed
X Not measured
Water level
Water outflow
Water inflow

MOISTURE
D Dry
M Moist
W Wet
Wp Plastic limit
Wl Liquid limit

PENETRATION
L Low
M Moderate
H High
R Refusal

CONSISTENCY
VS Very Soft
S Soft
F Firm
St Stiff
VSt Very Stiff
H Hard
F Friable

DENSITY
VL Very Loose
L Loose
MD Medium Dense
D Dense
VD Very Dense

SAMPLING & TESTING
A Auger sample
B Bulk sample
U Undisturbed sample
D Disturbed sample
M Moisture content
Ux Tube sample (x mm)
G Gas

pp Pocket penetrometer
S Standard penetration test
VS Vane shear
DCP Dynamic cone penetrometer
FD Field density
WS Water sample

CLASSIFICATION SYMBOLS AND SOIL DESCRIPTION
N USCS
Y Agricultural



EXCAVATION LOG TO BE READ IN CONJUNCTION WITH ACCOMPANYING REPORT NOTES AND ABBREVIATIONS

Document Set No. 1407809

MARTENS & ASSOCIATES PTY LTD
6/37 Leighton Place
Hornsby, NSW 2077 Australia
Phone: (02) 9476 9999 Fax: (02) 9476 8767
mail@martens.com.au WEB: http://www.martens.com.au

Engineering Log - Borehole


10 **Attachment D - Wastewater Management Plan**



TYPICAL CONCRETE THRUST BLOCK AND CAMLOCK FITTING DETAIL (NOT TO SCALE)

- KEY
- WASTEWATER BUFFER
 - . - STORMWATER DIVERSION BUND
 - WET WEATHER STORAGE (60 KL)

NOTE:
SITE CONTOURS SUPPLIED BY STIMSON CONSULTANT SERVICES
CONTOURS DO NOT INCLUDE EXISTING EARTH BUND ALONG WESTERN AND SOUTHERN BOUNDARIES



Martens & Associates Pty Ltd		ABN 85 070 240 890	Environment Water Wastewater Geotechnical Civil Management				
Drawn:	MLK		WASTEWATER MANAGEMENT PLAN AND CAMLOCK DETAIL		Drawing No./ID:		
Approved:	GT				SK001		
Date:	02.11.2016						
Scale @A3:	1:1000		6/37 Leighton Place, Hornsby, NSW 2077 Australia Phone: (02) 9476 9999 Fax: (02) 9476 8767 Email: mail@martens.com.au Internet: http://www.martens.com.au		Project: P1404110	File: JD02V04	Revision: A

11 Attachment E – Sydney Water Usage Rates

Last bill	Payments	Balance	This bill	Total amount due
\$960.45	\$960.45	\$0.00	\$1044.95	\$1044.95



DJ ARKCOLL, JA GREENE, JS JOYCE,
 MR GJ OVENDEN, MR JI THORNCROFT
 C/- PENRITH GOSPEL TRUST
 PO BOX 664
 PENRITH NSW 2751

45940950-1071

Please pay by

09/12/13

Account number

4594 095

Account for property

26 Kingswood Rd Orchard Hills

Fixed charges - GST free	1 Oct 13 - 31 Dec 13	\$
Water service		137.79

Usage charges - GST free	12 Aug 13 - 15 Nov 13	
Water	482 kL at \$2.1680 a kL	1044.97


See over for details

Other charges and credits

Exempt fixed charges credit	-137.79
Credit	-0.02

Your average daily usage

Total amount due \$1044.95



How much water did you use?

Goods Rec'd: _____
 Price/Coles: _____
 Approved: _____
 Cheque No: _____
 Date Paid: _____

N112938350388
 Continued overleaf

SYDNEY WATER CORPORATION ABN 49 776 225 038

TAX INVOICE

Date of issue 18 November 2013

Account for 26 Kingswood Rd Orchard Hills



*242 4594 095 0004

POSTbillpay: Use cash, cheque or debit card at any Australia Post Office.

Credit card limit:
\$1,000 per bill

Payment number

4594 095 0004

Please pay by

09/12/13

Total amount due

\$1044.95



BPAY: Internet or phone banking.
 Biller code: 45435 Ref no.: 4594 095 0004



Mail payments: Return slip and cheque payable to Sydney Water (no staples).

Send to:
 Sydney Water
 PO Box 339
 Silverwater NSW 2128



Telephone payments: Mastercard or Visa.
 Call **1300 12 34 58** (24 hour service)



Direct debit payments: For more information, please call 13 20 92 or visit sydneywater.com.au



Internet payments: Mastercard or Visa:
sydneywater.com.au

TRAN CODE USER CODE CUSTOMER REFERENCE NUMBER

831

066859

00004594 095 0004

Account for property**26 Kingswood Rd Orchard Hills****Water meter details****Meter Reading Period:** 12 Aug 13 - 15 Nov 13

Meter No.	This Reading	Last Reading	Consumption (kL)
EDYE0128	3152	2670	482

Total water used in 95 days was 482 kilolitres

Customer information

- * Visit sydneywater.com.au to view the Sydney Water Customer Contract in Brief.
- * If you are having difficulty paying your bill, we can help. We have flexible payment options to help you plan your payments. We may offer payment extensions or a regular payment arrangement. **Call us on 13 20 92.**
- * Direct Debit by credit card - now available. Register at sydneywater.com.au
- * Interest may be charged on overdue amounts at the current rate of 6.50% a year.
- * Hearing impaired customers can phone via NRS for a TTY service on **13 36 77**, quoting **13 20 90**.
- * We may exchange contact information with local councils to ensure your bills get to you.

Faults and Leaks (available 24 hours)

Please ring 13 20 90 in cases of service difficulty and emergency.

**Payment number****Total amount due****4594 095 0004****\$1044.95****Changing your mailing address?**

For changes to your mailing address, please ring general enquiries or visit sydneywater.com.au/SW/accounts-billing/ to change your address online.



Centrepay payments: call Centrelink to arrange regular Centrepay deductions.
Centrepay Reference No.: 555 052 086C

Interpreter Service 13 14 50**Arabic • Chinese • Greek • Italian • Korean • Vietnamese**

إذا كنت تحتاج إلى مترجم، يرجى الاتصال بالرقم أعلاه.

如果您需要傳譯員的協助，請致電以上的號碼。


Αν χρειάζεστε διερμηνέα, τηλεφωνήστε στον παραπάνω αριθμό.

Se vi serve un interprete, telefonate al numero indicato sopra.

통역사가 필요하시면 위의 번호로 전화하십시오.

Nếu quý vị cần thông dịch viên, hãy gọi đến số trên đây.

12 Attachment F – Existing Wastewater Treatment System Design (GEBEL, 2014)



CLIENT: PENRITH GOSPEL TRUST	ISSUE FOR APPROVAL :	CONFIDENTIAL – The drawings must not be disclosed to any third parties without written permission from GEBEL Sydney. Unauthorised disclosure may result in prosecution. © GEBEL– This drawing is the property of ABN : 32 186 023 552 and is subject to return on demand. It is submitted for the use only in connection with the proposal and contracts of GEBEL with the expressed conditions that it is not to be reproduced or copied in any form. This data must only be used in accordance with our standard terms and conditions. © Copyright GEBEL accepts no responsibility for any loss or damage resulting from any person acting on this information. The details and dimensions contained in this document may change, please check with GEBEL for confirmation of current specifications.	Drawn:	Date:	Title: Proposed Effluent Treatment Plant For Penrith Gospel trust–Lot43 Kingswood Rd Orchard Hills			
			M.T	7.10.14				
			Checked:	Date:				
			A.P	7.10.14				
			Verified:	Date:				
Approved:	Date:	Dig.Add.						
					Code:	Size:A3		
					Scale: N.T.S	Drawing No: GA1516-PGT-01	Sheet:1	Rev:1

13 Attachment G – Pump-out Contractor Invoice

ACN 070 120 928
ABN 68 070 120 928




P.O. Box 166, St Marys NSW 1790
P: 02 9623 1177
F: 02 9623 1002
www.brandsterservices.com.au

Penrith Gospel Trust
PO Box 584
PENRITH NSW 2751

TAX INVOICE

Invoice **S78178**
Date: 24/05/2016
Page: 1

Description	Amount	Tax
Pump out sullage as directed and transfer to Brandster Services Waste Facility at St Marys		
26 Kingswood Rd Orchard Hills		
D/N - S78177 / S78178 / S78421		
BS9825 / BS9816 - Pumped out 1 x Tank Removed a total of 60,000 Litres of liquids @ 5 cents per litre	\$3,000.00	GST



Your Order #: Terms: **C.O.D.**

MEMO 0438 017 166

Direct Deposits or EFT Deposits
Bank ANZ , BSB 012 408 Account 900317038

SALE AMOUNT	\$3,000.00
Freight:	\$0.00
GST:	\$300.00
Total Inc GST:	\$3,300.00
Amount Applied:	\$0.00
Balance Due:	\$3,300.00

ACN 070 120 928
ABN 68 070 120 928



P.O. Box 166, St Marys NSW 1790
P: 02 9623 1177
F: 02 9623 1002
www.brandsterservices.com.au

Penrith Gospel Trust
PO Box 584
PENRITH NSW 2751

TAX INVOICE

Invoice **S81187**

Date: 12/09/2016

Page: 1

Description	Amount	Tax
Penrit Gospel Trust Site - 26 Kingswood RD Orchard Hills D/N - S81187 BS9814 - Pumped out 1 x Tank Removed 22,000 ltrs @ 5 cents per ltr	\$1,100.00	GST
D/N - S81188 BS9814 - Pumped out 1 x Tank Removed 22,000 ltrs @ 5 cents per ltr	\$1,100.00	GST

Goods Rec'd	
Price/Cator	2
Approved	3
Cheque No	EFT
Date Paid	30/9/16

Your Order #:	S81187/188	Terms:	C.O.D.	SALE AMOUNT	\$2,200.00
MEMO	0438 017 166			Freight:	\$0.00
				GST:	\$220.00
				Total Inc GST:	\$2,420.00
Direct Deposits or EFT Deposits				Amount Applied:	\$0.00
Bank ANZ , BSB 012 408 Account 900317038				Balance Due:	\$2,420.00

*Vacuum Tankers for Domestic & Industrial Liquid Waste
Treatment Facility for Septic, Sullage, Oily Waters, Storm Waters, Ground Waters*