

PENRITH CITY COUNCIL

NOTICE OF DETERMINATION

DESCRIPTION OF DEVELOPMENT

Application number:	DA16/0211.02
Description of development:	Modification to an Approved Demolition of Existing Structures and Construction of 14 x Town Houses and Associated Works - Amendment to Correct Property Details in Land Description of the Notice of Determination
Classification of development:	Class 1a

DETAILS OF THE LAND TO BE DEVELOPED

Legal description:	Lot 6 DP 28248 Lot 165 DP 1573 Lot 5 DP 28248
Property address:	86 Reid Street, WERRINGTON NSW 2747 88 Reid Street, WERRINGTON NSW 2747

DETAILS OF THE APPLICANT

Name & Address:	Gloza Pty Ltd 19 Jezebel Street THE PONDS NSW 2769
-----------------	--

DECISION OF CONSENT AUTHORITY

In accordance with Sections 4.18(1) and 4.55 of the Environmental Planning and Assessment Act 1979, consent is granted subject to the conditions listed in attachment 1.

Please note that this consent will lapse on the expiry date unless the development has commenced in that time.

Date from which consent operates	3 July 2017
Date the consent expires	3 July 2019
Date of this decision	27 June 2017 as amended on 5 November 2018 under Section 96 of the Environmental Planning and Assessment Act.

POINT OF CONTACT

If you have any questions regarding this determination you should contact:

Assessing Officer:	Gavin Cherry
Contact telephone number:	+612 4732 8125

NOTES

Reasons

The conditions in the attached schedule have been imposed in accordance with Section 80A of the Environmental Planning and Assessment Act 1979 as amended.

Conditions

Your attention is drawn to the attached conditions of consent in attachment 1.

Certification and advisory notes

You should also check if this type of development requires a construction certificate in addition to this development consent

It is recommended that you read any Advisory Note enclosed with this notice of determination.

Review of determination

The applicant may request Council to review its determination pursuant to Section 82A of the Environmental Planning and Assessment Act 1979 within 6 months of receiving this Notice of Determination.

You cannot make this request if the development is Designated Development, Integrated Development or State Significant development or if the application was decided by Sydney West Planning Panel.

Appeals in the Land and Environment Court

The applicant can appeal against this decision in the Land and Environment Court within six (6) months of receiving this Notice of Determination.

You cannot appeal if a Commission of Inquiry was held for the subject development application, or if the development is a State Significant Development.

An appeal to the Land and Environment Court is made by lodging an application to the Court in accordance with the Rules of the Court.

Designated development

If the application was for designated development and a written objection was made in respect to the application, the objector can appeal against this decision to the Land and Environment Court within 28 days after the date of this notice. The objector cannot appeal if a Commission of Inquiry was held.

If the applicant appeals against this decision, objector(s) will be given a notice of the appeal and the objector(s) can apply to the Land and Environment Court within 28 days after the date of this appeal notice to attend the appeal and make submissions at that appeal.

Sydney West Planning Panels

If the application was decided by the Sydney West Planning Panel, please refer to Section 18 of the Greater Sydney Commission Act 2015 and Section 23H of the Environmental Planning and Assessment Act, 1979 (as amended) for any further regulations.

ATTACHMENT 1: CONDITIONS OF CONSENT

General

- 1 The development must be implemented substantially in accordance with the following plans stamped approved by Council, the application form, the BASIX Certificate No. 706430M and any supporting information received with the application, except as may be amended in red on the attached plans and by the following conditions.

Drawing Title	Drawing No.	Prepared By	Dated
Architectural Plans	1232.DA01A - DA05A	N. F. Billyard	06/03/2017
Landscape Plan	1648LAN2A (Sheets 1 - 3)	Bio Engineered Solutions P/L	24/02/2016
Civil Drawings	1860 C00 - C12	Leading Engineers	03/03/2017
Stormwater Drainage Plan	D15233 (ST01 & ST02)	Danmor Consulting Engineers	10/02/2016
External Colour Schedule	-	-	-
Waste Management Plan	-	-	1/03/2016

- 2 The work must be carried out in accordance with the requirements of the Building Code of Australia. If the work relates to a residential building and is valued in excess of \$20,000, then a contract of insurance for the residential development shall be in force in accordance with Part 6 of the Home Building Act 1989.

{Note: Residential building includes alterations and additions to a dwelling, and structures associated with a dwelling house/dwelling such as a carport, garage, shed, rural shed, swimming pool and the like}.

- 3 All construction works shall be in accordance with Penrith Development Control Plan-Residential Construction Works.
- 4 **The development shall not be used or occupied until an Occupation Certificate has been issued.**
- 5 Exterior lighting shall be located and directed in such a manner so as not to create a nuisance to surrounding landuses. The lighting shall be the minimum level of illumination necessary for safe operation. The lighting shall be in accordance with AS 4282 "Control of the obtrusive effects of outdoor lighting" (1997).
- 6
Prior to the issue of a Construction Certificate, the plans are to be amended to incorporate the recommendations of the Bushfire Risk Assessment (Ref 88Rei-01), prepared by Bushfire Consultancy Australia and dated 22 February 2016.
- 7 A **Construction Certificate** shall be obtained prior to commencement of any building works.
- 8 All boundary fences are to be 1.8m high colorbond fence, unless an alternate material is agreed to with the affected property owner. All fencing is to be at the expense of the developer.
- 9 As per the plans marked in red, fencing forward of the building line shall not be constructed on metal panels and is to be of open style design.

Demolition

- 10 All demolition works are to be conducted in accordance with the provisions of AS 2601-1991 "The Demolition of Structures". **Prior to demolition**, all services shall be suitably disconnected and capped off or sealed to the satisfaction of the relevant service authority requirements.

All demolition and excavated material shall be disposed of at a Council approved site or waste facility. Details of the proposed disposal location(s) of all excavated material from the development site shall be provided to the Principal Certifying Authority **prior to commencement of demolition**.

- 11 You should read Council's Fact Sheet titled "Handling and Disposal of Fibrous Cement Products" **before any demolition works commence on the site**.

Prior to commencement of demolition works on site, a portaloo with appropriate washing facilities shall be located on the site and the Principal Certifying Authority is to be satisfied that:

- Measures are in place so as to comply with the WorkCover Authority's "Short Guide to Working with Asbestos Cement" and
- The person employed to undertake the works is a licensed asbestos removal contractor and is holder of a current WorkCover Asbestos Licence.

Any demolition works involving the removal of all asbestos shall only be carried out by a licensed asbestos removal contractor who has a current WorkCover Asbestos Licence.

All asbestos laden waste, including asbestos cement flat and corrugated sheeting must be disposed of at a tipping facility licensed by the Environmental Protection Authority to receive asbestos wastes.

- 12 Dust suppression techniques are to be employed during demolition to reduce any potential nuisances to surrounding properties.

- 13 Mud and soil from vehicular movements to and from the site must not be deposited on the road.

- 14 Demolition works will be restricted to the following hours in accordance with the NSW Environment Protection Authority Noise Control Guidelines:

- Mondays to Fridays, 7am to 6pm
- Saturdays, 7am to 1pm (if inaudible on neighbouring residential premises), otherwise 8am to 1pm
- No demolition work is permitted on Sundays and Public Holidays.

In the event that the demolition relates to works inside the building and do not involve external walls or the roof, and do not involve the use of equipment that emits noise then the demolition works are not restricted to the hours stated above.

The provisions of the Protection of the Environment Operations Act, 1997 in regulating offensive noise also apply to all construction works.

Environmental Matters

- 15 Erosion and sediment control measures shall be installed **prior to the commencement of works on site** including approved clearing of site vegetation. The erosion and sediment control measures are to be maintained in accordance with the approved erosion and sediment control plan(s) for the development and the Department of Housing's "Managing Urban Stormwater: Soils and Construction" 2004.

(Note: To obtain a copy of the publication, you should contact Landcom on (02) 98418600).

- 16 No fill material is to be imported to the site without the prior approval of Penrith City Council in accordance with Sydney Regional Environmental Plan No.20 (Hawkesbury- Nepean River) (No.2-1997). No recycling of material for use as fill material shall be carried out on the site without the prior approval of Council.

- 17 No fill material shall be imported to the site until such time as a Validation Certificate(with a copy of any report forming the basis for the validation) for the fill material has been submitted to, considered and approved by Council. The Validation Certificate shall:
- state the legal property description of the fill material source site,
 - be prepared by an appropriately qualified person (as defined in Penrith Contaminated Land Development Control Plan) with consideration of all relevant guidelines (e.g. EPA, ANZECC, NH&MRC), standards, planning instruments and legislation,
 - clearly indicate the legal property description of the fill material source site,
 - provide details of the volume of fill material to be used in the filling operations,
 - provide a classification of the fill material to be imported to the site in accordance with the Environment Protection Authority's "Environmental Guidelines: Assessment, Classification & Management of Non-Liquid Wastes" 1997, and
 - (based on the fill classification) determine whether the fill material is suitable for its intended purpose and land use and whether the fill material will or will not pose an unacceptable risk to human health or the environment.

{Note: Penrith Contaminated Land Development Control Plan defines an appropriately qualified person as "a person who, in the opinion of Council, has a demonstrated experience, or access to experience in hydrology, environmental chemistry, soil science, eco-toxicology, sampling and analytical procedures, risk evaluation and remediation technologies. In addition, the person will be required to have appropriate professional indemnity and public risk insurance."}.

If the Principal Certifying Authority or Penrith City Council is not satisfied that suitable fill materials have been used on the site, further site investigations or remediation works may be requested. In these circumstances the works shall be carried out prior to any further approved works.

- 18 All waste materials stored on-site are to be contained within a designated area such as a waste bay or bin to ensure that no waste materials are allowed to enter the stormwater system or neighbouring properties. The designated waste storage areas shall provide at least two waste bays / bins so as to allow for the separation of wastes, and are to be fully enclosed when the site is unattended.
- 19 All excavated material and other wastes generated as a result of the development are to be re-used, recycled or disposed of in accordance with the approved waste management plan.

Waste materials not specified in the approved waste management plan are to be disposed of at a lawful waste management facility. Where the disposal location or waste materials have not been identified in the waste management plan, details shall be provided to the Certifying Authority as part of the waste

management documentation accompanying the Construction Certificate application.

All receipts and supporting documentation must be retained in order to verify lawful disposal of materials and are to be made available to Penrith City Council on request.

- 20 The operating noise level of plant and equipment shall not exceed 5dB(A) above the background noise level when measured at the boundaries of the premises. The provisions of the Protection of the Environment Operations Act 1997 apply to the development, in terms of regulating offensive noise.
- 21 Only clean and unpolluted water is to be discharged into Penrith City Council's stormwater drainage system. Liquid wastes suitable for discharge to the mains sewer are to be discharged in accordance with Sydney Water requirements.

If mains sewer is not available or if Sydney Water will not allow disposal to the sewer then a licensed waste contractor is to remove the liquid waste from the premises to an appropriate waste facility.

The waste contractor and waste facility are to hold the relevant licenses issued by the NSW Environment Protection Authority.

- 22 Bulky Waste Room is to remain open and unobstructed at the rear and at the entrance.

23 Indemnity Agreement

Prior to the issue of any OC, the developer is to enter into a formal agreement with Penrith City Council for the utilization of Council's Waste Collection Service. This is to include Council being provided with indemnity against claims for loss or damage.

Note: By entering into an agreement with Council for waste collection, the development will be required to operate in full compliance with Penrith City Council's Waste collection and Processing Contracts for Standard Waste Collection. The provision of Council's waste collection service will not commence until formalisation of the agreement.

The document can be downloaded from the following link below:

<https://www.penrithcity.nsw.gov.au/Building-and-Development/Development-Applications/Forms/>

BCA Issues

- 24 All aspects of the building design shall comply with the applicable performance requirements of the Building Code of Australia so as to achieve and maintain acceptable standards of structural sufficiency, safety (including fire safety), health and amenity for the on-going benefit of the community. Compliance with the performance requirements can only be achieved by:
- (a) complying with the deemed to satisfy provisions, or
 - (b) formulating an alternative solution which:
 - complies with the performance requirements, or
 - is shown to be at least equivalent to the deemed to satisfy provision, or
 - (c) a combination of (a) and (b).

Utility Services

- 25 A Section 73 Compliance Certificate under the Sydney Water Act 1994 shall be obtained from Sydney Water. The application must be made through an authorised Water Servicing Coordinator. Please refer to “Your Business” section of Sydney Water’s website at www.sydneywater.com.au then the “e-developer” icon, or telephone 13 20 92.

Note: It is recommended that the applicant contact Sydney Water or the relevant water services coordinator to discuss requirements outlined within the Sydney Water Feasibility Letter (Case No. 157510) prior to the issue of a construction certificate. This is to ensure that all necessary infrastructure works or upgrades are considered and addressed in the preparation of civil design drawings.

The Section 73 Compliance Certificate must be submitted to the Principal Certifying Authority before an Occupation Certificate is issued for the development.

- 26 Prior to the issue of a Construction Certificate, a written clearance is to be obtained from Endeavour Energy stating that electrical services have been made available to the development or that arrangements have been entered into for the provision of services to the development.

In the event that a pad mounted substation is necessary to service the development, Penrith City Council shall be consulted over the proposed location of the substation before the Construction Certificate for the development is issued as the location of the substation may impact on other services and building, driveway or landscape design already approved by Council.

- 27 **Prior to the issue of a Construction Certificate**, the Principal Certifying Authority shall be satisfied that telecommunications infrastructure may be installed to service the premises which complies with the following:
- The requirements of the Telecommunications Act 1997;
 - For a fibre ready facility, the NBN Co’s standard specifications current at the time of installation; and
 - For a line that is to connect a lot to telecommunications infrastructure external to the premises, the line shall be located underground.

Unless otherwise stipulated by telecommunications legislation at the time of construction, the development must be provided with all necessary pits and pipes, and conduits to accommodate the future connection of optic fibre technology telecommunications.

Prior to the issue of an Occupation Certificate, written certification from all relevant service providers that the telecommunications infrastructure is installed in accordance with the requirements above and the applicable legislation at the time of construction, must be submitted to the Principal Certifying Authority.

Construction

28 Stamped plans, specifications, a copy of the development consent, the Construction Certificate and any other Certificates to be relied upon shall be available on site at all times during construction.

The following details are to be displayed in a maximum of 2 signs to be erected on the site:

- the name of the Principal Certifying Authority, their address and telephone number,
- the name of the person in charge of the work site and telephone number at which that person may be contacted during work hours,
- that unauthorised entry to the work site is prohibited,
- the designated waste storage area must be covered when the site is unattended, and
- all sediment and erosion control measures shall be fully maintained until completion of the construction phase.

Signage but no more than 2 signs stating the above details are to be erected:

- at the commencement of, and for the full length of the, construction works onsite, and
- in a prominent position on the work site and in a manner that can be easily read by pedestrian traffic.

All construction signage is to be removed when the Occupation Certificate has been issued for the development.

29 Prior to the commencement of construction works:

(a) Toilet facilities at or in the vicinity of the work site shall be provided at the rate of one toilet for every 20 persons or part of 20 persons employed at the site. Each toilet provided must be:

- a standard flushing toilet connected to a public sewer, or
- if that is not practicable, an accredited sewage management facility approved by the council, or
- alternatively, any other sewage management facility approved by council.

(b) All excavations and backfilling associated with the erection or demolition of a building must be executed safely and in accordance with the appropriate professional standards. All excavations associated with the erection or demolition of a building must be properly guarded and protected to prevent them from being dangerous to life or property.

(c) If an excavation associated with the erection or demolition of a building extends below the level of the base of the footings of a building on an adjoining allotment of land, the person causing the excavation to be made:

- must preserve and protect the building from damage, and
- if necessary, must underpin and support the building in an approved manner, and
- must, at least 7 days before excavating below the level of the base of the footings of a building on an adjoining allotment of land, give notice of intention to do so to the owner of the adjoining allotment of land and furnish particulars of the excavation to the owner of the building being erected or demolished. The owner of the adjoining allotment of land is not liable for any part of the cost of work carried out for the purposes of this condition, whether carried out on the allotment of land being excavated or on the adjoining allotment of land, (includes a public road and any other public place).

(d) If the work involved in the erection or demolition of a building is likely to cause pedestrian or vehicular traffic in a public place to be obstructed or rendered inconvenient, or involves the enclosure of a public place, hoarding or fence must be erected between the work site and the public place:

- if necessary, an awning is to be erected, sufficient to prevent any substance from, or in connection with, the work falling into the public place,
- the work site must be kept lit between sunset and sunrise if it is likely to be hazardous to persons in the public place, and
- any such hoarding, fence or awning is to be removed when the work has been completed.

30 Clothes drying facilities are to be positioned and screened from public view.

31 Construction works or subdivision works that are carried out in accordance with an approved consent that involve the use of heavy vehicles, heavy machinery and other equipment likely to cause offence to adjoining properties shall be restricted to the following hours in accordance with the NSW Environment Protection Authority Noise Control Guidelines:

- Mondays to Fridays, 7am to 6pm
- Saturdays, 7am to 1pm (if inaudible on neighbouring residential premises), otherwise 8am to 1pm
- No work is permitted on Sundays and Public Holidays.

Other construction works carried out inside a building/tenancy and do not involve the use of equipment that emits noise are not restricted to the construction hours stated above.

The provisions of the Protection of the Environment Operations Act, 1997 in regulating offensive noise also apply to all construction works.

Engineering

- 32 All roadworks, stormwater drainage works, associated civil works and dedications, required to effect the consented development shall be undertaken at no cost to Penrith City Council.
- 33 An Infrastructure Restoration Bond is to be lodged with Penrith City Council for development involving works around Penrith City Council's Public Infrastructure Assets. The bond is to be lodged with Penrith City Council prior to the issue of any Construction Certificate. The bond and applicable fees are in accordance with Council's adopted Fees and Charges.

An application form together with an information sheet and conditions are available on Council's website.

Contact Penrith City Council's City Works Department on (02) 4732 7777 or visit Penrith City Council's website for more information.

- 34 Prior to the issue of any Construction Certificate, the Certifying Authority shall ensure that a Section 138 Roads Act application, including payment of application and inspection fees, has been lodged with, and approved by Penrith City Council (being the Roads Authority under the Roads Act), for provision of (bulk earthworks, road widening and drainage works) in (Reid Street, Werrington)

Engineering plans are to be prepared generally in accordance with civil plans, Project No: 1860, Revision up to C, Dated 03/03/2017, prepared by Leading Engineers.

A minimum 1:8 temporary asphalt kerbing to taper on eastern adjacent land shall be provided. Any pavement widening must join neatly to the existing pavement according to Council's Guidelines for Engineering Works.

Engineering plans are to be prepared in accordance with the development consent, Penrith City Council's Design Guidelines for Engineering Works for Subdivisions and Developments, Engineering Construction Specification for Civil Works, Austroads Guidelines, and best engineering practice.

Contact Penrith City Council's Development Engineering Department on (02) 4732 7777 or visit Penrith City Council's website for more information.

Note:

- a) Where Penrith City Council is the Certifying Authority for the development the Roads Act approval for the above works may be issued concurrently with the Construction Certificate.
 - c) All works associated with the Roads Act approval must be completed prior to the issue of any Occupation Certificate or Subdivision Certificate as applicable.
- 35 Prior to the issue of any Construction Certificate the Principal Certifying Authority and/ or Certifying Authority shall ensure that an application under S68 of the Local Government Act, including the payment of application and inspection fees, has been lodged with, and approved by Penrith City Council for provision of (bulk earth works and drainage works) in 86 Reid Street, Warrington (Lot 5 and Lot 6, DP28248).

Engineering plans are to be prepared generally in accordance with civil plans, Project No: 1860, Revision up to C, Dated 03/03/2017, prepared by Leading Engineers.

Engineering plans are to be prepared in accordance with the development consent, Penrith City Council's

Design Guidelines for Engineering Works for Subdivisions and Developments, Engineering Construction Specification for Civil Works, Austroads Guidelines and best engineering practice.

Contact Penrith City Council's Development Engineering Department on 4732 7777 or visit Penrith City Council's website for more information.

Note:

1. All works associated with the S68 Local Government Act Approval must be completed prior to the issue of any Occupation Certificate or Subdivision Certificate as applicable.

- 36 The stormwater management system shall be provided generally in accordance with the concept plan/s lodged for development approval, prepared by danmor Consulting Engineers, reference number D15233-ST01 & ST02, revision A, dated 10/02/2016. The rainwater tanks shall be connected for reuse as required by the BASIX certificate.

The invert level of the 600x600 stormwater drainage pit within the landscape area of unit 1 (IL = 21.06m) is higher than the invert levels of the two upstream 600x600 pits (IL = 21.00m). The stormwater drainage plan needs to be amended to ensure that the proposed onsite stormwater drainage system is free draining.

Engineering plans and supporting calculations for the stormwater management systems are to be prepared by a suitably qualified person and shall accompany the application for a Construction Certificate.

Prior to the issue of any Construction Certificate the Certifying Authority shall ensure that the stormwater management system has been designed in accordance with Penrith City Council's Stormwater Drainage for Building Developments and Water Sensitive Urban Design (WSUD) Policy.

- 37 Prior to the issue of any Construction Certificate the Certifying Authority shall ensure that all habitable floor levels are in accordance with the stamped approved plans with a minimum floor level of RL 22.5m AHD (standard flood level + 0.5m).
- 38 Prior to the issue of any Construction Certificate the Certifying Authority shall ensure that the garage floor level is a minimum of RL 22.2m AHD.
- 39 Prior to the issue of any Construction Certificate the Certifying Authority shall ensure that vehicular access, circulation, manoeuvring, pedestrian and parking areas associated with the subject development are in accordance with AS 2890.1 and Penrith City Council's Development Control Plan.
- 40 Prior to the issue of any Construction Certificate a performance bond is to be lodged with Penrith City Council for (road works and drainage works) within Reid Street road reserve.

The value of the bond shall be determined in accordance with Penrith City Council's adopted Fees and Charges.

Note:

Contact Penrith City Council's Development Engineering Unit on 4732 7777 for further information relating to bond requirements.

- 41 Prior to commencement of works sediment and erosion control measures shall be installed in accordance with the approved Construction Certificate and to ensure compliance with the Protection of the Environment Operations Act 1997.

The erosion and sediment control measures shall remain in place and be maintained until all disturbed areas have been rehabilitated and stabilised.

- 42 A certificate by a registered surveyor verifying that all habitable floor levels are at or above RL 25.5m AHD (standard flood level + 0.5m) shall be submitted upon completion of the building to that level. No further construction of the building is to be carried out until approval to proceed is issued by the Principal Certifying Authority.
- 43 All earthworks shall be undertaken in accordance with AS 3798 and Penrith City Council's Design Guidelines for Engineering Works for Subdivisions and Developments and Engineering Construction Specification for Civil Works.

The level of testing shall be determined by the Geotechnical Testing Authority/ Superintendent in consultation with the Principal Certifying Authority.

- 44 Upon completion of all works in the road reserve all verge areas fronting and within the development are to be turfed. The turf shall extend from back of kerb to the property boundary with the exception of concrete footpaths, service lids or other infrastructure which is not to be turfed over. Turf laid up to concrete footpaths, service lids or other infrastructure shall finish flush with the edge.
- 45 All existing (aerial) and proposed services for the development, including those across the frontage of the development are to be located or relocated underground in accordance with the relevant authorities regulations and standards.
- 46 Prior to the issue of any Occupation Certificate, the Principal Certifying Authority shall ensure that all works associated with a S138 Roads Act approval or S68 Local Government Act approval have been inspected and signed off by Penrith City Council.
- 47 For internal building works and drainage works within private lots, prior to the issue of an Occupation Certificate, works-as-executed drawings, final operation and maintenance management plans and any other compliance documentation shall be submitted to the Principal Certifying Authority in accordance with Penrith City Council's Engineering Construction Specification for Civil Works, WSUD Technical Guidelines and Stormwater Drainage for Building Developments.

An original set of Works-As-Executed drawings and copies of the final operation and maintenance management plans and compliance documentation shall also be submitted to Penrith City Council with notification of the issue of the Subdivision Certificate where Penrith City Council is not the Principal Certifying Authority.

- 48 Prior to the issue of any Occupation Certificate the Principal Certifying Authority shall ensure that the:
- a) Stormwater management systems (water sensitive urban design)
 - Have been satisfactorily completed in accordance with the approved Construction Certificate and the requirements of this consent.
 - Have met the design intent with regard to any construction variations to the approved design.
 - Any remedial works required to been undertaken have been satisfactorily completed.

Details of the approved and constructed system/s shall be provided as part of the works-as-executed drawings.

49 Prior to the issue of any Occupation Certificate a restriction as to user and positive covenant relating to the:

- a) Stormwater management systems (including on-site detention and water sensitive urban design)

Shall be registered on the title of the property. The restriction as to user and positive covenant shall be in Penrith City Council's standard wording as detailed in Penrith City Council's Stormwater Drainage for Building Development.

50 Prior to the issue of an Occupation Certificate, a maintenance bond is to be lodged with Penrith City Council for (road works and drainage works) within Reid Street road reserve.

The value of the bond shall be determined in accordance with Penrith City Council's adopted Fees and Charges.

Note:

1. Contact Penrith City Council's Engineering Services Department on 4732 7777 for further information relating to bond requirements.

51 For all works within road reserve and bulk earthwork within private lots, prior to the issue of an Occupation Certificate the following compliance documentation shall be submitted to the Principal Certifying Authority. A copy of the following documentation shall be provided to Penrith City Council where Penrith City Council is not the Principal Certifying Authority:

- a) Work As Executed (WAE) drawings of all civil works. The WAE drawings shall be marked in red on copies of the stamped Construction Certificate drawings signed, certified and dated by a registered surveyor or the design engineer. The Work As Executed drawings shall be prepared in accordance with Penrith City Council's Engineering Construction Specification for Civil Works.
- b) The WAE drawings shall clearly indicate the 1% Annual Exceedence Probability flood lines (local and mainstream flooding).
- c) The WAE drawings shall be accompanied by plans indicating the depth of fill for the entire development site. The plans must show, by various shadings or cross hatchings, the depth of any fill within 0.3m depth ranges.
- d) CCTV footage in DVD format to Penrith City Council's requirements and a report in "SEWRAT" format for all drainage within future public roads and public land. Any damage that is identified is to be rectified in consultation with Penrith City Council.
- g) Documentation for all road pavement materials used demonstrating compliance with Penrith City Council's Engineering Construction Specification for Civil Works.
- h) A Geotechnical Report certifying that all earthworks and road formation have been completed in accordance with AS3798 and Penrith City Council's Design Guidelines and Construction specifications. The report shall include:
 - Compaction reports for road pavement construction
 - Compaction reports for bulk earthworks and lot regrading.
 - Soil classification for all residential lots
 - Statement of Compliance

- i) Structural Engineer's construction certification of all structures
- j) A slope junction plan for interallotment drainage lines indicating distances to boundaries and depths.
- k) Soil Testing for each lot to be classified according to AS2870 "Residential Slabs and Footings".

52 The stormwater management systems shall continue to be operated and maintained in perpetuity for the life of the development in accordance with the final operation and maintenance management plan.

Regular inspection records are required to be maintained and made available to Penrith City Council on request. All necessary improvements are required to be made immediately upon awareness of any deficiencies in the stormwater management systems.

53 The stormwater management systems shall continue to be operated and maintained in perpetuity to the satisfaction of Council in accordance with the final operation and maintenance management plan. Regular inspection records are required to be maintained and made available to Council upon request. All necessary improvements are required to be made immediately upon awareness of any deficiencies in the treatment measure/s

Landscaping

54 All landscape works are to be constructed in accordance with the stamped approved Landscape Concept Plan, 1648LAN2 A, prepared by Bio Engineered Solutions P/L and dated 24/2/16 and Penrith Council's Development Control Plan 2014.

Landscaping shall be maintained:

- in accordance with the approved plan, and
- in a healthy state, and in perpetuity by the existing or future owners and occupiers of the property.

If any of the vegetation comprising that landscaping dies or is removed, it is to be replaced with vegetation of the same species and, to the greatest extent practicable, the same maturity as the vegetation which died or was removed.

55 The following series of reports relating to landscaping are to be submitted to the nominated consent authority at the appropriate time periods as listed below. These reports shall be prepared by a suitably qualified and experienced landscape professional.

i. Implementation Report

Upon completion of the landscape works associated with the development and prior to the issue of an Occupation Certificate for the development, an Implementation Report must be submitted to the Principal Certifying Authority attesting to the satisfactory completion of the landscaping works for the development.

An Occupation Certificate should not be issued until such time as a satisfactory Implementation Report has been received. If Penrith City Council is not the Principal Certifying Authority, a copy of the satisfactory Implementation Report is to be submitted to Council together with the Occupation Certificate for the development.

ii. Maintenance Report

On the first anniversary of the date of the Occupation Certificate issued for the development, a Landscape Maintenance Report is to be submitted to Penrith City Council certifying that the landscape works are still in accordance with the development consent and the plant material is alive and thriving.

56 All plant material associated with the construction of approved landscaping is to be planted in accordance with the Tree Planting Specification prescribed in Penrith Council's Landscape Development Control Plan.

57 All landscape works are to meet industry best practice and the following relevant Australian Standards:

- AS 4419 Soils for Landscaping and Garden Use,
- AS 4454 Composts, Soil Conditioners and Mulches, and
- AS 4373 Pruning of Amenity Trees.

58 No trees are to be removed, ringbarked, cut, topped or lopped or wilfully destroyed (other than those within the proposed building footprint or as shown on the approved plans) without the prior consent of Penrith City Council and in accordance with Council's Tree Preservation Order and Policy.

59 **Prior to the issue of a Construction Certificate**, the landscape plan is to be amended to include the planting of:

- Two (2) trees that can attain a minimum height of 8m, are to be planted within the road area of Reid Street.

The tree is to be a minimum 100 litre pot size, consistent with the predominant tree species in the street and appropriately placed to avoid impact to existing services and infrastructure.

Section 94

- 60 This condition is imposed in accordance with Penrith City Council's Section 94 Contributions Plan(s) for Cultural Facilities. Based on the current rates detailed in the accompanying schedule attached to this Notice, \$4,712 is to be paid to Council prior to a Construction Certificate being issued for this development (the rates are subject to quarterly reviews). If not paid within the current quarterly period, this contribution will be reviewed at the time of payment in accordance with the adopted Section 94 plan. The projected rates of this contribution amount are listed in Council's Fees and Charges Schedule.

Council should be contacted prior to payment to ascertain the rate for the current quarterly period. The S94 invoice accompanying this consent should accompany the contribution payment. The Section 94 Contributions Plan for Cultural Facilities may be inspected at Council's Civic Centre, 601 High Street, Penrith.

- 61 This condition is imposed in accordance with Penrith City Council's Section 94 Contributions Plan(s) for District Open Space. Based on the current rates detailed in the accompanying schedule attached to this Notice, \$46,936 is to be paid to Council prior to a Construction Certificate being issued for this development (the rates are subject to quarterly reviews). If not paid within the current quarterly period, this contribution will be reviewed at the time of payment in accordance with the adopted Section 94 plan. The projected rates of this contribution amount are listed in Council's Fees and Charges Schedule.

Council should be contacted prior to payment to ascertain the rate for the current quarterly period. The S94 invoice accompanying this consent should accompany the contribution payment. The Section 94 Contributions Plan for District Open Space may be inspected at Council's Civic Centre, 601 High Street, Penrith.

- 62 This condition is imposed in accordance with Penrith City Council's Section 94 Contributions Plan(s) for Local Open Space. Based on the current rates detailed in the accompanying schedule attached to this Notice, \$16,982 is to be paid to Council prior to a Construction Certificate being issued for this development (the rates are subject to quarterly reviews). If not paid within the current quarterly period, this contribution will be reviewed at the time of payment in accordance with the adopted Section 94 plan. The projected rates of this contribution amount are listed in Council's Fees and Charges Schedule.

Council should be contacted prior to payment to ascertain the rate for the current quarterly period. The S94 invoice accompanying this consent should accompany the contribution payment. The Section 94 Contributions Plan for Local Open Space may be inspected at Council's Civic Centre, 601 High Street, Penrith.

Certification

- 63 Prior to the commencement of any earthworks or construction works on site, the proponent is to:
- (a) employ a Principal Certifying Authority to oversee that the said works carried out on the site are in accordance with the development consent and related Construction Certificate issued for the approved development, and with the relevant provisions of the Environmental Planning and Assessment Act and accompanying Regulation, and
 - (b) submit a Notice of Commencement to Penrith City Council.

The Principal Certifying Authority shall submit to Council an "Appointment of Principal Certifying Authority" in accordance with Section 81A of the Environmental Planning and Assessment Act 1979.

Information to accompany the Notice of Commencement

Two (2) days before any earthworks or construction/demolition works are to commence on site (including the clearing site vegetation), the proponent shall submit a "Notice of Commencement" to Council in accordance with Section 81A of the Environmental Planning and Assessment Act 1979.

Operation of OSSM

- 64 The contents of the existing septic tank are to be removed by a licensed waste contractor and deposited to an approved waste facility. The disconnected tank shall be removed, demolished or filled with clean soil and garden lime. Documentation of the collection and disposal of waste are to be retained and provided to Council on request.

SIGNATURE

Name:	Gavin Cherry
Signature:	

For the Development Services Manager