



LOKA CONSULTING ENGINEERS
www.lceng.com.au

LOKA CONSULTING ENGINEERS PTY LTD

OFFICE: 14A, 8 AVENUE OF THE AMERICAS, NEWINGTON, NSW 2127
PHONE: 02 9748 8742 / 8065 9689 FAX: 02 9748 1290 / 8065 9690
MOBILE: 0404 142 063
EMAIL: info@lceng.com.au
WEB: www.lceng.com.au

Job Number: **19NL098-TR3**

Date: **21st October, 2020**

Traffic Management Report for 103-109 Laycock Street, Cranebrook, NSW

Prepared by

LOKA CONSULTING ENGINEERS PTY LTD

Nermein Loka

BSC, ME, MIE(AUST), CPEng, NPER, RPEQ

Senior Civil Engineer

Accredited Certifier

Director

Table of Contents

1. Introduction	3
2. Proposed Development	4
2.1. Public Transportations.....	5
3. Off Street Parking Provision	6
3.1. Car parking	6
4. Car Park and Driveway Layout	7
4.1. Driveway and Ramp Design	7
4.2. Dimensions of Parking Spaces.....	8
5. Traffic Generation.....	10
6. Swept Path Analysis.....	10
Appendix A Architectural Plan	11
Appendix B Swept Path Analysis	12

1. Introduction

Loka Consulting Engineers Pty Ltd has been engaged by Alvaro Architects to provide a Traffic Management Report for the site at 103-109 Laycock Street, Cranebrook, NSW (refer to Figure 1-1 and Figure 1-2).

A Traffic Management Plan and Report is required for the proposed development to identify the impacts of the proposal on the local street network and mitigation measures required to ameliorate any impacts. This includes:

- A description of the site and details of the development proposal;
- A review of the road network in the vicinity of the site, and traffic conditions on that road network;
- A review of the geometric design features of the proposed car parking facilities for compliance with the relevant codes and standards; and
- An assessment of the adequacy and suitability of the quantum of off-street car parking provided on site.



Figure 1-1 Subject site (from SIX maps)




Figure 1-2 Site location (from SIX maps)

2. Proposed Development

The proposed development will facilitate the construction of a seniors housing development within a site area of approximately 7974m².

The proposed development is bounded by

- 101 Laycock St, 15, 21, 23, 29, 31 Camelot Dr on the East;
- 111-119 Laycock St on the West;
- 22 Nepean St on the North; and
- Laycock Street on the South.

2.1.Public Transportations

The area is well connected to public transport, with bus stations located in close proximity to the site.

1. It takes 1-minute walking (3m) from the site to 103 Laycock St before Camelot Dr bus stop (refer to Figure 2-1).
2. It takes 2-minutes walking (130m) from the site to Laycock St Across From Camelot Dr bus stop (refer to Figure 2-2).

Table 2-1 shows the bus line name; routes and the time between two successive trips. Refer to Transport NSW for accurate details.

Location	Line Name	Route	Interval
Bus stop 1	673	Penrith to Windsor via Cranebrook	4 hrs
	783	Penrith to Jordan Springs	1 hr
Bus stop 2	673	Windsor to Penrith via Cranebrook	4 hrs
	783	Jordan Springs to Penrith	1 hr

Table 2-1 Bus line, route, and time




Figure 2-1 Subject Site to bus stop 1




Figure 2-2 Subject Site to bus stop 2

3. Off Street Parking Provision

3.1. Car parking

According to State Environmental Planning Policy (Housing for Seniors or People with a Disability) 2004, the car parking requirement and summary are shown in Table 3-1 to 3-3.

Land use	Minimum number of car parking spaces
Self-contained dwellings	0.5 car space for each bedroom if made by a person other than a social housing provider 1 space for each 5 dwellings if made by a person jointly with, a social housing provider

Table 3-1 Off-street car parking space provision rate

Units and bedrooms provided are summarized in Table 3-2.

Bedroom	Quantity
2-bed	0
3-bed	16
Total bedrooms	48

Table 3-2 Bedroom summary

Required minimum parking spaces for the proposed development is shown in Table 3-3.

Parking type	Amount	Parking rate	Required	Proposed
Residential	48	0.5	24	36
Visitor	-	-	-	-
Total			24	36

Table 3-3 Required minimum car parking spaces

The design complies with the requirement from State Environmental Planning Policy (Housing for Seniors or People with a Disability) 2004.

The architectural plan of the proposed development has been prepared by Alvaro Architects and is attached in Appendix A.

4. Car Park and Driveway Layout

4.1. Driveway and Ramp Design

The design of the driveway, internal roadways & ramps, and car parking spaces must comply with relevant Australian Standards; details are shown in the architectural plan. Table 4-1 and Table 4-2 assess the compliance of the site to Australian Standard and HSPD 2004.

FEATURE	AS 2890.1:2004	HSPD 2004	Architectural Plan	Compliance
Driveway width	<ul style="list-style-type: none"> • 3.0 to 5.5 for Category 1. • 6.0 to 9.0 for Category 2. 	According to AS2890.1	5.8m two-way combine entry with 150mm kerbs on both sides	The design is complied with AS2890.1 and council DCP
Internal driveway width	<ul style="list-style-type: none"> • One-way – 3.0m minimum between kerbs • Two- way – 5.5m minimum between kerbs • Note: 300mm clearance on both side when there is a high kerb or barrier on both sides. 	According to AS2890.1	Ensure the garage door and internal head clearance is min. 2.2m at CC stage	The design is complied with AS2890.1 and council DCP
Internal driveway grade	<p>Longer than 20m – 1:5 maximum. Up to 20m long – 1:4 maximum.</p> <p>Transition grade no more than 1:8.</p>	According to AS2890.1	Ensure the driveway levels are complying with AS2890.1 at CC stage.	The design is complied with AS2890.1 and council DCP

	First 6m no more than 1:20. Changes of grade no more than 1:8.			
Headroom	2.2m min between the floor and an overhead obstruction. Headroom above each dedicated space and adjacent shared area should be a minimum of 2.5m.	According to AS2890.1	Ensure the garage door and internal head clearance is min. 2.2m at CC stage	The design is complied with AS2890.1 and council DCP

Table 4-1 Driveway and ramp design

4.2. Dimensions of Parking Spaces

The design of the car parking spaces should be in compliance with AS 2890.1, 3 & 6.

FEATURE	AS/NZS 2890.1, 2890.6 & 4299	HSPD 2004	Architectural Plan	Compliance
Residential garage	6.0m x 3.8m (AS4299)	According to AS4299	Min. 6.120m x 3.805m	The design is complied with AS4299 and council DCP
Carport	5.4m x 2.4m	According to AS2890.1	5.42m x 2.5m	The design is complied with AS2890.1
Garage door width	Min. 2.4m	According to AS2890.1	2.5m	The design is complied with AS2890.1 and council DCP
Garage apron width	7.0m for 2.4m door 6.3m for 2.7m door 5.6m for 3.0m door	According to AS2890.1	More than 7m	The design is complied with AS2890.1 and council DCP
Residential parking space	5.4m x 2.4m Additional 300mm when adjacent a wall	According to AS2890.1	5.4m x 2.4m Additional 300mm when adjacent a wall	The design is complied with AS2890.1 and council DCP
Aisle Widths	5.8m minimum	According to AS2890.1	5.8m with 150mm kerb on both sides	The design is complied with AS2890.1 and council DCP

Table 4-2 Dimensions of parking spaces

As required in AS 2890.1:2004, a triangular area with 2.5m (face to driveway) by 2.0m (face to street) will be kept clear of obstructions to visibility (Refer to Figure 4-1).




Figure 4-1 AS 2890.1:2004 requirement

In accordance with AS 2890.1:2004, sight triangle is hatched in red and shown in the following Figure 4-2.




Figure 4-2 Sight triangle

Ensure any object within the sight triangle is max. 1.15m high or 50% transparent above 0.9m if higher than 1.15m.

The design complies with sight triangle requirement.

5. Traffic Generation

An indication of the traffic generation potential of the development proposal is provided in accordance with Roads and Maritime Services (RMS) publication 'Guide to Traffic Generating Developments – Updated traffic surveys (August 2013)'.

RMS guidelines are based on an extensive survey of a wide range of land uses.

The existing site is identified as dwelling house.

Dwelling houses

Daily vehicle trips = 9.0 per dwelling

Weekday peak hour vehicle trips = 0.85 per dwelling

The subject site is identified as medium density residential flat building.

Medium density residential flat building

Larger units and town houses (three or more bedrooms)

Daily vehicle trips = 5.0 - 6.5 per dwelling

Weekday peak hour vehicle trips = 0.5 - 0.65 per dwelling = 0.65 x 16 = 9.3

This value should be discounted by the expected existing volume of traffic, to determine the net increase (or decrease) in future expected traffic. This is shown in Table 5-1 below.

Traffic Generation Potential	Land Use	Peak hour vehicle trips
Future	Residential	+10
Existing	Residential	1
Net increase		+9

Table 5-1 Project Net Increase in Peak Hour Traffic Generation Potential

According to the Table above, it is likely that the proposed development will result in a change in the traffic generation by approximately **9 additional** peak hour vehicle trips.


6. Swept Path Analysis

To ensure all vehicles enter and exit the site in a forward direction, swept path analysis has been conducted in the Appendix B.

It is our opinion that the proposed car parking and driveway comply with Australia Standard.

APPENDIX A

Architectural Plan



REV	DATE	DESCRIPTION	BY
E	02.05.19	ISSUE TO CONSULTANTS FOR REVIEW	EF
F	01.06.19	ISSUE TO CLIENT, CONSULTANTS & COUNCIL FOR PRE-DA	EF
G	16.07.19	ISSUE TO CLIENT, CONSULTANTS & COUNCIL FOR REVIEW	EF
H	08.08.19	AMENDED PLANS TO CONSULTANTS FOR REVIEW	EF
J	28.08.19	ISSUE TO CONSULTANTS & CLIENT FOR REVIEW	EF
K	09.09.19	AMENDED PLANS TO CONSULTANTS FOR REVIEW	RA
L	13.09.19	AMENDED PLANS TO CONSULTANTS FOR REVIEW	RA
M	14.10.19	FINAL ISSUE TO CLIENT & CONSULTANTS FOR APPROVAL	EF
N	12.02.20	AMENDED ISSUE TO CLIENT & PLANNER FOR REVIEW	RA
P	20.03.20	AMENDED ISSUE TO CLIENT & PLANNER FOR REVIEW	RA
Q	02.04.20	AMENDED PLANS TO CLIENT FOR APPROVAL	EF
R	28.04.20	COMPARISON PLANS TO COUNCIL FOR REVIEW	RA
S	03.06.20	AMENDED PLANS TO COUNCIL FOR REVIEW	EF
T	03.08.20	PRELIMINARY ISSUE TO CONSULTANTS FOR REVIEW	EF
U	09.09.20	AMENDED ISSUE TO CONSULTANTS FOR REVIEW	VF
V	09.09.20	AMENDED ISSUE TO CONSULTANTS FOR REVIEW	EF
W	09.10.20	AMENDED ISSUE TO CONSULTANTS FOR REVIEW	EF

CLIENT PROJECT ADDRESS
 F. Catanea 103-109 Laycock Street
 49 Cross Road Cranebrook 2749
 Orchard Hills 2748

ALVARO ARCHITECTS PTY LTD
 ABN 71 604 570 309
 Mem. Architect R. Alvaro 9221
 0402 529 840
 Unit 24, 2-8 Daniel Street,
 Wetherill Park, NSW 2164
 info@alvaroarchitects.com.au
 ALVAROARCHITECTS.COM.AU



PROJECT
**Proposed Seniors Housing
 Cranebrook**


Use figured dimensions only. Verify all levels and dimensions on site before commencing construction, fabrication, or shop drawings.
 © Copyright - All rights reserved.

PRELIMINARY

NORTH	DRAWN	DRAWING TITLE
	EF	SITE PLAN
CHECKED	SCALE @A2	JOB NUMBER
RA	1:250	0246
APPROVED	DRAWING NO.	REV
RA	102	W

APPENDIX B

Swept Path Analysis



SWEPT PATH ANALYSIS ENTRY

NOT FOR CONSTRUCTION

A1 0 1 2 3 4 5 6 7 8 9 10

No	AMENDMENT	ENG	DRAFT	DATE	No	AMENDMENT	ENG	DRAFT	DATE
A	FOR D.A. APPROVAL	N.L.	L.W.	10-09-2020					

THIS DRAWING IS THE PROPERTY OF LOKA CONSULTING ENGINEERS AND MUST NOT BE RETAINED, COPIED OR USED WITHOUT THE WRITTEN CONSENT OF THE COMPANY

Copyright Loka Consulting Engineers as date of issue

ARCHITECT

ALVARO ARCHITECTS PTY LTD
 ABN 71 604 570 309
 Nbn, Archibald R, Alvaro 9221
 0402 529 8640
 H Unit 24, 2-8 Daniel Street,
 Wetherill Park, NSW 2164
 E info@alvaroarchitects.com.au
 ALVAROARCHITECTS.COM.AU

ALVARO

LOKA CONSULTING ENGINEERS PTY LTD

OFFICE: 16A, B AVENUE OF THE AMERICAS, NEWINGTON, NSW 2127
 PHONE: 02 9148 8100 / 8000 9600 FAX: 02 9148 1000 / 8000 9600
 MOBILE: 0404 142 083
 EMAIL: info@loka.com.au
 WEB: www.loka.com.au

COPYRIGHT: THIS DESIGN AND PLANS ARE NOT TO BE USED OR REPRODUCED WHOLLY OR IN PART WITHOUT WRITTEN PERMISSION OF LOKA CONSULTING ENGINEERS


PROJECT

SENIORS HOUSING DEVELOPMENT
103-109 LAYCOCK STREET,
CRANE BROOK, NSW

SHEET SUBJECT

SWEPT PATH ANALYSIS ENTRY

PROJECT 103-109 LAYCOCK STREET, CRANE BROOK, NSW			
DATE	DRAWN	DESIGNED	CHECKED
SEP 20	L.W.	A.E.	N.L.
SCALE @ A1 1 : 200 U.N.O		JOB No 19NL098	
AUTHORISED NERMEIN LOKA		DWG No T01	REV A



SWEPT PATH ANALYSIS EXIT

NOT FOR CONSTRUCTION

A1 0 1 2 3 4 5 6 7 8 9 10

No	AMENDMENT	ENG	DRAFT	DATE	No	AMENDMENT	ENG	DRAFT	DATE
A	FOR D.A. APPROVAL	N.L.	L.W.	10-09-2020					

THIS DRAWING IS THE PROPERTY OF LOKA CONSULTING ENGINEERS AND MUST NOT BE RETAINED, COPIED OR USED WITHOUT THE WRITTEN CONSENT OF THE COMPANY

Copyright Loka Consulting Engineers as date of issue

ARCHITECT
 ALVARO ARCHITECTS PTY LTD
 ABN 71 604 570 309
 Nelm Architects R. Alvaro 9221
 0402 529 8540
 H Unit 24, 2-8 Daniel Street,
 Wetherill Park, NSW 2164
 E info@alvaroarchitects.com.au
 ALVAROARCHITECTS.COM.AU



LOKA CONSULTING ENGINEERS PTY LTD
 OFFICE: 16A, B AVENUE OF THE AMERICAS, NEWINGTON, NSW 2127
 PHONE: 02 9148 8100 / 8000 9600 FAX: 02 9148 1000 / 8000 9600
 MOBILE: 0401 142 083
 EMAIL: info@loka.com.au
 WEB: WWW.LOKA.COM.AU




COPYRIGHT: THIS DESIGN AND PLANS ARE NOT TO BE USED OR REPRODUCED WHOLLY OR IN PART WITHOUT WRITTEN PERMISSION OF LOKA CONSULTING ENGINEERS

PROJECT
 SENIORS HOUSING DEVELOPMENT
 103-109 LAYCOCK STREET,
 CRANE BROOK, NSW



SHEET SUBJECT
 SWEPT PATH ANALYSIS
 EXIT

PROJECT 103-109 LAYCOCK STREET, CRANE BROOK, NSW			
DATE	DRAWN	DESIGNED	CHECKED
SEP 20	L.W.	A.E.	N.L.
SCALE @ A1	JOB No		
1 : 200 U.N.O	19NL098		
AUTHORISED	DWG No	REV	
NERMEIN LOKA	T02	A	



SWEPT PATH ANALYSIS B85 PASSING B99

NOT FOR CONSTRUCTION

A1 0 1 2 3 4 5 6 7 8 9 10

No	AMENDMENT	ENG	DRAFT	DATE	No	AMENDMENT	ENG	DRAFT	DATE
A	FOR D.A. APPROVAL	N.L.	L.W.	10-09-2020					

THIS DRAWING IS THE PROPERTY OF LOKA CONSULTING ENGINEERS AND MUST NOT BE RETAINED, COPIED OR USED WITHOUT THE WRITTEN CONSENT OF THE COMPANY

Copyright Loka Consulting Engineers as date of issue

ARCHITECT
 ALVARO ARCHITECTS PTY LTD
 ABN 71 604 570 309
 Non-Architects R. Alvaro 9221
 0402 529 8640
 H Unit 24, 2-8 Daniel Street,
 Wetherill Park, NSW 2164
 E info@alvaroarchitects.com.au
 ALVAROARCHITECTS.COM.AU

ALVARO

LOKA CONSULTING ENGINEERS PTY LTD
 OFFICE: 16A, B AVENUE OF THE AMERICAS, NEWINGTON, NSW 2127
 PHONE: 02 9148 8121 / 8000 9600 FAX: 02 9148 1200 / 8000 9600
 MOBILE: 0401 142 083
 EMAIL: info@loka.com.au
 WEB: www.loka.com.au

COPYRIGHT: THIS DESIGN AND PLANS ARE NOT TO BE USED OR REPRODUCED WHOLLY OR IN PART WITHOUT WRITTEN PERMISSION OF LOKA CONSULTING ENGINEERS

PROJECT
 SENIORS HOUSING DEVELOPMENT
 103-109 LAYCOCK STREET,
 CRANE BROOK, NSW

SHEET SUBJECT
 SWEPT PATH ANALYSIS
 B85 PASSING B99

PROJECT 103-109 LAYCOCK STREET, CRANE BROOK, NSW			
DATE	DRAWN	DESIGNED	CHECKED
SEP 20	L.W.	A.E.	N.L.
SCALE @ A1 1 : 200 U.N.O		JOB No 19NL098	
AUTHORISED NERMEIN LOKA		DWG No T03	REV A