





**LEGEND**

- 9:00 AM 22ND JUNE
- 12:00 PM 22ND JUNE
- 3:00 PM 22ND JUNE



 NY Project Services Pty Ltd  Mob: 0403 280 297 111 Barnier Drive, Quakers Hill, NSW 2763			PROJECT LOCATION			TITLE		FIGURED DIMENSIONS TO BE TAKEN IN PREFERENCE TO SCALED READINGS. VERIFY ALL DIMENSIONS ON SITE.		
			60 DONCASTER AVE			SHADOW DIAGRAMS				
			CLAREMONT MEADOWS NSW							
				DRAWN BY	DATE PLOTTED	SCRIPT FILE/S	PROJECT		SCALE	
				YH	15/08/2018	N/A	PROPOSED TWO STOREY DWELLING		1:500	
			CAD REFERENCE			XREF/S			DRAWING No.	REV
						N/A			SD-01	A



- NOTES:
- \* The position of features are indicative only.
  - \* Services shown hereon have been located where possible by field survey. Prior to any excavation or construction on the site, the relevant authority should be contacted for possible location of any other services including those which may be underground.
  - \* 45.45 \* indicates natural surface level.
  - \* Contours shown depict the general topography. They do not represent exact levels other than at spot levels shown.
  - \* Relationship of improvements to boundaries is diagrammatic only. Where offsets are critical they should be confirmed by further survey.
  - \* Bearings and distances are by title only. No boundary investigation has been carried out.
  - \* The shapes, sizes, and position, of trees are approximate only. Further field inspection should be carried out where tree details are considered to critically affect design.

(B) EASEMENT FOR DRAINAGE OF WATER 2 WIDE  
(F) POSITIVE COVENANT 1 WIDE  
(U) POSITIVE COVENANT 20 WIDE  
(V) RESTRICTION ON THE USE OF LAND 20 WIDE

LEVELS BASED ON SSM 60068, RL 41.299  
SOURCE: SCIMS DATED, 04-05-2018



Client: <b>MICHEAL BELLINO</b>	Project: <b>PLAN SHOWING DETAIL, LEVELS &amp; CONTOURS OVER LOT 32 IN DP 1224294 KNOWN AS N° 60 DONCASTER AVENUE, CLAREMONT MEADOWS</b>		<b>MATTHEW FREEBURN</b> LAND, ENGINEERING & MINING SURVEYOR SUITE 2, FIRST FLOOR, "SURVEYOR HOUSE" 2 CASTLEREAGH STREET PENRITH 2750	Telephone 02 4721 2289 Fax 02 4721 5646 email matthew@freeburnsurveyors.com	Date: 04/05/2018 Scale 1: 150 Surveyor: DC DATA-36395	Ref: 36395 Datum: AHD Drawn By: DC	Sheet 1 of 1 Contour: 0.2m INT Checked: MF A2 SHEET
-----------------------------------	--	---	--	---	--	--	--



# PROPOSED RESIDENCE

## AT 60 DONCASTER AVENUE, CLAREMONT MEADOWS

### GENERAL

- G1 These drawings shall be read in conjunction with all architectural and other consultant drawings and specifications and with such other written instructions and notices as may be issued during the course of the Contract. Any discrepancies shall be referred to the Superintendent before proceeding with any related works. Construction from these drawings, and their associated consultants drawings is not to commence until approved by the Local Authorities.
- G2 All materials and workmanship shall be in accordance with the relevant and current Standards Australia codes and with the By-Laws and Ordinances of the relevant building authorities except where varied by the project specification.
- G3 All set out dimensions shall be obtained from Architect's and Engineer's details. All discrepancies shall be referred to the Architect and Engineer for decision before proceeding with related work.
- G4 During construction the structure shall be maintained in a stable condition and no part shall be overstressed. Temporary bracing shall be provided by the builder/subcontractor to keep the works and excavations stable at all times.
- G5 Unless noted otherwise levels are in metres and dimensions are in millimetres.
- G6 The alignment and level of all services shown are approximate only. The contractor shall confirm the position and level of all services prior to commencement of construction. Any damage to services shall be rectified at the contractors expense.
- G7 Any substitution of materials shall be approved by the Engineer and included in any tender.
- G8 All services, or conduits for servicing shall be installed prior to commencement of pavement construction.
- G9 Subsoil drainage, comprising 100 agriculture pipe in geo-stocking to be placed as shown and as may be directed by the superintendent. Subsoil drainage shall be constructed in accordance with the relevant local authority construction specification.
- G10 The structural components detailed on these drawings have been designed in accordance with the relevant Standards Australia codes and Local Government Ordinances for the following loadings. Refer to the Architectural drawings for proposed floor usage. Refer to drawings for live loads and superimposed dead loads.

### DRAINAGE NOTES

- D1 All drainage levels to be confirmed on site, prior to any construction commencing.
- D2 All pipes within the property to be a minimum of 100 dia upvc @ 1% minimum grade, uno.
- D3 All pits within the property are to be fitted with "weldok" or approved equivalent grates:  
- Light duty for landscaped areas  
- Heavy duty where subjected to vehicular traffic
- D4 All pits within the property to be constructed as one of the following:  
1) Precast stormwater pits  
2) Cast in situ mass concrete  
3) Cement rendered 230mm brickwork subject to the relevant local authority construction specification.
- D5 Ensure all grates to pits are set below finished surface level within the property. Top of pit RL's are approximate only and may be varied subject to approval of the engineer. All invert levels are to be achieved.
- D6 Any pipes beneath relevant local authority road to be rubber ring jointed RCP, uno.
- D7 All pits in roadways are to be fitted with heavy duty grates with locking bolts and continuous hinge.
- D8 Provide step lrene to stormwater pits greater than 1200 in depth.
- D9 Trench back fill in roadways shall comprise sharp, clean granular back fill in accordance with the relevant local authority specification to non-trafficable areas to be compacted by rodding and tamping using a flat plate vibrator.
- D10 Where a high early discharge (had) pit is provided all pipes are to be connected to the had pit, uno.
- D11 Down pipes shall be a minimum of dn100 sw grade upvc or 100 x100 colorbond/zincalume steel, uno.
- D12 Colorbond or zincalume steel box gutters shall be a minimum of 450 wide x 150 deep.
- D13 Eaves gutters shall be a minimum of 125 wide x 100 deep (or of equivalent area) colorbond or zincalume steel, uno.
- D14 Subsoil drainage shall be provided to all retaining walls & embankments, with the lines feeding into the stormwater drainage system, uno.

### EROSION AND SEDIMENT CONTROL NOTES

- E1 These notes are to be read in conjunction with erosion and sediment control details in this drawing set.
- E2 The contractor shall implement all soil erosion and sediment control measures as necessary and to the satisfaction of the relevant local authority prior to the commencement of and during construction. No disturbance to the site shall be permitted other than in the immediate area of the works and no material shall be removed from the site without the relevant local authority approval. All erosion and sediment control devices to be installed and maintained in accordance with standards outlined in new department of housing's "managing urban stormwater - soils and construction".
- E3 Place straw bales length wise in a row as parallel as possible to the site contours, uno. Bale ends to be tightly butted. Bales are to be placed so that straw are parallel to the row. Bales are to be placed 1.5m to 2m down slope from the toe of the disturbed batter, uno.
- E4 Council approved filter fabric to be entrenched 150mm deep upslope towards disturbed surface. Fabric to be a minimum SF2000 or better. The fabric to posts with wire stake or as recommended with manufacturer's specifications. Fabric joints to have a minimum of 160mm overlap. Wire to be strung between posts with filter fabric overlap to prevent sagging.
- E5 Stabilised entry/exit points to remain intact until finished driveway is complete. Construction of entry/exit points to be maintained and repaired as required so that it's function is not compromised. Construction of entry/exit point to be in accordance with the detail contained within this drawing set.
- E6 All drainage pipe inlets to be capped until:  
- downpipes connected  
- pits constructed and protected with silt barrier
- E7 Provide and maintain silt traps around all surface inlet pits until catchment is revegetated or paved.
- E7 The contractor shall regularly maintain all erosion and sediment control device and remove accumulated silt from such devices such that more than 80% of their capacity is lost. All the silt is to be placed outside the limit of works. The period for maintaining these devices shall be at least until all disturbed areas are revegetated and further as may be directed by the superintendent or council.
- E8 The contractor shall implement dust control by regularly wetting down (but not saturating) disturbed area.
- E9 Topsoil shall be stripped and stockpiled outside hazard areas such as drainage lines. This topsoil shall be respread later on areas to be revegetated and stabilised only. (i.e. all footpaths, battens, site retaining areas, basins and catchdrains). Topsoil shall not be respread on any other areas unless specifically instructed by the superintendent. If they are to remain for longer than one month stockpile shall be protected from erosion by covering them with a mulch and hydros seeding and, if necessary, by locating barriers or drains downstream of a stockpile to retard silt laden runoff.
- E10 Lay 300 wide minimum turf strip on 100 topsoil behind all kerb and gutter with 1000 long returns every 8000 and around structures immediately after building as per the relevant local authority specification.
- E11 The contractor shall grass seed all disturbed areas with an approved mix as soon as practicable after completion of earthworks and regrading.
- E12 Revegetate all trenches immediately upon completion of backfilling.
- E13 When any device are to be handed over to council they shall be in clean and stable condition.

### STANDARD LINE TYPES AND SYMBOLS

	PROPOSED KERB & GUTTER
	EXISTING KERB & GUTTER
	PROPOSED BELOW GROUND PIPELINE
	PROPOSED SUSPENDED PIPELINE
	EXISTING PIPELINE
	SUBSOIL DRAINAGE LINE
	PROPOSED KERB INLET PIT
	EXISTING KERB INLET PIT
	PROPOSED JUNCTION OR INLET PIT
	EXISTING JUNCTION OR INLET PIT
	DESIGN CENTRELINE
	EXISTING EDGE OF BITUMEN
	TELECOMMUNICATION CONDUIT
	GAS MAIN
	WATER MAIN
	SEWER MAIN
	UNDERGROUND ELECTRICITY CABLES
	PERMANENT MARK & S.S.M.
	BENCHMARK, SURVEY STATION

### STANDARD LINE TYPES AND SYMBOLS

	OVERLAND FLOW PATH
	GUTTER DRAINAGE DIRECTION
	DOWNPIPE
	DOWNPIPE WITH SIDE OVERFLOW
	PERVIOUS (GRASSED) AREAS
	EXISTING (PRE-DEVELOPMENT) RL
	POST DEVELOPMENT RL
	GRADED IMPERVIOUS AREA (ROOF, CONC SLABS ETC)
	SEDIMENT FENCE
	CROSSING PIPES
	NODE POINT

### LEGEND

AHD	Australian height datum	SS	Stainless steel
AG	Ag pipe (Sub soil drainage)	SU	Box gutter sump
ARI	Average recurrence interval	TW	Top of wall
BG	Box Gutter	TWL	Top water level
BWL	Bottom water level	U/S	Underside of slab
CL	Cover level	VG	Vally gutter
CO	Clean out inspection opening	UNO	Unless noted otherwise
DCP	Discharge control pit		
DP	Down pipe		
DRP	Dropper pipe		
EBG	Existing box gutter		
EDP	Existing down pipe		
EEG	Existing eaves gutter		
EG	Eaves gutter		
FRC	Fiber reinforced concrete		
FW	Floor waste		
GD	Grated drain		
GSP	Grated surface inlet pit		
HED	High early discharge		
HP	High point of gutter		
IL	Invert level		
IO	Inspection opening		
QIF	On-site detention		
OSD	On-site detention		
PSD	Permissible site discharge		
P1	Pipe 1		
RCP	Reinforced concrete pipe		
RHS	Rectangular hollow section		
RL	Reduced level		
RJ	Rubber ring joint		
RRT	Rainwater re-use tank		
RWH	Rain water head		
RWO	Rain water outlet		
SLAP	Suited 1st access pit		
SP	Spreader pipe		
SPR	Spreader		

### RECOMMENDED MAINTENANCE SCHEDULE

DISCHARGE CONTROL PIT (DCP)	FREQUENCY	RESPONSIBILITY	PROCEDURE
Inspect flap valve and remove any blockage.	Six monthly	Owner	Remove grate. Ensure flap valve moves freely and remove any blockages or debris.
Inspect screen and clean.	Six monthly	Owner	Remove grate and screen if required and clean it.
Inspect & remove any blockage of orifice.	Six monthly	Owner	Remove grate & screen to inspect orifice, see plan for location of dcp.
Inspect dcp pump & remove any sediment-sludge.	Six monthly	Owner	Remove grate and screen. Remove sediment/sludge build-up and check orifice and flap valve clear.
Inspect grate for damage or blockage.	Six monthly	Owner	Check both sides of grate for corrosion, (especially corners and welds) damage or blockage.
Inspect return pipe from storage and return any blockage.	Six monthly	Owner	Remove grate and screen, ventilate underground storage if present, open flap valve and remove any blockages in return line. Check for sludge/debris on upstream side of return line.
Inspect outlet pipe and remove any blockage.	Six monthly	Maintenance Contractor	Remove grate and screen, ventilate underground storage if present. Check orifice and remove any blockages in outlet pipe. Flush outlet pipe to confirm it drains freely. Check for sludge/debris on upstream side of return line.
Check fitting of step lrene is secure.	Six monthly	Maintenance Contractor	Remove grate and ensure fittings secure prior to placing weight on step lrene.
Inspect overflow weir & remove any blockage.	Six monthly	Maintenance Contractor	Remove grate and open cover to ventilate underground storage if present, ensure weir clear of blockages.
Empty basket at overflow weir (if present).	Six monthly	Maintenance Contractor	Remove grate and ventilate underground storage chamber if present. Empty basket, check fittings secure and not corroded.
Check attachment of orifice plate to wall of pit (gaps less than 5 mm).	Annually	Maintenance Contractor	Remove grate and screen, ensure plate mounted securely, tighten fittings if required, seal gaps as required.
Check attachment of screen to wall of pit.	Annually	Maintenance Contractor	Remove grate and screen, ensure screen fittings secure, repair as required.
Check screen for corrosion.	Annually	Maintenance Contractor	Remove grate and examine screen for rust or corrosion, especially at corners or welds.
Check attachment of flap valve to wall of .	Annually	Maintenance Contractor	Remove grate. Ensure fittings of valve are secure.
Check flap valve seals against wall of pit.	Annually	Maintenance Contractor	Remove grate. Fill pit with water and check that flap seals against side of pit with minimal leakage.
Check any hinges of flap valve move freely.	Annually	Maintenance Contractor	Remove grate. Test valve hinge by moving flap to full extent.
Inspect dip valve (internal and external, if appropriate) for cracks or spalling.	Annually	Maintenance Contractor	Remove grate to inspect internal walls. Repair as required. Clear vegetation from external walls if necessary and repair as required.
Check step lrene for corrosion.	Annually	Maintenance Contractor	Remove grate. Examine step lrene and repair any corrosion or damage.
Check orifice diameter correct and retains sharp edge.	Five yearly	Maintenance Contractor	Compare diameter to design (see work-as-executed) and ensure edge is not pitted or damaged.
STORAGE			
Inspect & remove any blockage of orifice.	Six monthly	Owner	Remove grate and screen, remove sediment/sludge build-up.
Check orifice diameter correct and retains sharp edge.	Six monthly	Owner	Remove blockages from grate and check if pit blocked.
Inspect screen and clean.	Six monthly	Owner	Remove debris and floatable material likely to be carried to grates.
Check attachment of orifice plate to wall of pit (gaps less than 5 mm).	Annually	Maintenance Contractor	Remove grate to inspect internal walls, repair as required, clear vegetation from external walls if necessary and repair as required.
Check attachment of screen to wall of pit.	Five yearly	Maintenance Contractor	Compare actual storage available with work-as-executed plans. If volume loss is greater than 5%, arrange for reconstruction to replace the volume lost. Council to be notified of the proposal.
Check attachment of screen to wall of pit.	Five yearly	Maintenance Contractor	Check along drainage lines and at pits for subsidence likely to indicate leakages.

NOTE: DO NOT SCALE OFF DRAWINGS. REFER TO ARCHITECTURAL PLANS. VERIFY DIMENSIONS ON SITE

REV	DATE	DESCRIPTION	BY
B	27.08.18	RE-ISSUED FOR APPROVAL	O.G.
A	23.08.18	ISSUED FOR APPROVAL	D.M.

COPYRIGHT  
All rights reserved.  
These drawings, plans and specifications and the copyright are the property of Engineering Studio and must not be used, reproduced or copied wholly or in part without the written permission of Engineering Studio.



Phone: (02) 8022 2880  
Email: info@engineeringstudio.com.au  
Web: www.engineeringstudio.com.au

Postal Address  
PO Box 7191  
BAULKHAM HILLS NSW 2153


**PROPOSED RESIDENCE**  
**AT 60 DONCASTER AVENUE, CLAREMONT MEADOWS**  
**FOR DISTINCT INNOVATIONS**

### GENERAL NOTES


JOB NUMBER: 18519	DWG NUMBER: C00.01	ORIGINAL SIZE: A3
DESIGNED BY: O.G.	DATE: AUGUST 2018	
DRAWN BY: D.M.	SCALE: N.T.S	








OPTION 1 - EXISTING DRIVEWAY TO REMAIN



OPTION 2 - DRIVEWAY TO BE RENEWED



## BUILDING MATERIAL STOCKPILES

N.T.S


ALL STOCKPILES OF BUILDING MATERIAL SUCH AS SAND AND SOIL MUST BE PROTECTED TO PREVENT SCOUR AND EROSION.

THEY SHOULD NEVER BE PLACED IN THE STREET GUTTER WHERE THEY WILL WASH AWAY WITH THE FIRST RAINSTORM.

## VEHICLE ACCESS TO SITE


N.T.S

VEHICLE ACCESS TO THE BUILDING SITE SHOULD BE RESTRICTED TO A SINGLE POINT SO AS TO REDUCE THE AMOUNT OF SOIL DEPOSITED ON THE STREET PAVEMENT.




## STRAW BALE DETAIL

N.T.S



## SEDIMENT AND EROSION FENCE DETAIL

N.T.S



## SANDBAG KERB SEDIMENT TRAP

N.T.S

IN CERTAIN CIRCUMSTANCES EXTRA SEDIMENT TRAPPING MAY BE NEEDED IN THE STREET GUTTER.

REV	DATE	DESCRIPTION	BY
B	27.08.18	RE-ISSUED FOR APPROVAL	O.G.
A	23.08.18	ISSUED FOR APPROVAL	D.M.

NOTE: DO NOT SCALE OFF DRAWINGS. REFER TO ARCHITECTURAL PLANS. VERIFY DIMENSIONS ON SITE

COPYRIGHT  
All rights reserved.  
These drawings, plans and specifications and the copyright are the property of Engineering Studio and must not be used, reproduced or copied wholly or in part without the written permission of Engineering Studio.




Phone: (02) 8022 2880  
Email: info@engineeringstudio.com.au  
Web: www.engineeringstudio.com.au


Postal Address  
PO Box 7191  
BAULKHAM HILLS NSW 2153

PROPOSED RESIDENCE  
AT 60 DONCASTER AVENUE, CLAREMONT MEADOWS  
FOR DISTINCT INNOVATIONS

SEDIMENT & EROSION  
CONTROL DETAILS

JOB NUMBER: 18519	DWG NUMBER: C01.02	ORIGINAL SIZE: A3
DESIGNED BY: O.G.	DATE: AUGUST 2018	
DRAWN BY: D.M.	SCALE: 1:20 U.N.O	





## STORMWATER DRAINAGE PLAN

1:200

### STORMWATER DESIGN SUMMARY

COUNCIL: PENRITH CITY COUNCIL  
100 YEAR, 5 MIN STORM: 241 mm/h  
20 YEAR, 5 MIN STORM: 179 mm/h

TOTAL SITE AREA = 950.0 m<sup>2</sup>  
PROPOSED ROOF AREA = 415.0 m<sup>2</sup>  
IMPERVIOUS PATHS & DRIVEWAYS = 54.0 m<sup>2</sup>  
TOTAL IMPERVIOUS SITE AREA = 469.0 m<sup>2</sup>  
IMPERVIOUS SITE PERCENTAGE = 49.3%

100% NEW ROOF AREA DIRECTED TO ABOVE GROUND RAINWATER RE-USE TANK TO BUILDERS DETAILS IN ACCORDANCE WITH BASIX SPECIFICATIONS.

HIGH LEVEL OVERFLOW DIRECTED TO BELOW GROUND ON-SITE DETENTION TANK. OSD DISCHARGE DIRECTED TO EXISTING REAR DRAINAGE PIT VIA GRAVITY IN ACCORDANCE WITH COUNCIL REQUIREMENTS.

### ON-SITE DETENTION DESIGN SUMMARY

ON-SITE DETENTION REQUIRED FOR PROPOSED SINGLE RESIDENTIAL DEVELOPMENT IN ACCORDANCE WITH 'POSITIVE COVENANT NUMBER 19 IN THE SECTION 88B INSTRUMENT'.

ON-SITE DETENTION STORAGE REQUIRED = 33m<sup>3</sup>  
PERMISSIBLE SITE DISCHARGE REQUIRED FOR:  
1:5 YEAR ARI STORM: = 8 l/s  
1:100 YEAR ARI STORM: = 12 l/s  
MAXIMUM HEAD TO ORIFICE = 1.35 m  
ORIFICE DIAMETER = 70 mm  
STORAGE PROVIDED = 33.60 m<sup>3</sup>

### STORMWATER DRAINAGE NOTES

- ALL DRAINAGE LINES SHALL BE uPVC (CLASS SH) STORMWATER DRAINAGE PIPE, U.N.O.
- ALL DRAINAGE LINES SHALL BE LAID @ 1% FALL MIN, U.N.O.
- FIRST FLUSH RAINWATER DEVICES TO BE FITTED TO DRAINAGE LINES TO BUILDER'S DETAIL, TYPICAL
- MINIMUM EFFECTIVE BOX GUTTER SLOPE = 1:200 U.N.O.
- MINIMUM EFFECTIVE EAVES GUTTER SLOPE = 1:500 U.N.O.
- MINIMUM EFFECTIVE EAVES GUTTER SIZE = 6500 mm<sup>2</sup>

### LEGEND

- Ø90 OR 100 x 50 RECTANGULAR DOWN PIPE, U.N.O.
- INSPECTION POINT
- RAINWATER SPREADER
- FIRST FLUSH RAINWATER DEVICE TO BUILDERS DETAIL
- PROPOSED FINISHED SURFACE LEVEL
- CHARGED PIPE
- PROPOSED BELOW GROUND PIPELINE
- EXISTING PIPELINE
- PROPOSED SURFACE INLET PIT
- BG1 350W x 110D BOX GUTTER
- RWH 350W x 130D x 110L RAINWATER HEAD

REV	DATE	DESCRIPTION	BY
B	27.08.18	RE-ISSUED FOR APPROVAL	O.G.
A	23.08.18	ISSUED FOR APPROVAL	D.M.

NOTE: DO NOT SCALE OFF DRAWINGS. REFER TO ARCHITECTURAL PLANS. VERIFY DIMENSIONS ON SITE

COPYRIGHT  
All rights reserved.  
These drawings, plans and specifications and the copyright are the property of Engineering Studio and must not be used, reproduced or copied wholly or in part without the written permission of Engineering Studio.

**EngineeringStudio**  
CML & Structural  
Phone: (02) 8022 2880  
Email: info@engineeringstudio.com.au  
Web: www.engineeringstudio.com.au


Postal Address  
PO Box 7191  
BAULKHAM HILLS NSW 2153

**PROPOSED RESIDENCE**  
AT 60 DONCASTER AVENUE, CLAREMONT MEADOWS  
FOR DISTINCT INNOVATIONS

**STORMWATER DRAINAGE PLAN**


JOB NUMBER: 18519	DWG NUMBER: C02.01	ORIGINAL SIZE: A3
DESIGNED BY: O.G.	DATE: AUGUST 2018	
DRAWN BY: D.M.	SCALE: 1:200 U.N.O.	






**BELOW GROUND ON-SITE DETENTION TANK**  
 1:50


**SECTION 1**  
 1:20



**ORIFICE PLATE DETAIL**  
 1:10  
 REFER TO ON-SITE DETENTION SUMMARY FOR ORIFICE DIAMETER



**STANDARD TRASH SCREEN**  
 NTS



**STEP IRONS FOR DRAINAGE PITS**  
 1:20

NOTE: DO NOT SCALE OFF DRAWINGS. REFER TO ARCHITECTURAL PLANS. VERIFY DIMENSIONS ON SITE

REV	DATE	DESCRIPTION	BY
B	27.08.18	RE-ISSUED FOR APPROVAL	O.G.
A	23.08.18	ISSUED FOR APPROVAL	D.M.

COPYRIGHT  
 All rights reserved.  
 These drawings, plans and specifications and the copyright are the property of Engineering Studio and must not be used, reproduced or copied wholly or in part without the written permission of Engineering Studio.

**EngineeringStudio**  
 CML & Structural

Phone: (02) 8020 2880  
 Email: info@engineeringstudio.com.au  
 Web: www.engineeringstudio.com.au

Postal Address  
 PO Box 7191  
 BAULKHAM HILLS NSW 2153

**PROPOSED RESIDENCE**  
 AT 60 DONCASTER AVENUE, CLAREMONT MEADOWS  
 FOR DISTINCT INNOVATIONS

**STORMWATER DETAILS SHEET 1**

JOB NUMBER: 18519	DWG NUMBER: C02.02	ORIGINAL SIZE: A3
DESIGNED BY: O.G.	DATE: AUGUST 2018	
DRAWN BY: D.M.	SCALE: 1:20 U.N.O	





TABLE A			
RAINWATER TANK LOCATION	METER SIZE (mm)	TYPE OF TAP	TYPE OF BACKFLOW PREVENTION
ABOVE GROUND	20	BALL VALVE	DUAL CHECK VALVE (COMBINED WITH METER)
	25	BALL VALVE	DUAL CHECK VALVE
	> 32	BALL VALVE	DUAL CHECK VALVE
BELOW GROUND	20	BALL VALVE	TESTABLE DOUBLE CHECK VALVE
	25	BALL VALVE	TESTABLE DOUBLE CHECK VALVE
	> 32	BALL VALVE	TESTABLE DOUBLE CHECK VALVE

LEGEND	
	PRESSURE VESSEL
	METER
	BALL VALVE RIGHT ANGLE TYPE
	DUAL CHECK VALVE
	PUMP
	GARDEN TAP
	DRINKING WATER SUPPLY PIPES
	RAINWATER SUPPLY PIPES
	DOWN PIPES

- DIAGRAM NOTES:**
- DRAWING TO BE READ IN CONJUNCTION WITH SYDNEY WATER PLUMBING REQUIREMENTS
  - FOR TANKS 10,000 LITRES OR LESS, COUNCIL DEVELOPMENT CONSENT IS NOT REQUIRED, IF THEIR CONDITIONS FOR INSTALLATION ARE FOLLOWED.
  - FOR TANKS GREATER THAN 10,000 LITRES COUNCIL DEVELOPMENT CONSENT IS GENERALLY REQUIRED.
  - FOR TANKS MORE THAN 10,000 LITRES APPROVAL IS REQUIRED FOR BUILDING OVER SEWERS.
  - SYDNEY WATER'S APPROVAL IS REQUIRED FOR ANY TOP UP FROM DRINKING WATER SUPPLY, REGARDLESS OF TANK SIZE. NO DIRECT CONNECTION IS ALLOWED BETWEEN THE DRINKING WATER SUPPLY AND THE RAINWATER TANK SUPPLY.
  - RAINWATER PIPEWORK IS SHOWN ON THE DIAGRAM AS SUPPLYING INTERNAL AND EXTERNAL RAINWATER USES. CUSTOMERS MAY WANT ONE OR THE OTHER.
  - ANY DESIGNED ACCESS LID INTO RAINWATER RE-USE TANK IS TO HAVE A LOCKABLE LID. IF THE LID IS DESIGNED TO BE ACCESSED BY A MAINTENANCE PERSON, IT MUST BE AT LEAST 600 mm x 900 mm IN SIZE.




## DUAL DRINKING WATER & RAINWATER SUPPLY DIAGRAM

N.T.S.


## TYPICAL FIRST FLUSH DETAIL

N.T.S.



## TYPICAL EAVES GUTTER DETAIL

1:20



## RAINWATER HEAD SECTION

N.T.S.  
W \* = WIDTH OF BOX GUTTER AS PER PLAN NOTE.

NOTE: DO NOT SCALE OFF DRAWINGS. REFER TO ARCHITECTURAL PLANS. VERIFY DIMENSIONS ON SITE

REV	DATE	DESCRIPTION	BY
B	27.08.18	RE-ISSUED FOR APPROVAL	O.G.
A	23.08.18	ISSUED FOR APPROVAL	D.M.

**COPYRIGHT**  
All rights reserved.  
These drawings, plans and specifications and the copyright are the property of Engineering Studio and must not be used, reproduced or copied wholly or in part without the written permission of Engineering Studio.



Phone: (02) 8022 2880  
Email: info@engineeringstudio.com.au  
Web: www.engineeringstudio.com.au

Postal Address  
PO Box 7191  
BAULKHAM HILLS NSW 2153

**PROPOSED RESIDENCE**  
AT 60 DONCASTER AVENUE, CLAREMONT MEADOWS  
FOR DISTINCT INNOVATIONS

## STORMWATER DETAILS SHEET 2

JOB NUMBER: 18519	DWG NUMBER: C02.03	ORIGINAL SIZE: A3
DESIGNED BY: O.G.	DATE: AUGUST 2018	
DRAWN BY: D.M.	SCALE: 1:20 U.N.O	





# meadows house

## bellino

### no.60 doncaster ave claremont meadows nsw

#### architectural list:

- page 01 cover page, site plan, basix and roof plan
- page 02 floor plans
- page 03 elevations and sections

#### 1. FALLS, SLIPS, TRIPS

##### a) WORKING AT HEIGHTS

###### DURING CONSTRUCTION

Wherever possible, components for this building should be prefabricated off-site or at ground level to minimise the risk of workers falling more than two metres. However, construction of this building will require workers to be working at heights where a fall of two metres is possible and injury is likely to result from such a fall. The builder should provide suitable barriers wherever a person is required to work in a situation where falling more than two metres is a possibility.

###### DURING OPERATION OR MAINTENANCE

For houses or other low-rise buildings where scaffolding is required, the owner is responsible for ensuring that the scaffolding is erected, maintained and dismantled in accordance with relevant codes of practice. Cleaning and maintenance of windows, walls, roof or other external surfaces of this building will require persons to be situated where a fall from a height of two metres is possible. Where this type of activity is required, scaffolding, fall barriers or Personal Protective Equipment (PPE) should be used in accordance with relevant codes of practice, regulations or legislation.

###### FLOOR FINISHES

If broken have been specified by designer, these have been selected to minimise the risk of floors and paved areas becoming slippery when wet or when walked on with shoes/feet. Any changes to the specified finish should be made in consultation with the designer or, if this is not practical, surfaces with an equivalent or better slip resistance should be chosen.

###### FLOOR FINISHES BY OWNER

If broken have been specified by designer, these have been selected to minimise the risk of floors and paved areas becoming slippery when wet or when walked on with shoes/feet. Any changes to the specified finish should be made in consultation with the designer or, if this is not practical, surfaces with an equivalent or better slip resistance should be chosen.

###### STEPS, LOOSE OBJECTS AND UNEVEN SURFACES

For buildings where scaffolding, ladders, ladders or other components of this building will require persons to be situated where a fall from a height of two metres is possible, Where this type of activity is required, scaffolding, fall barriers or Personal Protective Equipment (PPE) should be used in accordance with relevant codes of practice, regulations or legislation.

###### WORKING AT HEIGHTS

Wherever possible, components for this building should be prefabricated off-site or at ground level to minimise the risk of workers falling more than two metres. However, construction of this building will require workers to be working at heights where a fall of two metres is possible and injury is likely to result from such a fall. The builder should provide suitable barriers wherever a person is required to work in a situation where falling more than two metres is a possibility.

###### DURING CONSTRUCTION

Wherever possible, components for this building should be prefabricated off-site or at ground level to minimise the risk of workers falling more than two metres. However, construction of this building will require workers to be working at heights where a fall of two metres is possible and injury is likely to result from such a fall. The builder should provide suitable barriers wherever a person is required to work in a situation where falling more than two metres is a possibility.

###### DURING OPERATION OR MAINTENANCE

For houses or other low-rise buildings where scaffolding is required, the owner is responsible for ensuring that the scaffolding is erected, maintained and dismantled in accordance with relevant codes of practice. Cleaning and maintenance of windows, walls, roof or other external surfaces of this building will require persons to be situated where a fall from a height of two metres is possible. Where this type of activity is required, scaffolding, fall barriers or Personal Protective Equipment (PPE) should be used in accordance with relevant codes of practice, regulations or legislation.

###### FLOOR FINISHES

If broken have been specified by designer, these have been selected to minimise the risk of floors and paved areas becoming slippery when wet or when walked on with shoes/feet. Any changes to the specified finish should be made in consultation with the designer or, if this is not practical, surfaces with an equivalent or better slip resistance should be chosen.

###### STEPS, LOOSE OBJECTS AND UNEVEN SURFACES

For buildings where scaffolding, ladders, ladders or other components of this building will require persons to be situated where a fall from a height of two metres is possible, Where this type of activity is required, scaffolding, fall barriers or Personal Protective Equipment (PPE) should be used in accordance with relevant codes of practice, regulations or legislation.

###### WORKING AT HEIGHTS

Wherever possible, components for this building should be prefabricated off-site or at ground level to minimise the risk of workers falling more than two metres. However, construction of this building will require workers to be working at heights where a fall of two metres is possible and injury is likely to result from such a fall. The builder should provide suitable barriers wherever a person is required to work in a situation where falling more than two metres is a possibility.

###### DURING CONSTRUCTION

Wherever possible, components for this building should be prefabricated off-site or at ground level to minimise the risk of workers falling more than two metres. However, construction of this building will require workers to be working at heights where a fall of two metres is possible and injury is likely to result from such a fall. The builder should provide suitable barriers wherever a person is required to work in a situation where falling more than two metres is a possibility.

###### DURING OPERATION OR MAINTENANCE

For houses or other low-rise buildings where scaffolding is required, the owner is responsible for ensuring that the scaffolding is erected, maintained and dismantled in accordance with relevant codes of practice. Cleaning and maintenance of windows, walls, roof or other external surfaces of this building will require persons to be situated where a fall from a height of two metres is possible. Where this type of activity is required, scaffolding, fall barriers or Personal Protective Equipment (PPE) should be used in accordance with relevant codes of practice, regulations or legislation.

###### FLOOR FINISHES

If broken have been specified by designer, these have been selected to minimise the risk of floors and paved areas becoming slippery when wet or when walked on with shoes/feet. Any changes to the specified finish should be made in consultation with the designer or, if this is not practical, surfaces with an equivalent or better slip resistance should be chosen.

###### STEPS, LOOSE OBJECTS AND UNEVEN SURFACES

For buildings where scaffolding, ladders, ladders or other components of this building will require persons to be situated where a fall from a height of two metres is possible, Where this type of activity is required, scaffolding, fall barriers or Personal Protective Equipment (PPE) should be used in accordance with relevant codes of practice, regulations or legislation.

###### WORKING AT HEIGHTS

Wherever possible, components for this building should be prefabricated off-site or at ground level to minimise the risk of workers falling more than two metres. However, construction of this building will require workers to be working at heights where a fall of two metres is possible and injury is likely to result from such a fall. The builder should provide suitable barriers wherever a person is required to work in a situation where falling more than two metres is a possibility.

###### DURING CONSTRUCTION

Wherever possible, components for this building should be prefabricated off-site or at ground level to minimise the risk of workers falling more than two metres. However, construction of this building will require workers to be working at heights where a fall of two metres is possible and injury is likely to result from such a fall. The builder should provide suitable barriers wherever a person is required to work in a situation where falling more than two metres is a possibility.

###### DURING OPERATION OR MAINTENANCE

For houses or other low-rise buildings where scaffolding is required, the owner is responsible for ensuring that the scaffolding is erected, maintained and dismantled in accordance with relevant codes of practice. Cleaning and maintenance of windows, walls, roof or other external surfaces of this building will require persons to be situated where a fall from a height of two metres is possible. Where this type of activity is required, scaffolding, fall barriers or Personal Protective Equipment (PPE) should be used in accordance with relevant codes of practice, regulations or legislation.

###### FLOOR FINISHES

If broken have been specified by designer, these have been selected to minimise the risk of floors and paved areas becoming slippery when wet or when walked on with shoes/feet. Any changes to the specified finish should be made in consultation with the designer or, if this is not practical, surfaces with an equivalent or better slip resistance should be chosen.

###### STEPS, LOOSE OBJECTS AND UNEVEN SURFACES

For buildings where scaffolding, ladders, ladders or other components of this building will require persons to be situated where a fall from a height of two metres is possible, Where this type of activity is required, scaffolding, fall barriers or Personal Protective Equipment (PPE) should be used in accordance with relevant codes of practice, regulations or legislation.

###### WORKING AT HEIGHTS


Wherever possible, components for this building should be prefabricated off-site or at ground level to minimise the risk of workers falling more than two metres. However, construction of this building will require workers to be working at heights where a fall of two metres is possible and injury is likely to result from such a fall. The builder should provide suitable barriers wherever a person is required to work in a situation where falling more than two metres is a possibility.

###### DURING CONSTRUCTION


Wherever possible, components for this building should be prefabricated off-site or at ground level to minimise the risk of workers falling more than two metres. However, construction of this building will require workers to be working at heights where a fall of two metres is possible and injury is likely to result from such a fall. The builder should provide suitable barriers wherever a person is required to work in a situation where falling more than two metres is a possibility.

###### DURING OPERATION OR MAINTENANCE

For houses or other low-rise buildings where scaffolding is required, the owner is responsible for ensuring that the scaffolding is erected, maintained and dismantled in accordance with relevant codes of practice. Cleaning and maintenance of windows, walls, roof or other external surfaces of this building will require persons to be situated where a fall from a height of two metres is possible. Where this type of activity is required, scaffolding, fall barriers or Personal Protective Equipment (PPE) should be used in accordance with relevant codes of practice, regulations or legislation.




roof plan. (scale 1:100)



- water
- The applicant must plant indigenous or low water use species of vegetation throughout the area of land specified for the dwelling in the Indigenous species column of the table on the basic certificate as private landscaping for that dwelling with a volume exceeding 40KL.
  - The applicant must not install a private swimming pool or spa for the dwelling and to run off from 310KL.
  - The applicant must install a rainwater tank of at least 7000 litres and to run off from 310KL.
  - All showerheads 3 star
  - All toilet flushing 4 star
  - All bathroom taps 4 star
  - rainwater tank must be connected to toilets, laundry and used for landscaping.
- energy
- The applicant must install a gas instant 6 stars
  - The applicant must install a air conditioner 3 phase EER 3.5-4.0
  - The applicant must install a solar heating only to pool
  - The applicant must install a gas cooktop and electric oven
  - The applicant must photovoltaic system of 1.5kw.
  - Indoor and outdoor clothesline must be fitted

## basix details- new home

certificate no: 951908M-02 date: 29th August 2018  
summary must be read inconjunction with certificate



## sediment fence. nts

### general notes and specifications (applies to all pages )

- It is the responsibility of the builder/owner to check & verify all boundaries, dimensions & building details prior to construction to ensure the work can be carried out as required. Any discrepancies must be related back to the designer before commencement of works.
- All work to be in accordance with BCA & local council by-laws.
- Do not scale off drawings, use figured dimensions
- All stormwater drains to be discharged into street gutter or registered drainage easement. Refer to hydraulic engineers details.
- All wall frames and roof trusses to be in accordance with AS1684 Framing Code
- All timber beams to be as per engineers details and/or AS1684 framing code.
- All RC floor slab and structural beams to engineers details.
- All downpipes to be located by roof plumber or otherwise as noted on hydraulic engineers plans.
- Termite protection AS3602.1 Kordon space or similar
- This drawing must be read inconjunction with all other approved plans / documents by other consultants related to this specific object.
- Whilst every effort is made to obtain approval, the client acknowledges that we cannot guarantee approval as circumstances may arise which we are beyond our control.
- Licence for the use of the documentation for statutory approvals or any form of construction remains the sole property of Distinct Innovations Pty Ltd. All designs and plans are the subject of Copyright Laws and remain the sole property of Distinct Innovations Pty Ltd. You will have non-exclusive right to use the design/plans for the purposes of this project only. You cannot use or make copies of such documents unless approval is granted by us in writing. In the event that you breach any obligation to make a payment to us, a notice of termination of agreement will be issued noting that approval to use all designs, plans and documentation has been revoked. If such is to occur, all documents, plans and designs and all copies thereof must be returned to us writing in 14 days of the date of issue of the notice of termination.
- We take no responsibility for the details or specifications in the plans/documentation of consultants that have been engaged in respect of this project. It is the responsibility of the superintendents to check and verify all details prior to construction to satisfy him or herself that work can be carried out as required. Any discrepancies must be immediately relayed back to us prior to the commencement of works or directly to the consultant who prepared the details.
- Distinct Innovations Pty Ltd at no time purports to be quantity surveyors for the purposes of estimating construction costs and meeting budgets. Although we can provide you with a ballpark guide to costs, we cannot formally advise you of actual costs of construction. This must only be done by a suitably qualified quantity surveyor or builder. Any opinion is expressed or otherwise given informally and is not to be taken as a construction cost or quotation.
- Distinct Innovations Pty Ltd expressly takes no responsibility for the estimates, quotes or workmanship provided to you by any consultants, building/construction companies or any other firm or person.
- Prior to proceeding with Distinct Innovations Pty Ltd, it is your expressed responsibility to satisfy yourself that all services are available to the site for the sole purpose of this developments. Contact your relevant government bodies in relation to all services and utilities to ensure that this development can be fulfilled in every aspect. Distinct Innovations Pty Ltd will take no responsibility for inaccessible services to the development site.
- Before building works commence it is the superintendents responsibility to ensure final architectural plans are read in conjunction with all associated plans and documents provided by other consultants and covenants related to this project. Distinct Innovations Pty Ltd takes no responsibility for errors or omissions in this regard.
- Prior to excavation you must call Dial before you Dig.
- All work safety procedures must be conducted in the proper manner as per the new legislation WHS act 2011.


## area calculations

site area	950m2
proposed new dwelling	
living	385.94m2
alfresco/patio	61.22m2
garage	62.82m2
total area	509.98m2 54.89squares
granny flat	60.00m2
landscape area	488.00m2 or 51.3%

 <b>Distinct Innovations</b> environment • lifestyle • architecture w: <a href="http://distinctinnovations.com.au">distinctinnovations.com.au</a> e: <a href="mailto:email@distinctinnovations.com.au">email@distinctinnovations.com.au</a>	p: 02 8890 6156	amendments	date	amendments	date	client / project: proposed new dwelling bellino no.60 doncaster ave claremont meadows	title: development application	north: 	scale: 1:200 1:100 page no: 1 of 3 drawn: vj	copyright date: july 2018 drawing no: 1690 checked:	 <b>BUILDING DESIGNERS ASSOCIATION</b> OF NEW SOUTH WALES INC. Accredited Building Designer No: 6164





LANDSCAPE CONCEPT PLAN



INDICATIVE SPECIES LIST			NOTES			MASS PLANTING IN EXISTING TOPSOIL		
BOTANICAL NAME	COMMON NAME	MATURE HEIGHT	POT SIZE	QUANTITY				
GROUND COVER (TYPE A)								
<i>Tulbaghia violacea</i>	Society Garlic	30-40cm	150mm	25				
SCREEN TREES & SHRUBS								
<i>Syzygium Resilience</i>	Lilly Pilly	3-4m	200mm	20				
<i>Gardenia augusta "Florida"</i>	Florists Gardenia	1-1.5m	150mm	11				
<i>Hebe franciscana "Blue Gem"</i>	Hebe	1-1.5m	150mm	10				
FEATURE SHRUB								
<i>Acacia cognata "Limalight"</i>	Weeping Acacia	0.5-1.0m	200mm	16				
FEATURE TREE								
<i>Lagerstroemia indica "Cavendish"</i>	Crape Myrtle	3-7m	45 litre	2				
<i>Elaeagnus argentea</i>	Blueberry Ash	8-10m	45 litre	6				
CANOPY TREE								
<i>Eucalyptus sideroxylon</i>	Mugga Ironbark	8-10m	45 litre	2				
PLANTING NOTES								
GROUND COVER TYPE "A" TO BE PLANTED AT 2 - 3 PER SQM								
Bio Engineered Solutions Pty. Ltd.			DESIGNED: JKN			SCALES: 1:100 FOR A1		
Landscape design and Environmental Management			DRAWN: JKN			CLIENT: MR & MRS BELLINO		
3 TERRIMONT RD WARRIMOO, 2774			CHECKED: _____			PROPOSED SINGLE DWELLING DEVELOPMENT		
EMAIL: bio_engineered_solutions@bigpond.com.au			APPROVED: _____ DATE: _____			No 60 DONCASTER AVENUE, CLAREMONT MEADOWS		
ABN: 83 104865219			Ph: (02) 4753 6614			LANDSCAPE CONCEPT PLAN		
DATE: 5/9/16			DATE: 23/8/16			PLAN No. 1789LAN1 B		
DATE: 23/8/16			DATE: 23/8/16			FILE No. 1789LAN		
DATE: 23/8/16			DATE: 23/8/16			SHEET 1 OF 1 SHEETS		





1 within the "Area of garden and lawn" for the dwelling specified in the "Description of Project" table).

