

# PENRITH CITY COUNCIL

## NOTICE OF DETERMINATION

### DESCRIPTION OF DEVELOPMENT

Application number:	DA21/0301
Description of development:	Single storey dwelling and OSSM
Classification of development:	Class 1a

### DETAILS OF THE LAND TO BE DEVELOPED

Legal description:	Lot 3 DP 1242079
Property address:	13 - 15 Vane Street, CRANEBROOK NSW 2749

### DETAILS OF THE APPLICANT

Name & Address:	Lynt Pty Ltd 162-178 Aldington Road KEMPS CREEK NSW 2178
-----------------	--

### DECISION OF CONSENT AUTHORITY

In accordance with Section 4.18(1) (a) of the Environmental Planning and Assessment Act 1979, consent is granted subject to the conditions listed in attachment 1.

Please note that this consent will lapse on the expiry date unless the development has commenced in that time.

Date from which consent operates	9 August 2021
Date the consent expires	9 August 2026
Date of this decision	9 August 2021

### POINT OF CONTACT

If you have any questions regarding this determination you should contact:

Assessing Officer:	Paul Buttigieg
Contact telephone number:	+612 4732 8207

## NOTES

---

### **Reasons**

The conditions in the attached schedule have been imposed in accordance with Section 4.17 of the Environmental Planning and Assessment Act 1979 as amended.

### **Conditions**

Your attention is drawn to the attached conditions of consent in attachment 1.

### **Certification and advisory notes**

You should also check if this type of development requires a construction certificate in addition to this development consent.

It is recommended that you read any Advisory Note enclosed with this notice of determination.

### **Review of determination**

The applicant may request Council to review its determination pursuant to Division 8.2 of the Environmental Planning and Assessment Act 1979 within twelve months of receiving this Notice of Determination.

These provisions do not apply to designated development, complying development or crown development pursuant to Section 8.2(2) of the Environmental Planning and Assessment Act 1979.

### **Appeals in the Land and Environment Court**

The applicant can appeal against this decision in the Land and Environment Court within twelve months of receiving this Notice of Determination.

There is no right of appeal to a decision of the Independent Planning Commission or matters relating to a complying development certificate pursuant to clause 8.6(3) of the Environmental Planning and Assessment Act 1979.

### **Designated development**

If the application was for designated development and a written objection was made in respect to the application, the objector can appeal against this decision to the Land and Environment Court within 56 days after the date of this notice.

If the applicant appeals against this decision, objector(s) will be given a notice of the appeal and the objector(s) can apply to the Land and Environment Court within 56 days after the date of this appeal notice to attend the appeal and make submissions at that appeal.

### **Sydney Western City Planning Panels**

If the application was decided by the Sydney Western City Planning Panel, please refer to Section 2.16 of the Environmental Planning and Assessment Act, 1979 (as amended) for any further regulations.

# ATTACHMENT 1: CONDITIONS OF CONSENT

## General

1 The development must be implemented substantially in accordance with the plans drawn by LYMT, numbered 20014 and dated 3/06/21 Rev 05, and stamped approved by Council, the application form, the BASIX Certificate and any supporting information received with the application, except as may be amended in red on the attached plans and by the following conditions.

2 The work must be carried out in accordance with the requirements of the Building Code of Australia. If the work relates to a residential building and is valued in excess of \$20,000, then a contract of insurance for the residential development shall be in force in accordance with Part 6 of the Home Building Act 1989.

{Note: Residential building includes alterations and additions to a dwelling, and structures associated with a dwelling house/dwelling such as a carport, garage, shed, rural shed, swimming pool and the like}.

3 **The development shall not be used or occupied until an Occupation Certificate has been issued.**

4 A **Construction Certificate** shall be obtained prior to commencement of any building works.

5 The building shall be constructed in accordance with the provisions of "Planning for Bushfire Protection" November 2019, and to BAL-29 construction under AS3959-2018 "Construction of buildings in bushfire-prone areas.

And,

Prior to the issue of an **Occupation Certificate** the principal certifier shall ensure the recommendations detailed in Bushfire Assessment Report carried out by Australian Bushfire Consulting Services numbered 21-188 and dated 23rd April 2021 have been met.

## Demolition

6 Dust suppression techniques are to be employed during construction to reduce any potential nuisances to surrounding properties.

7 Mud and soil from vehicular movements to and from the site must not be deposited on the road.

## Environmental Matters

8 Erosion and sediment control measures shall be installed **prior to the commencement of works on site** including approved clearing of site vegetation. The erosion and sediment control measures are to be maintained in accordance with the approved erosion and sediment control plan(s) for the development.

The approved sediment and erosion control measures are to be installed **prior to and maintained throughout the construction phase of the development until the land, that was subject to the works, have been stabilised and grass cover established.** These measures shall ensure that mud and soil from vehicular movements to and from the site does not occur during the construction of the development.

- 9 No fill material is to be imported to the site without the prior approval of Penrith City Council in accordance with Sydney Regional Environmental Plan No.20 (Hawkesbury- Nepean River) (No.2-1997). No recycling of material for use as fill material shall be carried out on the site without the prior approval of Council.
- 10 No fill material shall be imported to the site until such time as a Validation Certificate(with a copy of any report forming the basis for the validation) for the fill material has been submitted to, considered and approved by Council. The Validation Certificate shall:
- state the legal property description of the fill material source site,
  - be prepared by an appropriately qualified person (as defined in Penrith Contaminated Land Development Control Plan) with consideration of all relevant guidelines (e.g. EPA, ANZECC, NH&MRC), standards, planning instruments and legislation,
  - clearly indicate the legal property description of the fill material source site,
  - provide details of the volume of fill material to be used in the filling operations,
  - provide a classification of the fill material to be imported to the site in accordance with the Environment Protection Authority's "Environmental Guidelines: Assessment, Classification & Management of Non-Liquid Wastes" 1997, and
  - (based on the fill classification) determine whether the fill material is suitable for its intended purpose and land use and whether the fill material will or will not pose an unacceptable risk to human health or the environment.

{Note: Penrith Contaminated Land Development Control Plan defines an appropriately qualified person as "a person who, in the opinion of Council, has a demonstrated experience, or access to experience in hydrology, environmental chemistry, soil science, eco-toxicology, sampling and analytical procedures, risk evaluation and remediation technologies. In addition, the person will be required to have appropriate professional indemnity and public risk insurance."}

If the Principal Certifying Authority or Penrith City Council is not satisfied that suitable fill materials have been used on the site, further site investigations or remediation works may be requested. In these circumstances the works shall be carried out prior to any further approved works.

- 11 All waste materials stored on-site are to be contained within a designated area such as a waste bay or bin to ensure that no waste materials are allowed to enter the stormwater system or neighbouring properties. The designated waste storage areas shall provide at least two waste bays / bins so as to allow for the separation of wastes, and are to be fully enclosed when the site is unattended.
- 12 All excavated material and other wastes generated as a result of the development are to be re-used, recycled or disposed of in accordance with the waste management plan.

Waste materials not specified in the waste management plan are to be disposed of at a lawful waste management facility. Where the disposal location or waste materials have not been identified in the waste management plan, details shall be provided to the Certifying Authority as part of the waste management documentation accompanying the Construction Certificate application.

All receipts and supporting documentation must be retained in order to verify lawful disposal of materials and are to be made available to Penrith City Council on request.

- 13 The operating noise level of plant and equipment shall not exceed 5dB(A) above the background noise level when measured at the boundaries of the premises. The provisions of the Protection of the Environment Operations Act 1997 apply to the development, in terms of regulating offensive noise.

## BCA Issues

14 All aspects of the building design shall comply with the applicable performance requirements of the Building Code of Australia so as to achieve and maintain acceptable standards of structural sufficiency, safety (including fire safety), health and amenity for the on-going benefit of the community. Compliance with the performance requirements can only be achieved by:

- (a) complying with the deemed to satisfy provisions, or
- (b) formulating an alternative solution which:
  - complies with the performance requirements, or
  - is shown to be at least equivalent to the deemed to satisfy provision, or
- (c) a combination of (a) and (b).

## Health Matters and OSSM installations

15 The rainwater tank must be maintained so as not to create a nuisance and it must be protected against mosquito infestation.

## Construction

16 Stamped plans, specifications, a copy of the development consent, the Construction Certificate and any other Certificates to be relied upon shall be available on site at all times during construction.

The following details are to be displayed in a maximum of 2 signs to be erected on the site:

- the name of the Principal Certifying Authority, their address and telephone number,
- the name of the person in charge of the work site and telephone number at which that person may be contacted during work hours,
- that unauthorised entry to the work site is prohibited,
- the designated waste storage area must be covered when the site is unattended, and
- all sediment and erosion control measures shall be fully maintained until completion of the construction phase.

Signage but no more than 2 signs stating the above details is to be erected:

- at the commencement of, and for the full length of the, construction works onsite, and
- in a prominent position on the work site and in a manner that can be easily read by pedestrian traffic.

All construction signage is to be removed when the Occupation Certificate has been issued for the development.

17 Prior to the commencement of construction works:

(a) Toilet facilities at or in the vicinity of the work site shall be provided at the rate of one toilet for every 20 persons or part of 20 persons employed at the site. Each toilet provided must be:

- a standard flushing toilet connected to a public sewer, or
- if that is not practicable, an accredited sewage management facility approved by the council, or
- alternatively, any other sewage management facility approved by council.

(b) All excavations and backfilling associated with the erection or demolition of a building must be executed safely and in accordance with the appropriate professional standards. All excavations associated with the erection or demolition of a building must be properly guarded and protected to prevent them from being dangerous to life or property.

(c) If an excavation associated with the erection or demolition of a building extends below the level of the base of the footings of a building on an adjoining allotment of land, the person causing the excavation to be made:

- must preserve and protect the building from damage, and
- if necessary, must underpin and support the building in an approved manner, and
- must, at least 7 days before excavating below the level of the base of the footings of a building on an adjoining allotment of land, give notice of intention to do so to the owner of the adjoining allotment of land and furnish particulars of the excavation to the owner of the building being erected or demolished. The owner of the adjoining allotment of land is not liable for any part of the cost of work carried out for the purposes of this condition, whether carried out on the allotment of land being excavated or on the adjoining allotment of land, (includes a public road and any other public place).

18 The approved waste management plan must be implemented on-site and adhered to throughout all stages of the development including demolition, with supporting documentation / receipts retained in order to verify the recycling and disposal of materials in accordance with the approved plan.

19 The building shall be set out by a registered surveyor. A Survey Certificate shall be undertaken and submitted to the Principal Certifying Authority when the building is constructed.

20 The roof of the structure is to be a dull, non-reflective surface and colour. The external finishes of the dwelling are to compliment and blend with the established streetscape and amenity of the area.

21 The rainwater tank(s) is to be:

- erected on a self-supporting base in the approved location on the property in accordance with the stamped-approved site plans for the development,
- structurally sound and constructed in accordance with AS/NZS 3500 1.2- 1998: National Plumbing and Drainage - Water Supply - Acceptable Solutions,
- fully enclosed and all openings sealed to prevent access by mosquitoes,
- fitted with a first flush device,
- fitted with a trickle system to top up from mains water,
- provided with an air gap, and
- installed by a licensed plumber in accordance with Sydney Water's "Plumbing requirements Information for rainwater tank suppliers and plumbers April 2003" and the NSW Code of Practice: Plumbing and Drainage.

Additionally, the following are to be provided:

- A back flow prevention device shall be provided at the water meter in accordance with Sydney Water requirements.
- In the event of a power failure, a back up supply of mains water shall be provided to at least one toilet in

the dwelling.

- The rainwater tank(s) and associated piping is to be labelled 'Rainwater - Not for Drinking' in accordance with Sydney Water requirements.
- The rainwater tank and pipework is to be painted in colours matching the external finishes of the dwelling and is to be of non-reflective finish.
- The overflow for the rainwater tank is to be connected into the existing stormwater disposal system on the site.

Before a rainwater tank(s) can be used, a certificate or suitable document is to be submitted to the Principal Certifying Authority stating that the rainwater tank has been installed in accordance with:

- the manufacturer's specifications, and
- Sydney Water and NSW Health requirements

This certificate or documentation is to be provided by the licensed plumber who installed the rainwater tank on the property, and is to be submitted prior to the issue of the Occupation Certificate.

- 22 The catchment area (for the rainwater tank) includes the parts of the roof of the dwelling(s) from which water is collected and includes gutters. To ensure a safe supply of water:
- roof catchment areas must be kept clear of overhanging vegetation,
  - gutters must have sufficient fall to downpipes to prevent pooling of water,
  - overflow, discharge from bleed off pipes from roof mounted appliances such as airconditioners, hot water services and solar heaters must not discharge into the rainwater catchment area,
  - for roofs containing lead based, tar based or asbestos material the tank supply must not be connected to drinking, bathing and gardening tap water outlets,
  - appropriate measures must be installed to prevent foreign materials from contaminating the water which enters the rainwater tank.
- 23 The rainwater tank supply must not be connected to drinking and bathing water tap outlets.
- 24 The pump must not exceed 5dBA above ambient background noise level at the nearest residential property boundary. The provisions of the Protection of the Environment Operations Act 1997 apply to the development, in terms of regulating offensive noise.
- 25 Construction works or subdivision works that are carried out in accordance with an approved consent that involve the use of heavy vehicles, heavy machinery and other equipment likely to cause offence to adjoining properties shall be restricted to the following hours in accordance with the NSW Environment Protection Authority Noise Control Guidelines:
- Mondays to Fridays, 7am to 6pm
  - Saturdays, 7am to 1pm (if inaudible on neighbouring residential premises), otherwise 8am to 1pm
  - No work is permitted on Sundays and Public Holidays.

Other construction works carried out inside a building/tenancy and do not involve the use of equipment that emits noise are not restricted to the construction hours stated above.

The provisions of the Protection of the Environment Operations Act, 1997 in regulating offensive noise also apply to all construction works.

## Engineering

- 26 All land required for vehicular access within the site is to be stabilised.
- 27 An Infrastructure Restoration Bond is to be lodged with Penrith City Council for development involving works around Penrith City Council's Public Infrastructure Assets. The bond is to be lodged with Penrith City Council prior to commencement of any works on site or prior to the issue of any Construction Certificate, whichever occurs first. The bond and applicable fees are in accordance with Council's adopted Fees and Charges.

An application form together with an information sheet and conditions are available on Council's website.

Contact Penrith City Council's City Works Department on (02) 4732 7777 or visit Penrith City Council's website for more information.

- 28 All roadworks, stormwater drainage works, signage, line marking, associated civil works and dedications required to effect the consented development shall be undertaken by the applicant at no cost to Penrith City Council.
- 29 Prior to the issue of any Construction Certificate, a Section 138 Roads Act application, including payment of application and inspection fees together with any applicable bonds, shall be lodged with and approved by Penrith City Council (being the Roads Authority for any works required in a public road). These works may include but are not limited to the following:
- a) Vehicular crossings (including kerb reinstatement of redundant vehicular crossings)
  - b) Concrete footpaths and or cycleways
  - c) Road opening for utilities and stormwater (including stormwater connection to Penrith City Council roads and other Penrith City Council owned drainage)
  - d) Road occupancy or road closures (including temporary construction work zones and tower crane operation)
  - e) The placement of hoardings, structures, containers, waste skips, signs etc. in the road reserve
  - f) Temporary construction access
  - g) Temporary ground anchors (for basement construction)

All works shall be carried out in accordance with the Roads Act approval, the development consent, including the stamped approved plans, and Penrith City Council's specifications, guidelines and best engineering practice.

Contact Penrith City Council's Asset Management Department on 4732 7777 or visit Penrith City Council's website for more information.

Note:

- Where Penrith City Council is the Certifier for the development, the Roads Act approval for the above works may be issued concurrently with the Construction Certificate or Subdivision Works Certificate.
- Separate approval may be required from Transport for NSW for classified roads.
- All works associated with the Roads Act approval must be completed prior to the issue of any Occupation Certificate or Subdivision Certificate as applicable.
- On completion of any awning over the road reserve, a certificate from a practising structural engineer

certifying the structural adequacy of the awning is to be submitted to Council before Council will inspect the works and issue its final approval under the Roads Act.

30 Stormwater drainage from the site shall be discharged to the level spreader system.

The stormwater drainage system shall be designed in accordance with Penrith City Council's Stormwater Drainage Specification for Building Developments. The design shall ensure that the development has no adverse impact on adjoining properties by the diversion, damming or concentration of stormwater flows.

The proposed method of stormwater discharge shall be detailed in the Construction Certificate or Subdivision Works Certificate issued by the Certifier.

31 Prior to the issue of any Occupation Certificate, the Principal Certifier shall ensure that all works associated with a S138 Roads Act consent have been inspected and signed off by Penrith City Council.

## **Landscaping**

32 All landscape works are to be constructed in accordance with the stamped approved plan and Sections F5 "Planting Techniques", F8 "Quality Assurance Standards", F9 "Site Management Plan" of Penrith Council's Landscape Development Control Plan.

Landscaping shall be maintained:

- in accordance with the approved plan, and
- in a healthy state, and
- in perpetuity by the existing or future owners and occupiers of the property.

If any of the vegetation comprising that landscaping dies or is removed, it is to be replaced with vegetation of the same species and, to the greatest extent practicable, the same maturity, as the vegetation which died or was removed.

33 No trees are to be removed, ringbarked, cut, topped or lopped or wilfully destroyed (other than those within the proposed building footprint or as shown on the approved plans) without the prior consent of Penrith City Council and in accordance with Council's Tree Preservation Order and Policy.

## **Payment of Fees**

34 Prior to the commencement of any works on site, all fees associated with Penrith City Council-owned land and infrastructure shall be paid to Council. These fees include Road Opening fees and Infrastructure Restoration fees.

## Certification

- 35 Prior to the commencement of any earthworks or construction works on site, the proponent is to:
- (a) employ a Principal Certifying Authority to oversee that the said works carried out on the site are in accordance with the development consent and related Construction Certificate issued for the approved development, and with the relevant provisions of the Environmental Planning and Assessment Act and accompanying Regulation, and
  - (b) submit a Notice of Commencement to Penrith City Council.

The Principal Certifying Authority shall submit to Council an "Appointment of Principal Certifying Authority" in accordance with Section 81A of the Environmental Planning and Assessment Act 1979.

### Information to accompany the Notice of Commencement

Two (2) days before any earthworks or construction/demolition works are to commence on site (including the clearing site vegetation), the proponent shall submit a "Notice of Commencement" to Council in accordance with Section 81A of the Environmental Planning and Assessment Act 1979.

- 36 An Occupation Certificate is to be obtained from the Principal Certifying Authority on completion of all works and prior to the occupation/use of the development.

The Certificate shall not be issued if any conditions of this consent, but not the conditions relating to the operation of the development, are outstanding.

A copy of the Occupation Certificate and all necessary documentation supporting the issue of the Certificate is to be submitted to Penrith City Council, if Council is not the Principal Certifying Authority.

## Operation of OSSM

- 37 The on-site sewage management (OSSM) system and effluent management area shall be installed and operated in accordance with the:
- "Environmental and Health Protection Guidelines On Site Sewage Management for Single Households"
  - Australian Standards AS1547:2012,
  - Council's On-Site Sewage Management and Greywater Reuse Policy,
  - current (at the time of installation) NSW Health Accreditation documentation,
  - the Wastewater Report prepared by Strategic Environmental an Engineering Consultancy Pty Ltd (dated 31 May 2021, ref 21000176), and
  - the Effluent Management Area Plan prepared by Strategic Environmental an Engineering Consultancy Pty Ltd (dated 31 May 2021, ref 21000176),
  - And, the conditions of this consent.

**Prior to the issue of the 'Approval to Operate', a Commissioning Certificate for the OSSM system shall be provided to Penrith City Council for approval.** This Certificate shall certify that the aerated wastewater treatment system (AWTS) has been installed and is operating in accordance with the conditions of its NSW Health accreditation documentation.

**Prior to the issue of the Occupation Certificate and before the OSSM system can be used, an 'Approval to Operate' for the OSSM system is to be sought from and issued by Penrith City Council.**

- 38 All wastewater generated on the site is to be diverted to an Aerated Wastewater Treatment System and be disposed of by way of pressure dosed absorption beds in the approved effluent management area. The effluent management area is to be located in accordance with the stamped approved Effluent Management Plan prepared by Strategic Environmental an Engineering Consultancy Pty Ltd (dated 31 May 2021, ref 21000176) and have a minimum area of 135m<sup>2</sup>.

The system and effluent management area are to be installed and managed in accordance with the:

- “Environmental and Health Protection Guidelines On Site Sewage Management for Single Households”
- Australian Standards AS 1547:2012,
- Council's On-Site Sewage Management and Greywater Reuse Policy,
- the Wastewater Report prepared by Strategic Environmental an Engineering Consultancy Pty Ltd (dated 31 May 2021, ref 21000176), and
- the Effluent Management Area Plan prepared by Strategic Environmental an Engineering Consultancy Pty Ltd (dated 31 May 2021, ref 21000176).

The system is to be utilised for a 2 bedroom dwelling in accordance with the Wastewater Report prepared by Strategic Environmental an Engineering Consultancy Pty Ltd (dated 31 May 2021, ref 21000176). Any dwelling approval on the site greater than this may require a new wastewater report for Council's consideration.

- 39 Penrith City Council is both the consent authority and certifying authority for the installation of the On-Site Sewage Management System (OSSM). **It is your responsibility to contact Council's Development Services Department to organise all inspections required for the installation of the system.**

In this regard, the septic tank(s) and disposal area(s) will need to be inspected on completion of the system's installation (before backfilling occurs) and prior to its commissioning, to ensure compliance with those conditions specific to the installation of the system.

A copy of the satisfactory inspection reports carried out by Council shall be submitted to the Principal Certifying Authority if Council is not the Principal Certifying Authority.

- 40 The septic tank, drainage and irrigation lines and effluent management area shall not be altered without the prior approval of Council. In addition, the septic tank shall not be buried or covered.
- 41 All house drainage and sanitary plumbing shall be carried out in accordance with the requirements of the Plumbing and Drainage Act 2011 and the Plumbing Code of Australia.
- 42 The design of the irrigation system for the effluent management area is to be such that:
- The distribution line is to be buried from the tank to the designated disposal area.
  - The moveable irrigation line and sprinklers (including the plume from the sprinklers) situated within the disposal area can not exceed the designated boundaries of the disposal area.
  - The treated wastewater can be evenly irrigated across the entire designated disposal area, **avoiding the drip line of native trees.**
- 43 The disposal area shall:
- the distribution line is to be buried from the tank to the designated disposal area;
  - the treated wastewater can be evenly irrigated across the entire designated disposal area;
  - be prepared with a minimum 100mm cover of absorbent soil that has been ripped into the existing top soil. The area to be prepared should include up to 2.5m either side of the trench;

- have an even grade / be graded to a minimum 1% crossfall and turfed in accordance with the stamped-approved plans.

44 There shall be no effluent runoff from the subject property to adjoining premises, public places or reserves.

45 A minimum of two signs shall be erected within the effluent management area. These signs are to state "RECLAIMED EFFLUENT - NOT FOR DRINKING - AVOID CONTACT". The signage shall be maintained for the term of the development.

46 The owner/occupier shall enter into an annual service contract with the manufacturer, distributor or other person authorised (in writing) by Penrith City Council to service the aerated septic tank(s) every three (3) months from the date of commissioning in the following manner:

i. A three monthly service shall include a check on all mechanical, electrical and functioning parts of the aerated system including:

- the chlorinator,
- replenishment of the disinfectant,
- the UV disinfection unit (if required),
- all pumps and switches,
- the air blower, fan or air venturi,
- the alarm system,
- the effluent disposal area and sub-surface irrigation lines and filters,
- the slime growth on the filter media, and
- the operation of the sludge returns system.

ii. The following field tests are to be carried out at every service:

- free residual chlorine using DPD colorimetric or photometric method,
- pH from a sample taken from the irrigation chamber,
- dissolved oxygen from a sample taken from the final aeration or stilling chamber (although recommended) is optional.

iii. On the yearly anniversary date of the commissioning of the system, an annual service of the system shall also be carried out which includes a check on the sludge accumulation in the septic tank (primary treatment tank) and the clarifier, where appropriate.

iv. For systems which utilise the sewage treatment principle of activated sludge or contact aeration, a sludge bulking test, known as a SV30 Test, shall also be conducted on an annual basis. This test is to determine whether the accumulated sludge is bulking, indicating that the aeration compartment(s) will require desludging.

v. On completion of each service, a service report sheet is to specify all service items and test results, the amount of chlorine compound provided, parts replaced (if applicable), the date the service was conducted and the technician's name. A copy of the service report is to be:

- given to the property owner and another to the applicant (if not the same), and
- forwarded to Penrith City Council.

Each service agent shall provide a registered business office which, if unattended during business hours, is provided with a telephone answering device or service. A means of reporting a malfunction or breakdown outside normal business hours shall be available. In the event of a breakdown or malfunction, the service agent shall, within 24 hours of the breakdown or malfunction, ensure that temporary repairs are carried out to the aerated system to ensure continued operation of the system. This may necessitate provision of adequate spare parts and temporary replacement blowers and irrigation pumps where repairs cannot be completed on site.

- 47 The effluent management area is to be turfed to the satisfaction of Council. Where a specific variety of turf is identified in the approved Wastewater Report that variety is to be installed and maintained.
- 48 No concreting, driveways, vehicles or any other structure or access way is to be located over any portion of the effluent management area.
- 49 All stormwater and seepage shall be diverted away from the septic tank and the disposal area. At no time is stormwater to be directed into the Aerated Wastewater Treatment System or onto the wastewater effluent disposal area and associated reserve area.
- 50 Orchards, vegetable gardens or any other plant species that can be used for the purposes of human consumption are not to be planted within the effluent management area. Effluent from the on-site sewage management system is not to be used on fruit or vegetables grown for human consumption.
- 51 The effluent management area shall be protected from possible stock damage.
- 52 No wastewater associated with the on-site sewage management system is to be applied or irrigated within the drip line of any native trees within the effluent management area.  
It is the responsibility of the applicant to ensure the ongoing health of the trees in relation to the effluent management area.
- 53 **Prior to the issue of the Construction Certificate**, the NSW Health Accreditation documentation is to be submitted to Council for approval. If Council is not the certifying authority, a copy of Council's written approval is to be provided to the Private Certifying Authority.
- 54 The reserve area, as marked on the Effluent Management Plan prepared by Strategic Environmental an Engineering Consultancy Pty Ltd (dated 31 May 2021, ref 21000176), is to be established with turf and is not to be used for any ancillary purpose. No materials are to be stored in the reserve area, and the reserve area is not to be developed. In the event that the primary effluent disposal area is to fail the reserve area is to be used. Written approval is to be obtained from Penrith City Council prior to any works being undertaken.

## SIGNATURE

Name:	Paul Buttigieg
Signature:	

For the Development Services Manager