



CONCEPT STORMWATER REPORT

# Australian Arms Hotel – 351 High Street Penrith NSW

PREPARED FOR  
Australian Arms Hotel Pty Ltd

Ref: SY200785

Rev: 1  
Date: 29.06.2020

# Concept Stormwater Report

## Revision Schedule

Date	Revision	Issue	Prepared By	Approved By
29.06.20	1	Development Application	N. Sutherland	J. Gilligan

**Northrop Consulting Engineers Pty Ltd**

ACN 064 775 088 | ABN 81 094 433 100

Level 11, 345 George Street, Sydney NSW 2000

02 9241 4188 | [sydney@northrop.com.au](mailto:sydney@northrop.com.au) | [www.northrop.com.au](http://www.northrop.com.au)

© 2020 Northrop Consulting Engineers Pty Ltd. All rights reserved.

This document has been prepared on behalf of and for the exclusive use of Australian Arms Hotel Pty Ltd and is subject to and issued in accordance with the agreement between Australian Arms Hotel Pty Ltd and Northrop Consulting Engineers. Northrop Consulting Engineers accepts no liability or responsibility whatsoever for it in respect of any use of or reliance upon this document by any third party. Copying this document without the permission of Australian Arms Hotel Pty Ltd or Northrop Consulting Engineers is not permitted.

## Table of Contents

1. Introduction .....	3
1.1 General.....	3
1.2 Site Description .....	3
1.3 Project Description .....	4
2. Civil Engineering .....	5
2.1 General.....	5
2.2 Design Criteria & Methodology .....	5
2.3 Sediment and Erosion Control .....	5
2.4 Stormwater Infrastructure and modelling .....	5
2.5 Sewer Main .....	6
3. Conclusion .....	7

# 1. Introduction

## 1.1 General

This report has been prepared by Northrop Consulting Engineers Pty Ltd (Northrop), as the Civil Engineering Consultants for the project. The development entails provision of a new hotel adjoining the existing Australian Arms Hotel along with a new modular café and playground. The site is located at 351 & 359 High Street and 18 Lawson Street, Penrith NSW.

This report outlines the proposed site stormwater management system for the site including, water quality, water conservation and other civil engineering requirements for the proposed development.

## 1.2 Site Description



Figure 1- Site Aerial Image

The existing site consists of a Hotel on the corner of High Street and Lawson Street. A substation and on-grade carpark exists off the laneway where the new building is proposed. On the other side of the laneway is a single dwelling and associated car parking at the rear, in the location of the proposed cafe. The site falls towards Lawson Street to the west. There is an existing sewer main which runs through the site, this would be required to be diverted around the new development as part of the detailed design phase of the project. Refer survey plan below.




Figure 2: Survey Plan

### 1.3 Project Description

The proposed development consists of a new multi-storey building, which includes two (2) levels of basement carparking. On the other northern side of the laneway, there is a proposed landscape area with pop up café. Below is the Ground Floor Architectural Site Plan.



Figure 3: Architectural Site Plan

## 2. Civil Engineering

### 2.1 General

A stormwater management system has been designed for the development to comply with Penrith City Council Stormwater Drainage Specification for Building Developments.

### 2.2 Design Criteria & Methodology

The objectives of this report are to provide commentary on the proposed stormwater management of the site to meet the requirements of the Penrith City Council's Stormwater Drainage Specification for Building Developments. In particular the report focuses on stormwater quantity and stormwater discharge to Council's stormwater system.

Other specific controls considered in the development of the site's stormwater system include:

- Management of 'minor' flows using piped systems for the 5% AEP;
- Management of 'major' flows using dedicated overland flow paths up to the 100-year ARI;
- Water conservation and flows are managed.
- Assessment of pre and post development flowrates (using DRAINS)
- Stormwater quality assessment

### 2.3 Sediment and Erosion Control

Prior to any earthworks commencing on site, erosion and sediment control measures will need to be put in place generally in accordance with Managing Urban Stormwater: Soils and Construction 4<sup>th</sup> Edition, March 2004. These measures will include:

- Installation of a 1.8m high chain wire fence covered with geo-textile filter fabric, to the perimeter of the work site area, where required;
- The use of sediment diverting methods to minimize sediment in Council's stormwater drainage network using sandbags around kerb inlet pits and geo-textile filter fabric around drop inlet pits, haybales and the like;
- Indicative locations for stockpiling

### 2.4 Stormwater Infrastructure and modelling

As part of the stormwater strategy, the site stormwater is to connect into Council's existing system on Lawson Street. Based on investigations, there is no Council stormwater pit in close proximity to the site. Therefore the development is to connect to kerb and gutter on Lawson Street. Based on Council's requirements, in order to connect to kerb;

- The maximum discharge rate is 25L/s per kerb connection in the 10% AEP;
- As the site frontage is greater than 15m long Council will allow two (2) kerb connections;
- Each stormwater drainage connection point shall be minimum 15m apart.
- 

Based on the above we prepared a DRAINS model to analyse the flowrates to ensure the development can connect to kerb in accordance with Council's above requirements. As a result, the Post-development flowrate is **48L/s** for the 10% AEP, which allows two (2) kerb connections. This is based on the site area of 1,302 square meters.

### 2.4.1 Proposed Stormwater Quantity Assessment

Based on the survey plan provided the total site is 100% impervious and therefore On-site Stormwater Detention (OSD) is not required for this development as no increase in flowrates. On the other side of the laneway the proposed landscape area reduces the pre-development flowrates to Council's stormwater system.

### 2.4.2 Proposed Stormwater Quality Assessment

Based on Council's Water Sensitive Urban Design Policy, water quality measures and MUSIC modelling to achieve pollutant removal targets is not required for this development as the developable site is;

- Less than 2,500m<sup>2</sup> and
- There is no increase in impervious areas due to the development. The existing site is 100% impervious.

However to achieve water conservation measures, the new multi-storey building roof drainage is proposed to connect to a 5KL rainwater tank (RWT) which is proposed to be used for irrigation and toilet flushing. This will be located within the basement. The overflow from the RWT will split into two (2) in order to allow two (2) kerb connections via gravity.

The other side of the laneway proposes landscape areas, where stormwater will infiltrate into the ground, providing improved water quality then pre-development scenario.

### 2.5 Sewer Main

As noted in Section 1.2, there is an existing sewer main which runs through the site. This would be required to be diverted as part of this development. Refer below



Figure 4: Sewer Diversion Sketch

### 3. Conclusion

In conclusion, Northrop Consulting Engineers Pty Ltd has undertaken the relevant analysis for the development in terms of stormwater management systems to support Development Application.



# AUSTRALIAN ARMS HOTEL

351 HIGH STREET PENRITH NSW 2750

CIVIL DOCUMENTATION: DEVELOPMENT APPLICATION



LOCALITY PLAN

SOURCE : NEARMAP.COM.AU (©2020)

## CIVIL DRAWING SCHEDULE

DWG No.	DRAWING TITLE
DAC01.01	COVER SHEET, DRAWING SCHEDULE AND LOCALITY PLAN
DAC01.11	SPECIFICATION NOTES - SHEET 01
DAC01.12	SPECIFICATION NOTES - SHEET 02
DAC02.01	CONCEPT SEDIMENT AND SOIL EROSION CONTROL PLAN
DAC02.11	SEDIMENT AND SOIL EROSION CONTROL DETAILS
DAC03.11	BULK EARTHWORKS CUT AND FILL PLAN
DAC04.01	SITEWORKS GRADING PLAN
DAC07.01	DETAILS - SHEET 01
DAC07.02	DETAILS - SHEET 02
DAC07.03	DETAILS - SHEET 03
DAC08.01	CATCHMENT PLAN

DRAWN: A.SUWAN DESIGNED: XXXX JOB MANAGER: N.SUTHERLAND VERIFIER:

REVISION	DESCRIPTION	ISSUED	VER'D	APP'D	DATE	CLIENT
1	ISSUED FOR REVIEW	AS		NS	02.06.20	
2	ISSUED FOR DEVELOPMENT APPLICATION	AS		NS	23.06.20	
3	ISSUED FOR DEVELOPMENT APPLICATION	JO		NS	30.06.20	

DRAWING NOT TO BE USED FOR CONSTRUCTION UNLESS VERIFICATION SIGNATURE HAS BEEN ADDED

ARCHITECT  
**nra-co-lab**  
THE COPYRIGHT OF THIS DRAWING REMAINS WITH NORTHROP CONSULTING ENGINEERS PTY LTD

ALL DIMENSIONS TO BE VERIFIED ON SITE BEFORE COMMENCING WORK. NORTHROP ACCEPTS NO RESPONSIBILITY FOR THE USABILITY, COMPLETENESS OR SCALE OF DRAWINGS TRANSFERRED ELECTRONICALLY. THIS DRAWING MAY HAVE BEEN PREPARED USING COLOUR, AND MAY BE INCOMPLETE IF COPIED TO BLACK & WHITE.

SCALE 1:2000@A1

**NORTHROP**  
Sydney  
Level 11 345 George Street, Sydney NSW 2000  
Ph (02) 9241 4188 Fax (02) 9241 4324  
Email sydney@northrop.com.au ABN 81 094 433 100

PROJECT  
**AUSTRALIAN ARMS HOTEL**  
351 HIGH STREET PENRITH,  
NSW 2750

DRAWING TITLE  
**CIVIL DOCUMENTATION:  
DEVELOPMENT APPLICATION**  
**COVER SHEET, DRAWING  
SCHEDULE AND LOCALITY PLAN**

JOB NUMBER <b>200785</b>	
DRAWING NUMBER <b>DAC01.01</b>	REVISION <b>3</b>
DRAWING SHEET SIZE = A1	

**NOT FOR CONSTRUCTION**

Printed By : JOHN O Found : \\nas\projects\2020 Jobs\200785 - Australian Arms Hotel\BID Drawings\Civil\2-CAD\CAD FILES\DAC01.01.dwg Date : 18.03.2020 3:17 PM



NOTE: ALL CIVIL ENGINEERING CONSTRUCTION WORKS TO BE CARRIED OUT IN ACCORDANCE WITH PENRITH CITY COUNCIL DEVELOPMENT GUIDELINES .THE AFOREMENTIONED GUIDELINES INCLUSIVE OF ALL SPECIFICATIONS TAKE PRECEDENCE OVER NOTES PROVIDED BELOW.

### ENGINEERING CERTIFICATION

- TO CERTIFY THE CONSTRUCTED CIVIL WORKS, A QUALIFIED EXPERIENCED ENGINEER IS TO VISIT THE SITE TO OBSERVE CONSTRUCTION TECHNIQUES AND VARIOUS ELEMENTS THAT MAY BE CONCEALED WHEN THE WORKS ARE COMPLETE.
- THIS SPECIFICATION ALLOWS FOR CERTIFICATION OF WORKS CONTROLLED BY A PRIVATE CERTIFIER FOR LAND DEVELOPMENT WORKS. THIS SPECIFICATION DOES NOT COVER CERTIFICATION REQUIREMENTS FOR AUTHORITIES SUCH AS COUNCIL, RMS OR OFFICE OF WATER. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO DETERMINE AND PROVIDE ALL PROJECT SPECIFIC CONSTRUCTION COMPLIANCE (WORKS AS EXECUTED) INFORMATION TO THE SATISFACTION OF THE STAKEHOLDER / AUTHORITY. DISCREPANCIES BETWEEN THIS SPECIFICATION AND SPECIFICATIONS OF OTHER EXTERNAL STAKEHOLDERS / AUTHORITIES IS TO BE REPORTED TO THE SUPERINTENDENT FOR CLARIFICATION.
- THE CONTRACTOR IS TO AGREE WITH THE ENGINEER AN APPROPRIATE SITE VISIT SCHEDULE AND FEE ARRANGEMENT PRIOR TO COMMENCEMENT OF THE WORKS. THE CONTRACTOR SHALL ENSURE THAT THE ENGINEER CAN SAFELY ACCESS ALL CIVIL ELEMENTS TO BE REVIEWED. SITE VISITS ARE CONDUCTED DURING NORMAL BUSINESS HOURS. WE REQUIRE TWO (2) WORKING DAY NOTICE FOR ANY SITE VISIT.
- TO PROVIDE CERTIFICATION THE ENGINEER MUST VISIT THE SITE TO OBSERVE.
  - PAVEMENTS**
    - POOR SUBGRADE CONDITIONS
    - PROOF ROLLING OF SUB-BASE
    - PLACEMENT OF SUB-BASE COURSE, BASE COURSE AND WEARING COURSE.
    - PLACEMENT OF STEEL REINFORCEMENT, DOWELS AND JOINT CRADLES PRIOR TO POURING OF CONCRETE
  - EARTHWORKS**
    - TOPSOIL STRIP
    - EARTHWORKS BATTER
    - FILLING
  - STORMWATER DRAINAGE**
    - DRAINAGE TRENCHES PRIOR TO BACKFILLING
    - LEGAL POINT OF CONNECTION PRIOR TO BACKFILLING
    - ANY OTHER DRAINAGE STRUCTURE THAT MAY BE CONCEALED DURING THE COURSE OF THE WORKS
  - CONCRETE STRUCTURES**
    - PLACEMENT OF ANY STEEL REINFORCEMENT PRIOR TO CONSTRUCTION.
- THE CONTRACTOR SHALL PROVIDE SURVEYED LEVELS, PREPARED BY A QUALIFIED SURVEYOR FOR SUBGRADE, SUB-BASE COURSE, BASE COURSE AND WEARING COURSE.
- THE CONTRACTOR SHALL PROVIDE WORKS AS EXECUTED (WAE) DOCUMENTATION PREPARED BY A QUALIFIED PRACTISING SURVEYOR. THE WAE DRAWINGS SHALL CLEARLY SHOW STORMWATER GRATE/COVER LEVELS, STORMWATER PIT INVERT LEVELS AND CORRESPONDING INVERT LEVELS OF ANY INCOMING OR OUTGOING PIPES, DIAMETER OF ALL PIPES, DIMENSIONS AND VOLUME OF ON-SITE DETENTION FACILITIES, INVERT LEVELS OF ORIFICE PLATES, OVERFLOW WEIRS, BASE OF TANK FINISHED LEVELS OF PAVEMENTS. THE WAE SHALL SHOW WHERE THE SIZE OR ALIGNMENT OF CIVIL ENGINEERING ELEMENTS WHEN THEY DEVIATE FROM THE DESIGN DOCUMENTATION.
- THE WAE DRAWINGS SHALL BE STAMPED WITH THE FOLLOWING STATEMENT "THESE WAE DRAWINGS HAVE BEEN PREPARED BY [COMPANY NAME] AND ARE A TRUE AND ACCURATE REPRESENTATION OF THE CONSTRUCTED WORKS". EACH DRAWING SHALL BE SIGNED AND DATED BY THE SURVEYOR WHO PREPARED THE DRAWINGS.  
  
THESE WAE DRAWINGS HAVE BEEN PREPARED BY [COMPANY NAME] AND ARE A TRUE AND ACCURATE REPRESENTATION OF THE CONSTRUCTED WORKS.  
  
SIGNED:..... DATE:.....  
  
NAME:.....  
  
POSITION:.....
- WAE SHALL BE PROVIDED IN BOTH AUTOCAD AND PDF FORMAT. NORTHROP CONSULTING ENGINEERS WILL PROVIDE ENGINEERING PLANS TO THE CONTRACTOR IN AUTOCAD FORMAT TO AID PREPARATION OF WAE DOCUMENTATION.
- IF THE WORKS ARE SUBJECT TO APPROVAL BY THE UPPER PARRAMATTA RIVER CATCHMENT TRUST (UPRCT) THE CONTRACTOR IS TO ABIDE BY THE UPRCT APPROVAL CHECKLIST.
- CONTRACTOR IS TO UNDERTAKE A CCTV INSPECTION OF ALL STORMWATER DRAINAGE PIPELINES AND PROVIDE TO THE ENGINEER FOR APPROVAL.
- THE CONTRACTOR SHALL PROVIDE ALL RELEVANT TEST CERTIFICATES PROGRESSIVELY THROUGHOUT THE DURATION OF THE WORKS. ALL TEST CERTIFICATES SHALL BE PREPARED BY A NATA REGISTERED LABORATORY. TEST CERTIFICATES ARE REQUIRED FOR PROOF ROLLING, SUBGRADE COMPACTION, COMPACTION OF PAVEMENT LAYERS, COMPACTION OF FILLING OPERATIONS, CONCRETE SLUMP TEST, AND CONCRETE STRENGTH TESTS. THE CONTRACTOR SHALL PROVIDE ALL RELEVANT VALIDATIONS BY A GEOTECHNICAL ENGINEER FOR ALL IMPORTED FILL.
- EACH TEST CERTIFICATE WILL NOMINATE THE DATE AND TIME OF THE TEST AND PROVIDE A LOCATION OF WHERE THE TEST SAMPLE WAS TAKEN FROM.
- THE CONTRACTOR SHALL ARRANGE FOR THE ENGINEER TO CONDUCT A FINAL VISIT TO REVIEW OF THE CONSTRUCTED WORKS. THIS WILL REVIEW WILL NOT TAKE PLACE UNTIL THE WAE DOCUMENTATION AND RELEVANT TEST CERTIFICATES HAVE BEEN RECEIVED.
- IF DEFECTIVE OR INCOMPLETE WORK IS FOUND DURING THE FINAL INSPECTION ANOTHER INSPECTION MAY BE REQUIRED AT THE CONTRACTORS EXPENSE TO VERIFY THE RECTIFICATION WORKS HAVE BEEN COMPLETED.

### ASPHALTIC CONCRETE

- GENERAL**
  - ALL ASPHALTIC CONCRETE (AC) WORK TO BE PREPARED AND CARRIED OUT IN ACCORDANCE WITH GOOD ASPHALTIC PAVING PRACTICE AS DESCRIBED IN AS2150-2005 "ASPHALT (HOT-MIXED) PAVING - GUIDE TO GOOD PRACTICE" AND CURRENT RMS SPECIFICATIONS.
- PAVEMENT PREPARATION**
  - THE FINISHED PAVEMENT SURFACE TO BE SEALED SHALL BE WITHIN +/- 2% OF THE OPTIMUM AND BROOMED BEFORE COMMENCEMENT OF WORK TO ENSURE COMPLETE REMOVAL OF ALL SUPERFICIAL FOREIGN MATTER.
  - PRIME ALL SURFACES TO BE SEALED. ALLOW PRIME TO SETTLE FOR A MINIMUM OF 3 DAYS BEFORE APPLYING TACK COAT AND ASPHALT.
  - SWEEP PRIMED SURFACES BEFORE APPLYING TACK COAT.
  - ALL DEPRESSIONS OR UNEVEN AREAS ARE TO BE TACK-COATED AND BROUGHT UP TO GENERAL LEVEL OF PAVEMENT WITH ASPHALTIC CONCRETE BEFORE LAYING OF MAIN COURSE.
  - ALL DEFECTS IN THE BASE COURSE INCLUDING CRACKS, SURFACE DEFORMATION AND THE LIKE SHALL BE REPAIRED AS DIRECTED BY THE SUPERINTENDENT PRIOR TO PLACEMENT OF TACK COAT AND/OR AC COURSES.
- PLACEMENTS**
  - ALL ASPHALT SHALL BE PLACED UTILISING APPROVED MECHANICAL PAVING MACHINES. DO NOT HAND PLACE ASPHALT WITHOUT PRIOR APPROVAL FROM ENGINEER.
- JOINTS**
  - THE DENSITY AND SURFACE FINISH AT JOINTS SHALL BE SIMILAR TO THOSE OF THE REMAINDER OF THE LAYER.
- COMPACTION**
  - ALL COMPACTION SHALL BE UNDERTAKEN USING SELF PROPULLED ROLLERS.
  - INITIAL ROLLING SHALL BE COMPLETED BEFORE THE MIX TEMPERATURE FALLS BELOW 105°C USING A STEEL DRUM ROLLER HAVING A MINIMUM WEIGHT OF 8 TONNES AND A MAXIMUM UNIT LOAD ON THE REAR DRUM EQUIVALENT TO 55kN/m WIDTH OF DRUM.
  - SECONDARY ROLLING SHALL BE COMPLETED BEFORE THE MIX TEMPERATURE FALLS BELOW 80°C USING A PNEUMATIC TYRED ROLLER OF AT LEAST 10 TONNES MASS. A MINIMUM TYRE PRESSURE OF 550kPa AND A MINIMUM TOTAL LOAD OF 1 TONNE ON EACH TYRE.
  - ROLLED SURFACES SHALL BE SMOOTH AND FREE OF UNDUCTIONS, BONY AND/OR UNEVEN SURFACES WILL BE REJECTED.
  - PROVIDE 2 No. MINIMUM COMPACTION TESTS.
- FINISHED SURFACE PROPERTIES**
  - FINISHED SURFACES SHALL BE SMOOTH, DENSE AND TRUE OF SHAPE AND SHALL NOT VARY MORE THAN:
    - 3mm FROM THE SPECIFIED PLAN LEVEL AT ANY POINT.
    - 3mm FROM THE BOTTOM OF A STRAIGHT EDGE LAID TRANSVERSELY.
    - 5mm FROM THE BOTTOM OF A STRAIGHT EDGE LAID LONGITUDINALLY.
    - MINUS 0 TO PLUS 2mm ADJACENT TO OTHER ELEMENTS SUCH AS KERBS AND THE LIKE TO AVOID POOLING OF SURFACE WATER.
    - MINUS 0 FROM THE SPECIFIED THICKNESS.
- DO NOT STORE PLANT EQUIPMENT OR TRAFFIC NEWLY LAID ASPHALTIC CONCRETE PAVEMENTS WITHOUT PRIOR APPROVAL FROM THE ENGINEER.
- DO NOT APPLY MARKING PAINTS UNTIL ASPHALT HAS CURED IN ACCORDANCE WITH PAINT MANUFACTURERS SPECIFICATIONS.

### CONCRETE PAVEMENTS

- THIS SECTION REFERS TO CIVIL CONCRETE WORKS AND DOES NOT INCLUDE STRUCTURAL ELEMENTS SUCH AS BUILDINGS, BELOW GROUND STRUCTURES OR RETAINING WALLS.
- ALL WORKMANSHIP AND MATERIALS SHALL BE IN ACCORDANCE WITH AS3600 CURRENT EDITION WITH AMENDMENTS, EXCEPT WHERE VARIED BY THE CONTRACT DOCUMENTS.
- CONCRETE QUALITY AND REINFORCING COVER**  
ALL REQUIREMENTS OF THE CURRENT ACSE CONCRETE SPECIFICATION DOCUMENT 1 SHALL APPLY TO THE FORMWORK, REINFORCEMENT AND CONCRETE UNLESS NOTED OTHERWISE.
 

ELEMENT	CONCRETE STRENGTH f <sub>c</sub> (MPa)	SPECIFIED SLUMP	NOMINAL AGGREGATE SIZE	MAX. 56 DAY DRYING SHRINKAGE	COVER (mm)
KERBS AND PATHS	25	60	20	650microns	TOP 40
PITS AND VEHICULAR PAVEMENTS	32	80	20	650microns	TOP 40
- CONCRETE PROPERTIES SHALL BE VARIED FROM NORMAL CLASS AS FOLLOWS:
  - MINIMUM CEMENT CONTENT 250 kg/m<sup>3</sup>
  - MAXIMUM 56 DAY SHRINKAGE STRAIN - AS NOMINATED ABOVE
  - PRIOR TO COMMENCEMENT CONCRETE SUPPLIER TO PROVIDE DRYING SHRINKAGE TEST RESULTS FROM PRODUCTION ASSESSMENT AS EVIDENCE THAT SPECIFIED DRYING SHRINKAGE LIMITS CAN BE ACHIEVED USING NORMAL MIX DESIGN.
- ALL REINFORCEMENT SHALL BE FIRMLY SUPPORTED ON MILD STEEL PLASTIC TIPPED CHAIRS. PLASTIC CHAIRS OR CONCRETE CHAIRS AT NOT GREATER THAN 1m CENTRES BOTH WAYS. BARS SHALL BE TIED AT ALTERNATE INTERSECTIONS.
- CEMENT TYPE SHALL BE (ACSE SPECIFICATION) TYPE SL.
- PROJECT CONTROL TESTING SHALL BE CARRIED OUT IN ACCORDANCE WITH AS 1379. TEST CYLINDERS ARE TO BE KEPT ON SITE.
- ALL COMPRESSIVE STRENGTH TEST REPORTS SHALL BE SUBMITTED TO THE CIVIL ENGINEER FOR REVIEW.
- ALL CONCRETE IS TO BE CONTINUOUSLY CURED FOR A MINIMUM PERIOD OF 10 DAYS AFTER PLACING. CURING TO COMMENCE IMMEDIATELY AFTER FINISHING. SPRAY ON CURING COMPOUNDS TO COMPLY WITH AS3799.
- PLACE CONCRETE CONTINUOUSLY BETWEEN CONSTRUCTION JOINTS SHOWN ON PLAN. DO NOT BREAK OR INTERRUPT SUCCESSIVE POURS SUCH THAT COLD JOINTS OCCUR. ANY REVISIONS OR ADDITIONS TO CONSTRUCTION JOINTS SHOWN ON PLAN REQUIRE APPROVAL FROM THE CIVIL ENGINEER.
- FALLS IN SLAB AS SHOWN ON PLAN MAINTAIN MINIMUM SLAB THICKNESS AS SHOWN.
- NO ADMIXTURES SHALL BE USED IN CONCRETE UNLESS APPROVED IN WRITING BY THE DESIGN ENGINEER.
- THE FINISHED CONCRETE SHALL BE A DENSE HOMOGENOUS MASS, COMPLETELY FILLING THE FORMWORK, THOROUGHLY EMBEDDING THE REINFORCEMENT AND FREE OF STONE POCKETS.
- FABRIC SHALL BE LAPPED IN ACCORDANCE WITH THE FOLLOWING DETAIL:  

25 MM LAP TWO WIRES

FOLLOWING THE FABRIC SYMBOL SL IS THE REFERENCE NUMBER FOR FABRIC TO AS1304.
- ALL PENETRATIONS TO HAVE 2/N12 TRIMMER BARS TOP AND BOTTOM TO EACH FACE U.N.O. EXTEND TRIMMERS 700 BEYOND PENETRATION. MAINTAIN 40mm COVER TOP AND BOTTOM.
- FORMWORK CLASS SHALL BE IN ACCORDANCE WITH AS3600.
- SURFACE FINISHES:**

ELEMENT	FORMWORK CLASS
STORMWATER PIT	OFF FORM
PAVEMENTS	MACHINE FLOAT OR BROOM FINISH
KERBS	STEEL FLOAT OR TROWEL
- REINFORCEMENT SYMBOLS:  
 N DENOTES GRADE 450 N BARS TO AS1302 GRADE N  
 R DENOTES 230 R HOT ROLLED PLAIN BARS TO AS1302  
 SL DENOTES HARD-DRAWN WIRE REINFORCING FABRIC TO AS1304

NUMBER OF BARS IN GROUP      NOMINAL BAR SIZE IN mm

↑      ↑

17 N 20 250      17 N 20 250

BAR GRADE AND TYPE      SPACING IN mm THE FIGURE

### PAVEMENTS

ALL PAVEMENT MATERIALS SHALL COMPLY WITH CURRENT RMS SPECIFICATIONS. PROVIDE MECHANICAL ANALYSIS FOR EACH BATCH OF PAVEMENT MATERIAL TO ENSURE CONFORMITY.

- COMPACTION STANDARDS**

BASE	98% MODIFIED MAXIMUM DRY DENSITY
SUBBASE	98% MODIFIED MAXIMUM DRY DENSITY
SUBGRADE	100% STANDARD MAXIMUM DRY DENSITY
- THE CONTRACTOR SHALL CONFIRM THE DESIGN CBR WITH A MINIMUM OF 3 TESTS TAKEN AT SUBGRADE LEVEL. WHERE DISCREPANCY IS FOUND, CONTACT THE DESIGN ENGINEER.
- ALLOW FOR COMPACTION TESTING BY A N.A.T.A. REGISTERED LABORATORY FOR BASE LAYER, SUBBASE LAYER AND SUBGRADE LAYER IN ACCORDANCE WITH THE LATEST VERSION OF AS3798 FOR PAVEMENTS (MINIMUM 2 TESTS PER LAYER) ALLOW FOR AT LEAST TWO SUCCESSFUL COMPACTION TESTS IN EACH LAYER.
- MATCH NEW PAVEMENTS NEATLY AND FLUSH WITH EXISTING
- AFTER BASE IS APPROVED, SWEEP CLEAN AND PRIME AT NOMINAL RATE OF 1.0L PER 1.0 sq.m.
- PAVEMENT HOLD POINTS**
  - SUB-GRADE PROOF ROLL PRIOR TO SET-UP AND FORM FOR CONCRETE POUR.
  - INSPECTION OF FORMWORK / STEEL PRIOR TO CONCRETE POUR.

### PAVEMENT JOINTS

- PROVIDE 10mm ABLEFLEX BETWEEN NEW CONCRETE WORKS AND EXISTING STRUCTURES.
- LOCAL AUTHORITY REQUIREMENTS SHALL TAKE PRECEDENCE WITHIN THE PUBLIC ROAD RESERVE.
- DOWELS TO BE PLACED ON PROPRIETARY CRADLES TO ENSURE CORRECT SPACING AND ALIGNMENT.
- PEDESTRIAN PAVEMENTS**  
ALL PEDESTRIAN PAVEMENTS ARE TO BE JOINTED AS FOLLOWS U.N.O. ON THE DESIGN DRAWINGS.
- EXPANSION JOINTS ARE TO BE LOCATED WHERE POSSIBLE AT TANGENT POINTS OF CURVES AND ELSEWHERE AT MAX. 6.0m CENTRES.
- WEAKENED PLANE JOINTS (SAWN OR TOOL JOINTS) ARE TO BE LOCATED AT A MAX. SPACING OF 15m x WIDTH OF THE PAVEMENT.
- WHERE POSSIBLE JOINTS SHOULD BE LOCATED TO MATCH KERBING AND/OR ADJACENT PAVEMENT JOINTS.
- TYPICAL PEDESTRIAN PAVEMENT JOINT DETAIL
- VEHICULAR PAVEMENTS**  
ALL VEHICULAR PAVEMENTS TO BE JOINTED AS FOLLOWS U.N.O. ON THE DESIGN DRAWINGS.
- TIED KEYED CONSTRUCTION JOINTS SHOULD GENERALLY BE LOCATED LONGITUDINALLY AT A MAX. OF 6.0m CENTRES.
- SAWN JOINTS SHOULD GENERALLY BE LOCATED LATERSALLY AT A MAX. OF 6.0m CENTRES WITH DOWELED EXPANSION JOINTS AT MAX. 18.0m CENTRES.
- TYPICAL VEHICULAR PAVEMENT JOINT DETAIL
- KERB EXPANSION JOINTS SHALL BE FORMED FROM 10mm ABLEFLEX FOR FULL DEPTH OF SECTION.
- KERB EXPANSION JOINTS TO BE LOCATED AT DRAINAGE PITS, TANGENT POINTS OF CURVES / CORNERS AND AT 12m MAX CENTRES.
- KERB TOOLED JOINTS TO BE MIN 3mm WIDE AND LOCATED AT MAX 3m CENTRES.
- INTEGRAL KERB JOINTS SHALL MATCH THE LOCATION OF PAVEMENT JOINTS.

### 3D INFORMATION DISCLAIMER

PLEASE BE ADVISED 12D DESIGN FILE, IF SUPPLIED, IS DEEMED TO BE AN ACCURATE REFLECTION OF NORTHROP'S DESIGN AT THE TIME OF FINAL DESIGN DEVELOPMENT AND MAY NOT FULLY REFLECT THE DESIGN SURFACE AS PRESENTED. HOWEVER THIS INFORMATION SHALL BE VERIFIED BY THE CONTRACTOR PRIOR TO INCORPORATION IN THE CONSTRUCTION WORKS.

YOU ARE FURTHER ADVISED THAT ISSUED HARDCOPY/PDF PLANS AND DOCUMENTS TAKE PRECEDENCE OVER THE SUPPLIED ELECTRONIC INFORMATION AND ANY INCONSISTENCIES SHOULD IMMEDIATELY BE REPORTED TO NORTHROP CONSULTING ENGINEERS FOR VERIFICATION PRIOR TO THEIR INCORPORATION IN THE WORKS.

NORTHROP CONSULTING ENGINEERS TAKES NO RESPONSIBILITY FOR USE OF NON-VERIFIED 3D DESIGN INFORMATION USED IN THE WORKS.

THE USE OF THE 3D MODEL INFORMATION SHALL CONSTITUTE ACKNOWLEDGMENT AND ACCEPTANCE OF THE ABOVE STATEMENTS BY THE RECIPIENT.

### SAFETY IN DESIGN

THE FOLLOWING ITEMS HAVE BEEN IDENTIFIED AS SAFETY RISKS

S01

INTERCEPTION OF EXISTING SERVICES

S02

FALL DURING CONSTRUCTION

S03

VEHICULAR TRAFFIC

S04

DEEP TRENCHES

SXX

RISK DESCRIPTION

SXX

RISK DESCRIPTION

### RMS WORKS

- ALL WORKS WITHIN RMS JURISDICTION TO COMPLY WITH RMS STANDARDS AND SPECIFICATIONS. FOR REMAINING WORKS, THE ATTACHED SPECIFICATIONS APPLY. ANY CONTRADICTIONS WITHIN TO BE REFERRED TO THE SUPERINTENDENT ON SITE TO SEEK FURTHER CLARIFICATION.

### STANDARD DETAILS

ANY DISCREPANCIES TO BE REPORTED IMMEDIATELY TO NORTHROP ENGINEERS FOR CLARIFICATION

RMS STANDARD DETAILS		
COMPONENT	DWG REFERENCE	DRAWING TITLE
KERB 'SA TYPE'	MD.R15 A01A	STANDARD KERB & GUTTER SHAPES
COUNCIL DETAILS - xxCOUNCIL NAMExx		
COMPONENT	DWG REFERENCE	DRAWING TITLE
CONCRETE DRIVEWAY	B.C.C A(BS) 103S	STD INDUSTRIAL & COMMERCIAL FOOTWAY CROSSINGS

DESIGNED: XXXX      VERIFIER: ASUWAN      JOB MANAGER: N.SUTHERLAND

REVISION	DESCRIPTION	ISSUED	VER'D	APP'D	DATE	CLIENT
1	ISSUED FOR REVIEW	AS		NS	02.06.20	
2	ISSUED FOR DEVELOPMENT APPLICATION	AS		NS	23.06.20	
3	ISSUED FOR DEVELOPMENT APPLICATION	JO		NS	30.06.20	

DRAWING NOT TO BE USED FOR CONSTRUCTION UNLESS VERIFICATION SIGNATURE HAS BEEN ADDED

THE COPYRIGHT OF THIS DRAWING REMAINS WITH NORTHROP CONSULTING ENGINEERS PTY LTD

ALL DIMENSIONS TO BE VERIFIED ON SITE BEFORE COMMENCING WORK. NORTHROP ACCEPTS NO RESPONSIBILITY FOR THE USABILITY, COMPLETENESS OR SCALE OF DRAWINGS TRANSFERRED ELECTRONICALLY. THIS DRAWING MAY HAVE BEEN PREPARED USING COLOUR AND MAY BE INCOMPLETE IF COPIED TO BLACK & WHITE

**Sydney**  
 Level 11 345 George Street, Sydney NSW 2000  
 Ph (02) 9241 4188 Fax (02) 9241 4324  
 Email sydney@northrop.com.au ABN 81 094 433 100

PROJECT

**AUSTRALIAN ARMS HOTEL**  
**351 HIGH STREET PENRITH,**  
**NSW 2750**

DRAWING TITLE

**CIVIL DOCUMENTATION:**  
**DEVELOPMENT APPLICATION**  
**SPECIFICATION NOTES - SHEET 02**

JOB NUMBER

**200785**

DRAWING NUMBER      REVISION

**DAC01.12      3**

DRAWING SHEET SIZE = A1

## NOT FOR CONSTRUCTION

Found: I:\nra\proj\proj2020\Jobs\200785 - Australian Arms Hotel\3D Drawings\3D-Model\CAD FILE\1-DAC00112.dwg      Printed By: JJOHN O      Date: 19.03.2020 3:17 PM

DRAWN: A.SUWAN  
DESIGNED: XXXX  
JOB MANAGER: N.SUTHERLAND  
VERIFIER:

REVISION	DESCRIPTION	ISSUED	VER'D	APP'D	DATE	CLIENT
1	ISSUED FOR REVIEW	AS		NS	02.06.20	
2	ISSUED FOR DEVELOPMENT APPLICATION	AS		NS	23.06.20	
3	ISSUED FOR DEVELOPMENT APPLICATION	JO		NS	30.06.20	

DRAWING NOT TO BE USED FOR CONSTRUCTION UNLESS VERIFICATION SIGNATURE HAS BEEN ADDED

ARCHITECT  
**nra-co-lab**  
THE COPYRIGHT OF THIS DRAWING REMAINS WITH NORTHROP CONSULTING ENGINEERS PTY LTD

ALL DIMENSIONS TO BE VERIFIED ON SITE BEFORE COMMENCING WORK. NORTHROP ACCEPTS NO RESPONSIBILITY FOR THE USABILITY, COMPLETENESS OR SCALE OF DRAWINGS TRANSFERRED ELECTRONICALLY. THIS DRAWING MAY HAVE BEEN PREPARED USING COLOUR, AND MAY BE INCOMPLETE IF COPIED TO BLACK & WHITE.

SCALE 1:200@A1


**NORTHROP**  
Sydney  
Level 11 345 George Street, Sydney NSW 2000  
Ph (02) 9241 4188 Fax (02) 9241 4324  
Email sydney@northrop.com.au ABN 81 094 433 100

PROJECT  
**AUSTRALIAN ARMS HOTEL**  
351 HIGH STREET PENRITH,  
NSW 2750

DRAWING TITLE  
**CIVIL DOCUMENTATION:  
DEVELOPMENT APPLICATION  
CONCEPT SEDIMENT AND SOIL  
EROSION CONTROL PLAN**

JOB NUMBER <b>200785</b>	
DRAWING NUMBER <b>DAC02.01</b>	REVISION <b>3</b>
DRAWING SHEET SIZE = A1	

**NOT FOR CONSTRUCTION**




**LEGEND**

- BOUNDARY LINE
- EASEMENT LINE
- SEDIMENT FENCE
- SECURITY FENCE
- WIRE MESH AND GRAVEL SEDIMENT FILTER
- DROP INLET SEDIMENT TRAP
- DRAINAGE SWALE
- STABILISED SITE ACCESS
- STOCKPILE

- GENERAL NOTES**
- REFER SPECIFICATIONS NOTES FOR SEDIMENT AND SOIL EROSION CONTROL GENERAL REQUIREMENTS.
  - ALL WORKS TO BE CARRIED OUT IN ACCORDANCE WITH COUNCIL / RELEVANT AUTHORITY SPECIFICATIONS AND DETAILS.
  - ALL SEDIMENT AND SOIL EROSION CONTROL MEASURES TO BE INSTALLED IN ACCORDANCE WITH THE 'BLUE BOOK'. CONTRACTOR TO ENSURE THESE MEASURES ARE IN PLACE AND MAINTAINED AT ALL TIMES DURING CONSTRUCTION WORKS.
  - CONTRACTOR TO PROVIDE 'WIRE MESH AND GRAVEL SEDIMENT FILTER' TO ALL PAVED / ROAD AREAS (BOTH PROPOSED AND EXISTING) IN ACCORDANCE WITH THE 'BLUE BOOK'.
  - CONTRACTOR TO PROVIDE 'GEOTEXTILE INLET FILTER TRAPS' TO ALL STORMWATER DRAINAGE INLETS (BOTH PROPOSED AND EXISTING) IN ACCORDANCE WITH THE 'BLUE BOOK'.


Printed By: JOHN O  
Date: 18.03.2020 3:17 PM  
Found: \\nas\projects\2020 Jobs\200785 - Australian Arms Hotel\Drawings\Civil\2-DAC02-CAD FILE\1-DAC020785\_DAC02.dwg



**CONSTRUCTION NOTES**

1. PLACE STOCKPILES MORE THAN 2m (PREFERABLY 5m) FROM EXISTING VEGETATION, CONCENTRATED WATER FLOW, ROADS AND HAZARD AREAS.
2. CONSTRUCT ON THE CONTOUR AS LOW, FLAT, ELONGATED MOUNDS.
3. WHERE THERE IS SUFFICIENT AREA, TOPSOIL STOCKPILES SHALL BE LESS THAN 2m IN HEIGHT.
4. WHERE THEY ARE TO BE IN PLACE FOR MORE THAN 10 DAYS, STABILISE FOLLOWING THE APPROVED ESCP OR SWMP TO REDUCE THE C-FACTOR TO LESS THAN 0.10.
5. CONSTRUCT EARTH BANKS (STANDARD DRAWING 5-5) ON THE UPSLOPE SIDE TO DIVERT WATER AROUND STOCKPILES AND SEDIMENT FENCES (STANDARD DRAWING 6-8) 1 TO 2m DOWN SLOPE.


**STOCKPILE**



**CONSTRUCTION NOTES**

1. FABRICATE A SEDIMENT BARRIER MADE FROM GEOTEXTILE OR STRAW BALES.
2. FOLLOW STANDARD DRAWING 6-7 AND STANDARD DRAWING 6-8 FOR INSTALLATION PROCEDURES FOR THE STRAW BALES OR GEOFABRIC. REDUCE THE PICKET SPACING TO 1 METRE CENTRES.
3. IN WATERWAYS, ARTIFICIAL SAG POINTS CAN BE CREATED WITH SANDBAGS OR EARTH BANKS AS SHOWN IN THE DRAWING.
4. DO NOT COVER THE INLET WITH GEOTEXTILE UNLESS THE DESIGN IS ADEQUATE TO ALLOW FOR ALL WATERS TO BYPASS IT.

**GEOTEXTILE INLET FILTER TRAPS**



**CONSTRUCTION NOTES**

1. STRIP THE TOPSOIL, LEVEL THE SITE AND COMPACT THE SUBGRADE.
2. COVER THE AREA WITH NEEDLE-PUNCHED GEOTEXTILE.
3. CONSTRUCT A 200mm THICK PAD OVER THE GEOTEXTILE USING ROAD BASE OR 30mm AGGREGATE.
4. ENSURE THE STRUCTURE IS AT LEAST 15 METRES LONG OR TO BUILDING ALIGNMENT AND AT LEAST 3 METRES WIDE.
5. WHERE A SEDIMENT FENCE JOINS ONTO THE STABILISED ACCESS, CONSTRUCT A HUMP IN THE STABILISED ACCESS TO DIVERT WATER TO THE SEDIMENT FENCE.

**STABILISED SITE ACCESS**

DRAWN: A.SUWAN DESIGNED: XXXX JOB MANAGER: N.SUTHERLAND VERIFIER:

REVISION	DESCRIPTION	ISSUED	VER'D	APP'D	DATE	CLIENT
1	ISSUED FOR REVIEW	AS		NS	02.06.20	
2	ISSUED FOR DEVELOPMENT APPLICATION	AS		NS	23.06.20	
3	ISSUED FOR DEVELOPMENT APPLICATION	JO		NS	30.06.20	

DRAWING NOT TO BE USED FOR CONSTRUCTION UNLESS VERIFICATION SIGNATURE HAS BEEN ADDED

ARCHITECT

THE COPYRIGHT OF THIS DRAWING REMAINS WITH NORTHROP CONSULTING ENGINEERS PTY LTD

ALL DIMENSIONS TO BE VERIFIED ON SITE BEFORE COMMENCING WORK. NORTHROP ACCEPTS NO RESPONSIBILITY FOR THE USABILITY, COMPLETENESS OR SCALE OF DRAWINGS TRANSFERRED ELECTRONICALLY. THIS DRAWING MAY HAVE BEEN PREPARED USING COLOUR, AND MAY BE INCOMPLETE IF COPIED TO BLACK & WHITE.

Sydney  
Level 11 345 George Street, Sydney NSW 2000  
Ph (02) 9241 4188 Fax (02) 9241 4324  
Email sydney@northrop.com.au ABN 81 094 433 100

PROJECT

**AUSTRALIAN ARMS HOTEL  
351 HIGH STREET PENRITH,  
NSW 2750**

DRAWING TITLE

**CIVIL DOCUMENTATION:  
DEVELOPMENT APPLICATION  
SEDIMENT AND SOIL EROSION  
CONTROL DETAILS**

JOB NUMBER

**200785**

DRAWING NUMBER

**DAC02.11**

REVISION

**3**

DRAWING SHEET SIZE = A1

**NOT FOR CONSTRUCTION**

DRAWN: A.SUWAN  
DESIGNED: XXXX  
JOB MANAGER: N.SUTHERLAND  
VERIFIER:

REVISION	DESCRIPTION	ISSUED	VER'D	APP'D	DATE	CLIENT
1	ISSUED FOR DEVELOPMENT APPLICATION	AS		NS	23.06.20	
2	ISSUED FOR DEVELOPMENT APPLICATION	JO		NS	30.06.20	

DRAWING NOT TO BE USED FOR CONSTRUCTION UNLESS VERIFICATION SIGNATURE HAS BEEN ADDED

ARCHITECT  
**nra-co-lab**  
THE COPYRIGHT OF THIS DRAWING REMAINS WITH NORTHROP CONSULTING ENGINEERS PTY LTD

ALL DIMENSIONS TO BE VERIFIED ON SITE BEFORE COMMENCING WORK. NORTHROP ACCEPTS NO RESPONSIBILITY FOR THE USABILITY, COMPLETENESS OR SCALE OF DRAWINGS TRANSFERRED ELECTRONICALLY. THIS DRAWING MAY HAVE BEEN PREPARED USING COLOUR, AND MAY BE INCOMPLETE IF COPIED TO BLACK & WHITE.

SCALE 1:200@A1


**NORTHROP**  
Sydney  
Level 11 345 George Street, Sydney NSW 2000  
Ph (02) 9241 4188 Fax (02) 9241 4324  
Email sydney@northrop.com.au ABN 81 094 433 100

PROJECT  
**AUSTRALIAN ARMS HOTEL**  
351 HIGH STREET PENRITH,  
NSW 2750

DRAWING TITLE  
**CIVIL DOCUMENTATION:  
DEVELOPMENT APPLICATION  
BULK EARTHWORKS CUT AND  
FILL PLAN**

JOB NUMBER <b>200785</b>	
DRAWING NUMBER <b>DAC03.11</b>	REVISION <b>2</b>
DRAWING SHEET SIZE = A1	

**NOT FOR CONSTRUCTION**



**LEGEND**

- BOUNDARY LINE
- EASEMENT LINE
- BEXX.XX** BULK EARTHWORKS PAD LEVEL

**DEPTH OF CUT**


- 9.0m TO - 8.5m
- 8.5m TO - 8.0m
- 8.0m TO - 7.5m
- 7.5m TO - 7.0m
- 7.0m TO - 6.5m
- 6.5m TO - 6.0m

- GENERAL NOTES**
- REFER SPECIFICATIONS NOTES FOR EARTHWORKS GENERAL REQUIREMENTS
  - ALL WORKS TO BE CARRIED OUT IN ACCORDANCE WITH COUNCIL / RELEVANT AUTHORITY SPECIFICATIONS AND DETAILS.
  - CAD FILES / DTM FILES TO BE SUPPLIED IN AUTOCAD FORMAT FOR SETOUT PURPOSES (UPON REQUEST).
  - NO ALLOWANCE HAS BEEN MADE FOR BULKING FACTORS. NOTE ALL VOLUMES DEPICTED ARE SOLID VOLUMES ONLY AND MAY NOT REFLECT DETAILED EARTHWORKS.
  - NO ALLOWANCE HAS BEEN MADE FOR DETAILED EARTHWORKS; ie SERVICE TRENCHING, DETAILED EXCAVATION, FOOTINGS, RETAINING WALLS AND THE LIKE. CONTRACTOR IS TO ALLOW FOR REMOVAL OF ALL EXCESS MATERIAL GENERATED BY THE WORKS.
  - THE CONTRACTOR SHALL USE FINAL SURFACE LEVELS AND TYPICAL PAVEMENT DETAILS FOR ACTUAL EARTHWORKS LEVELS. BULK EARTHWORKS ARE BASED ON THE FOLLOWING DEPTHS FROM FINISHED SURFACE LEVELS:
  - BASEMENT SLAB 200mm
  - APPROXIMATE BULK EARTHWORK VALUES AS FOLLOWS;
 

8.1 CUT	10,017 cu.m
8.2 FILL	0 cu.m
8.3 BALANCE	10,017 cu.m (EXPORT)
8.4 NOTE: SITE TOP SOIL STRIPPING VOLUMES HAVE NOT BEEN INCLUDED IN ABOVE CALCULATIONS.	

Printed By: JOHN O  
Date: 18.03.2020 3:17 PM  
Found: \\nas-files\project\2020 Jobs\200785 - Australian Arms Hotel\Drawings\Civil\2-CAD\CAD FILES\DAC03.11.dwg

HIGH STREET



LEGEND	
	BOUNDARY LINE
	EASEMENT LINE
	PROPOSED KERB
	EXISTING KERB
	EXISTING KERB AND GUTTER
	INTEGRAL KERB
	DISH DRAIN
	PROPOSED SPOT HEIGHT
	PROPOSED FINISHED FLOOR LEVEL
	DIRECTION OF GRADE
	DRAINAGE SWALE
	NEW DRAINAGE STRUCTURE
	STORMWATER PIPE
	EXISTING ELECTRICITY
	EXISTING WATER
	EXISTING TELSTRA AND NBN
	EXISTING GAS
	EXISTING SEWER
	PROPOSED SEWER
	PAVEMENT
	FOOTPATH
	LANDSCAPING

- GENERAL NOTES**
- REFER SPECIFICATIONS NOTES FOR STORMWATER AND SITEWORKS GENERAL REQUIREMENTS.
  - ALL WORKS TO BE CARRIED OUT IN ACCORDANCE WITH COUNCIL / RELEVANT AUTHORITY SPECIFICATIONS AND DETAILS. CAD FILES TO BE SUPPLIED IN AUTOCAD FORMAT FOR SETOUT PURPOSES (UPON REQUEST).
  - SUBSOIL DRAINAGE TO RETAINING WALLS, KERBS AND SWALE DRAINS NOT SHOWN FOR CLARITY - REFER RELEVANT DETAILS. REFER 'STORMWATER PIT SCHEDULE' OR LONGSECTIONS FOR PIT INFORMATION.
  - REFER HYDRAULIC ENGINEERS / ARCHITECTS DRAWINGS FOR DOWNPIPE LOCATIONS AND SIZING.
  - PROVIDE DRAINAGE CONNECTIONS TO KERB IN ACCORDANCE WITH COUNCIL STANDARD DETAILS AND SPECIFICATION.
  - CONTRACTOR TO ALLOW TO ADJUST AND LIAISE WITH RELEVANT SERVICE AUTHORITIES IN RELATION TO EXISTING SERVICE ADJUSTMENT AND MODIFICATIONS.

DRAWN: A.SUWAN DESIGNED: XXXX JOB MANAGER: N.SUTHERLAND VERIFIER:

Found: \\nas\projects\2020\Jobs\200785 - Australian Arms Hotel\Drawings\Civil\CAD\CAD FILES\DWG\DWG\_0400785\_DAC04.dwg Pinned By: J.OHN O



**NOT FOR CONSTRUCTION**

REVISION	DESCRIPTION	ISSUED	VER'D	APP'D	DATE	CLIENT
1	ISSUED FOR REVIEW	AS	NS	02.06.20		
2	ISSUED FOR DEVELOPMENT APPLICATION	AS	NS	23.06.20		
3	ISSUED FOR DEVELOPMENT APPLICATION	JO	NS	30.06.20		

DRAWING NOT TO BE USED FOR CONSTRUCTION UNLESS VERIFICATION SIGNATURE HAS BEEN ADDED

ARCHITECT  
**nra-co-lab**  
THE COPYRIGHT OF THIS DRAWING REMAINS WITH NORTHROP CONSULTING ENGINEERS PTY LTD

ALL DIMENSIONS TO BE VERIFIED ON SITE BEFORE COMMENCING WORK. NORTHROP ACCEPTS NO RESPONSIBILITY FOR THE USABILITY, COMPLETENESS OR SCALE OF DRAWINGS TRANSFERRED ELECTRONICALLY. THIS DRAWING MAY HAVE BEEN PREPARED USING COLOUR, AND MAY BE INCOMPLETE IF COPIED TO BLACK & WHITE.


SCALE 1:200@A1

**NORTHROP**  
Sydney  
Level 11 345 George Street, Sydney NSW 2000  
Ph (02) 9241 4188 Fax (02) 9241 4324  
Email sydney@northrop.com.au ABN 81 094 433 100


PROJECT  
**AUSTRALIAN ARMS HOTEL**  
351 HIGH STREET PENRITH,  
NSW 2750

DRAWING TITLE  
**CIVIL DOCUMENTATION:**  
DEVELOPMENT APPLICATION  
SITEWORKS GRADING PLAN


JOB NUMBER <b>200785</b>	
DRAWING NUMBER <b>DAC04.01</b>	REVISION <b>3</b>
DRAWING SHEET SIZE = A1	




SECTION 1




PLAN  
SURFACE INLET 'SIP' / JUNCTION PIT 'JP'  
PIT STRUCTURE TO BE 200mm THICK UNLESS SHOWN OTHERWISE. DRILL AND EPOXY PLASTIC PROPRIETARY STEP IRONS IN ACCORDANCE WITH AUSTRALIAN STANDARDS AND MANUFACTURERS SPECIFICATIONS (PITS - 1000mm DEPTH). REFER PIT INTERFACE DETAIL 'F' FOR CORNER REINFORCEMENT




PIT INTERFACE - DETAIL 'B'




PIT INTERFACE - DETAIL 'D'



SUBSOIL DRAINAGE CLEAROUT 'CO'  
CLEAROUT TO BE INSTALLED AT UPSTREAM POINTS ALONG SUBSOIL DRAINAGE LINES @ MAX 30m CENTRES AND DISCHARGING TO DRAINAGE STRUCTURES @ MAX 60m CENTRES.



SUBSOIL DRAINAGE CLEAROUT 'CO'  
CLEAROUT TO BE INSTALLED AT INTERMEDIATE POINTS ALONG SUBSOIL DRAINAGE LINES @ MAX 30m CENTRES AND DISCHARGING TO DRAINAGE STRUCTURES @ MAX 60m CENTRES.



SUBSOIL DRAINAGE TRENCH - LANDSCAPING 'SSD'  
CLEAROUT TO BE INSTALLED @ MAX 30m CENTRES AND DISCHARGING TO DRAINAGE STRUCTURES @ MAX 60m CENTRES.

DRAWN: A.SUWAN  
DESIGNED: XXXX  
JOB MANAGER: N.SUTHERLAND  
VERIFIER:

REVISION	DESCRIPTION	ISSUED	VER'D	APP'D	DATE	CLIENT
1	ISSUED FOR REVIEW	AS		NS	02.06.20	
2	ISSUED FOR DEVELOPMENT APPLICATION	AS		NS	23.06.20	
3	ISSUED FOR DEVELOPMENT APPLICATION	JO		NS	30.06.20	

DRAWING NOT TO BE USED FOR CONSTRUCTION UNLESS VERIFICATION SIGNATURE HAS BEEN ADDED

ARCHITECT  
**nra-co-lab**  
THE COPYRIGHT OF THIS DRAWING REMAINS WITH NORTHROP CONSULTING ENGINEERS PTY LTD

ALL DIMENSIONS TO BE VERIFIED ON SITE BEFORE COMMENCING WORK. NORTHROP ACCEPTS NO RESPONSIBILITY FOR THE USABILITY, COMPLETENESS OR SCALE OF DRAWINGS TRANSFERRED ELECTRONICALLY. THIS DRAWING MAY HAVE BEEN PREPARED USING COLOUR, AND MAY BE INCOMPLETE IF COPIED TO BLACK & WHITE.

**NORTHROP**  
Sydney  
Level 11 345 George Street, Sydney NSW 2000  
Ph (02) 9241 4188 Fax (02) 9241 4324  
Email sydney@northrop.com.au ABN 81 094 433 100

PROJECT  
**AUSTRALIAN ARMS HOTEL**  
351 HIGH STREET PENRITH,  
NSW 2750


DRAWING TITLE  
**CIVIL DOCUMENTATION:**  
DEVELOPMENT APPLICATION  
DETAILS - SHEET 03

JOB NUMBER <b>200785</b>	
DRAWING NUMBER <b>DAC07.03</b>	REVISION <b>3</b>
DRAWING SHEET SIZE = A1	


**NOT FOR CONSTRUCTION**

Found: \\nas\projects\2020 Jobs\200785 - Australian Arms Hotel\3D Drawings\Civil\CAD\CAD FILES\DAC07.03.dwg  
Printed By: JOHN O  
Date: 18.03.2020 3:17 PM






**TYPICAL KERB & GUTTER RECONSTRUCTION**  
 REFER NOTE 6 (SHEET 2)



**KERB & GUTTER**


**LOW PROFILE ROLL KERB**




**DRIVEWAY LAYBACK - RESIDENTIAL**

**DRIVEWAY LAYBACK - COMMERCIAL & INDUSTRIAL AND LOW LEVEL RESIDENTIAL**

DRAWN:	STANDARD KERB & GUTTER, LAYBACKS & DISH CROSSING SHEET 1 OF 2	APPROVED:
<b>PENRITH CITY COUNCIL</b>		PLAN No: <b>SD1003/1</b>



**REINFORCED DISH CROSSING**




**KERB EDGING**


**MOUNTABLE KERB**

- NOTES**
1. CONCRETE COMPRESSIVE STRENGTH (f'c) AT 28 DAYS, TO BE 25MPa FOR KERB & GUTTER AND DISH CROSSINGS.
  2. ROAD SUB-BASE SHALL BE EXTENDED 300mm BEHIND BACK OF KERB WITH THE THICKNESS TO BE NOT LESS THAN THE ROAD PAVEMENT SUB-BASE THICKNESS.
  3. GALVANIZED STEEL OR SIMILAR APPROVED STORMWATER KERB ADAPTORS THE FULL HEIGHT OF THE KERB SHALL BE USED. THE KERB OUTLETS ARE TO MATCH THE PROFILE OF THE KERB. SEE SPECIFICATION
  4. ALL DIMENSIONS ARE IN MILLIMETERS, UNLESS OTHERWISE STATED.
  5. ALL EXPOSED EDGES TO BE ROUNDED TO 20mm RADIUS UNLESS SHOWN OTHERWISE
  6. SPECIFICATIONS FOR RECONSTRUCTION WORKS TO BE DETERMINED BY COUNCIL'S ENGINEER.
  7. SERVICE CONDUIT LOCATIONS SHALL BE MARKED ON KERB FACE WITH AN APPROVED TOOL OR AS OTHERWISE DIRECTED.


DRAWN:	STANDARD KERB & GUTTER, LAYBACKS & DISH CROSSING SHEET 2 OF 2	APPROVED:
<b>PENRITH CITY COUNCIL</b>		PLAN No: <b>SD1003/2</b>



**RESIDENTIAL**



**INDUSTRIAL/COMMERCIAL**



**VEHICULAR CROSSING PROFILE - HIGH & LOW LEVEL**

DRAWN:	TYPICAL VEHICULAR CROSSOVER	APPROVED:
<b>PENRITH CITY COUNCIL</b>		PLAN No: <b>SD1004</b>

**NOT FOR CONSTRUCTION**

REVISION	DESCRIPTION	ISSUED	VER'D	APP'D	DATE
1	ISSUED FOR REVIEW	AS	NS		02.06.20
2	ISSUED FOR DEVELOPMENT APPLICATION	AS	NS		23.06.20
3	ISSUED FOR DEVELOPMENT APPLICATION	JO	NS		30.06.20

CLIENT	ARCHITECT
	<b>nra-co-lab</b>
DRAWING NOT TO BE USED FOR CONSTRUCTION UNLESS VERIFICATION SIGNATURE HAS BEEN ADDED	
THE COPYRIGHT OF THIS DRAWING REMAINS WITH NORTHROP CONSULTING ENGINEERS PTY LTD	


ALL DIMENSIONS TO BE VERIFIED ON SITE BEFORE COMMENCING WORK.  
 NORTHROP ACCEPTS NO RESPONSIBILITY FOR THE USABILITY, COMPLETENESS OR SCALE OF DRAWINGS TRANSFERRED ELECTRONICALLY.  
 THIS DRAWING MAY HAVE BEEN PREPARED USING COLOUR, AND MAY BE INCOMPLETE IF COPIED TO BLACK & WHITE.

**NORTHROP**  
 Sydney  
 Level 11 345 George Street, Sydney NSW 2000  
 Ph (02) 9241 4188 Fax (02) 9241 4324  
 Email sydney@northrop.com.au ABN 81 094 433 100

PROJECT	AUSTRALIAN ARMS HOTEL 351 HIGH STREET PENRITH, NSW 2750
---------	---


DRAWING TITLE	CIVIL DOCUMENTATION: DEVELOPMENT APPLICATION DETAILS - SHEET 01
---------------	---

JOB NUMBER	200785
DRAWING NUMBER	DAC07.01
REVISION	3
DRAWING SHEET SIZE = A1	




**INTEGRAL KERB 'IK'**

EXPANSION JOINTS @ MAX 12m CTRS / TOOL JOINTS @ MAX 3m CTRS TO ALIGN WITH PAVEMENT JOINTING. ALL RADII TO BE 20mm U.N.O.




**CONCRETE VEHICULAR PAVEMENT**

MIN CBR      % (CONTRACTOR TO CONFIRM ONSITE)  
DESIGN LOADING = xxxxx ESA's



**CONCRETE FOOTPATH PAVEMENT**

MIN CBR      % (CONTRACTOR TO CONFIRM ONSITE)  
CONTRACTOR TO ALLOW FOR JOINTS - REFER JOINT DETAILS



**600 WIDE OPEN GRASS SWALE**

DRAWN: A.SUWAN    DESIGNED: XXXX    JOB MANAGER: N.SUTHERLAND    VERIFIER:

**NOT FOR CONSTRUCTION**

REVISION	DESCRIPTION	ISSUED	VER'D	APP'D	DATE
1	ISSUED FOR REVIEW	AS		NS	02.06.20
2	ISSUED FOR DEVELOPMENT APPLICATION	AS		NS	23.06.20
3	ISSUED FOR DEVELOPMENT APPLICATION	JO		NS	30.06.20

DRAWING NOT TO BE USED FOR CONSTRUCTION UNLESS VERIFICATION SIGNATURE HAS BEEN ADDED

ARCHITECT  
**nra-co-lab**  
THE COPYRIGHT OF THIS DRAWING REMAINS WITH NORTHROP CONSULTING ENGINEERS PTY LTD

ALL DIMENSIONS TO BE VERIFIED ON SITE BEFORE COMMENCING WORK. NORTHROP ACCEPTS NO RESPONSIBILITY FOR THE USABILITY, COMPLETENESS OR SCALE OF DRAWINGS TRANSFERRED ELECTRONICALLY. THIS DRAWING MAY HAVE BEEN PREPARED USING COLOUR, AND MAY BE INCOMPLETE IF COPIED TO BLACK & WHITE.


**NORTHROP**  
Sydney  
Level 11 345 George Street, Sydney NSW 2000  
Ph (02) 9241 4188 Fax (02) 9241 4324  
Email sydney@northrop.com.au ABN 81 094 433 100

PROJECT  
**AUSTRALIAN ARMS HOTEL  
351 HIGH STREET PENRITH,  
NSW 2750**

DRAWING TITLE  
**CIVIL DOCUMENTATION:  
DEVELOPMENT APPLICATION  
DETAILS - SHEET 02**

JOB NUMBER <b>200785</b>	
DRAWING NUMBER <b>DAC07.02</b>	REVISION <b>3</b>
DRAWING SHEET SIZE = A1	

Found: \\nas-files\project\2020 Jobs\200785 - Australian Arms Hotel\Drawings\Civil\CAD\CAD FILES\DAC07.02\DAC07.dwg    Printed By: JOHN O    Date: 18.03.2020 3:17 PM



LEGEND	
	BOUNDARY LINE
	EXISTING EASEMENT LINE
	OVERLAND FLOW
	CATCHMENT BOUNDARY

GENERAL NOTES	
1.	REFER TO CIVIL DRAWINGS / STORMWATER REPORT / DRAINS FILE FOR HYDROLOGICAL AND HYDRAULIC CALCULATIONS. CATCHMENTS INDICATED AND THEIR CORRESPONDING PITS ARE THOSE WHICH HAVE BEEN USED FOR MODELING PURPOSES.
2.	REFER HYDRAULIC ENGINEERS CALCULATIONS FOR ROOF DRAINAGE.

DRAWN: A.SUWAN    DESIGNED: XXXX    JOB MANAGER: N.SUTHERLAND    VERIFIER:

**NOT FOR CONSTRUCTION**

REVISION	DESCRIPTION	ISSUED	VER'D	APP'D	DATE
1	ISSUED FOR REVIEW	AS		NS	02.06.20
2	ISSUED FOR DEVELOPMENT APPLICATION	AS		NS	23.06.20
3	ISSUED FOR DEVELOPMENT APPLICATION	JO		NS	30.06.20

CLIENT

DRAWING NOT TO BE USED FOR CONSTRUCTION UNLESS VERIFICATION SIGNATURE HAS BEEN ADDED

ARCHITECT

**nra-co-lab**

THE COPYRIGHT OF THIS DRAWING REMAINS WITH NORTHROP CONSULTING ENGINEERS PTY LTD

ALL DIMENSIONS TO BE VERIFIED ON SITE BEFORE COMMENCING WORK. NORTHROP ACCEPTS NO RESPONSIBILITY FOR THE USABILITY, COMPLETENESS OR SCALE OF DRAWINGS TRANSFERRED ELECTRONICALLY. THIS DRAWING MAY HAVE BEEN PREPARED USING COLOUR, AND MAY BE INCOMPLETE IF COPIED TO BLACK & WHITE.

SCALE 1:200@A1

**NORTHROP**

Sydney

Level 11 345 George Street, Sydney NSW 2000  
 Ph (02) 9241 4188 Fax (02) 9241 4324  
 Email sydney@northrop.com.au ABN 81 094 433 100

PROJECT

**AUSTRALIAN ARMS HOTEL**  
 351 HIGH STREET PENRITH,  
 NSW 2750

DRAWING TITLE

**CIVIL DOCUMENTATION:  
 DEVELOPMENT APPLICATION  
 CATCHMENT PLAN**

JOB NUMBER	
200785	
DRAWING NUMBER	REVISION
<b>DAC08.01</b>	<b>3</b>
DRAWING SHEET SIZE = A1	

Found: \\nas\projects\2020 Jobs\200785 - Australian Arms Hotel\Drawings\Civil\CAD\CAD FILES\DAC08.01.dwg  
 Plotted By: JOHN O  
 Date: 19.03.2020 3:17 PM