



Douglas Partners

Geotechnics | Environment | Groundwater

Report on
Preliminary Site Investigation - Contamination

Proposed Cemetery
Wallacia Golf Course, Wallacia, NSW

Prepared for
Catholic Metropolitan Cemeteries Trust

Project 76652.02
June 2017

Integrated Practical Solutions





Douglas Partners

Geotechnics | Environment | Groundwater

Document History

Document details

Project No.	76652.02	Document No.	R.001.Rev0
Document title	Report on Preliminary Site Investigation - Contamination Proposed Cemetery		
Site address	Wallacia Golf Course, Wallacia, NSW		
Report prepared for	Catholic Metropolitan Cemeteries Trust		
File name	76652.02.R.001.Rev0		

Document status and review

Status	Prepared by	Reviewed by	Date issued
Revision 0	Grant Russell	J.M. Nash	6 June 2017

Distribution of copies

Status	Electronic	Paper	Issued to
Revision 0			John Richardson

The undersigned, on behalf of Douglas Partners Pty Ltd, confirm that this document and all attached drawings, logs and test results have been checked and reviewed for errors, omissions and inaccuracies.

	Signature	Date
Author		6 June 2017
Reviewer	 For J.M. Nash.	6 June 2017



Douglas Partners Pty Ltd
 ABN 75 053 980 117
www.douglaspartners.com.au
 18 Waler Crescent
 Smeaton Grange NSW 2567
 Phone (02) 4647 0075
 Fax (02) 4646 1886

Executive Summary

Douglas Partners Pty Ltd (DP) was commissioned by Catholic Metropolitan Cemeteries Trust (CMCT) to prepare a Preliminary Site Investigation (PSI) for the site located at 13 Park Road, Wallacia, NSW (the site). Land use at the site currently includes a golf course and associated amenities. DP understands that the assessment is required as part of a pre-purchase due diligence exercise, and to provide a background to support planning proposals for potential future redevelopment of the site as a cemetery.

The aim of the PSI is to provide preliminary contamination, salinity and acid sulphate soil information regarding the site. DP notes that the scope of works completed as part of the assessment is limited due to the confidential due diligence nature of the assessment, as requested by CMCT.

A site walkover and a review of site history information was undertaken to identify Potential Areas of Environmental Concern (PAEC) and Potential Contaminants of Concern (PCOC) which may arise from previous land uses. Given the reduced scope (based on the confidential nature of the assessment) the investigation was limited to a site walkover, review of aerial photographs, NSW EPA data base searches and listing of other potential site contamination issues based on DP experience with sites of a similar nature and scale.

The investigation identified 15 PAEC at the site and immediately surrounding areas. The majority of PAEC are associated with the identification of the following:

- Current onsite sheds and demolition / removal of several former sheds. The environmental concern is due to potential for chemical storage and hazardous building materials used within sheds;
- Possible burial of asbestos pipes given the age of the site and use as a golf course; and
- Areas of filling at the site.

The potential for contamination in PAEC associated with current / former sheds, pipe burial and filling is considered likely to be relatively localised in relation to the size of the site and presents a low to medium hazard rating (hazard rating of 1 to 2). Further intrusive investigation however is recommended to ascertain the extent of each PAEC and the presence or absence of related PCOC.

In addition given the site's use as a golf course for the past 40 years the use of fertilizers, pesticides and herbicides at the site is likely to have occurred. Whilst the likelihood of widespread fertilizer, pesticide and herbicide contamination at the site is considered to be low there is potential for localised hotspot contamination in the vicinity of former and current sheds due to storage / mixing malpractice and spillages; areas of spray equipment turning; tee boxes; and putting greens.

Noting the limited scope of works, DP considers that the potential risk of significant constraints to the proposed redevelopment of the site associated with land contamination, salinity and acid sulphate soils is low to medium.

With respect to site contamination the recommended further assessment should build on the information provided in this report with reference to National Environment Protection Council (NEPC, 1999) National Environment Protection Council (Assessment of Site Contamination) Measure 1999 (amended 2013) (NEPC, 2013). Further assessment should include intrusive investigations, sampling,

analysis and assessment to determine land use suitability. Further investigations should focus principally on the identified PAEC.

Table of Contents

	Page
1. Introduction.....	1
2. Scope of Works.....	1
3. Site Description	2
3.1 Site Identification.....	2
3.2 Site Description.....	2
3.3 Surrounding Landuse.....	3
3.4 Topography, Watercourses and Hydrology	3
3.5 Regional Geology and Soils	4
3.6 Salinity	4
3.7 Acid Sulphate Soils.....	5
3.8 Sensitive Receptors and Environments.....	5
4. Review of Site History Information.....	5
4.1 Historical Aerial Photography	5
4.2 Regulatory Notices Search	8
4.3 Review of Previous Environmental Reports	8
5. Potential for Areas of Environmental Concern.....	8
6. Summary of Findings	13
7. Conclusions and Recommendations	13
8. References.....	14
9. Limitations	14
Appendix A: Drawings	
Appendix B: NSW Office of Water Groundwater Bore Information	
Appendix C: NSW EPA Website Searches	
Appendix D: About this Report	

Report on Preliminary Site Investigation - Contamination Proposed Cemetery Wallacia Golf Course, Wallacia, NSW

1. Introduction

Douglas Partners Pty Ltd (DP) was commissioned by Catholic Metropolitan Cemeteries Trust (CMCT) to prepare a Preliminary Site Investigation (PSI) for the site located at 13 Park Road, Wallacia, NSW (the site) as shown on Drawing 1 (Appendix A). DP understands that the assessment is required as part of a pre-purchase due diligence exercise, and to provide a background to support planning proposals for potential future redevelopment of the site as a cemetery.

The site covers an approximate area of 44 ha and is located within the Local Government Area of Penrith City Council. Land use at the site currently includes a golf course and associated amenities.

The aim of the PSI is to provide preliminary contamination, salinity and acid sulphate soil information regarding the site. DP notes that the scope of works completed as part of the assessment is limited due to the confidential due diligence nature of the assessment, as requested by CMCT.

2. Scope of Works

The PSI included completion of the following scope of works:

- Undertaking a site visit and walkover to identify Potential Areas of Environmental Concern (PAEC);
- Review of local topographic, soil, geological, salinity and acid sulphate soils mapping;
- Search of the NSW EPA Land Information records to confirm that there are no statutory notices current on any parts of the site under the *Contaminated Land Management Act (1997)*;
- Search for groundwater bores on or adjacent to the site registered with the NSW Office of Water;
- Review of historical aerial photography for the area through the Land Information Section of the NSW Department of Planning;
- Determination of PAEC based on the review of aerial photographs and site inspection. Each PAEC was assessed individually to infer associated risk and hazard ratings; and
- Recommend requirements for future contamination, salinity and geotechnical investigations at the site.

3. Site Description

3.1 Site Identification

The site covers an approximate area of 44 ha and comprises the following land parcels as detailed in Table 1 below.

Table 1: Study Area Identification

Lot / Deposited Plan	Current Land Use	Approx. Area (ha)
13 Park Road		
2 / 1108408	Golf course	42.7
512 / 1079728	Golf course	1.6
Total Approximate Area		44.3

3.2 Site Description

The following site description is based on site inspection completed on 30 May 2017 and review of Nearmap Imagery.

The site is an irregular shaped property that comprises the Wallacia (Panthers) Golf and Country Club. The majority of the site is covered by grass covered fairways and putting greens. Several of the T-Boxes and putting greens were observed to be slightly elevated in relation to the surrounding topography indicating localised filling. A club house building is located in the far south western portion of the site and is constructed of timber board and brick walls, glass windows, ceramic tiled roofing and a concrete slab floor. An asphalt sealed carpark is located to the immediate south and west of club house and is accessed via an asphalt sealed driveway leading from Park Road located to the south of the site.

A shed is located in the central southern portion of the site and is constructed of corrugated steel walls and roofing upon a concrete slab floor. The steel shed appears to be used as greens keeper maintenance shed used for the storage of equipment such as ride on lawn mowers, spraying equipment and chain saws. Minor fuel/ oil and herbicide storage was observed within the southern portion of the shed. An electricity generator and large spraying equipment was observed adjacent to the north western corner of the shed.

Two 1000L above ground storage tanks (ASTs) were observed immediately adjacent to the exterior of northern wall of the shed. One AST was labelled as containing diesel while the other AST was labelled as containing petroleum. The AST area was underlain by a concrete slab and the concrete was stained in the vicinity of both ASTs. The concrete area underlying the ASTs was bunded on the down gradient western edge of the slab.

One man made dam is located in the far north western portion of the site and two manmade dams are located in the north eastern portion of the site. The dam walls and areas immediately surrounding all three of the dams appeared to have been filled as part of construction of the dams. A number of nearby gulleys also appear to have minor filling. A creek runs from one of the dams in the north

eastern portion of the site in an east-west direction along portions of the northern boundary of the site. Another small creek runs through the western portion of the site in a south-north direction. Both creeks appear to flow towards the Nepean River located to the west and northwest of the site.

A telecommunications tower is located nearby the dams in the north eastern portion of the site.

3.3 Surrounding Landuse

Site inspection and review of Nearmap imagery identified the following surrounding landuse:

North:	Rural residential properties.
East:	Rural residential properties.
South (eastern section):	Park Road, beyond which are mostly rural residential properties. A commercial water tank and pump business was observed immediately adjacent to the southeast boundary of the site where minor oil storage was observed in the storage yard.
South (western section):	Residential property, rural fire fighting service facility and a church, beyond which is Park Road and residential properties.
West:	Commercial and residential properties beyond which is Mulgoa Road. To the west of Mulgoa Road is a Caltex petrol station, post office, a school and residential properties.

3.4 Topography, Watercourses and Hydrology

Reference to the 1:100 000 Penrith topographic Series Sheet indicates that the site grades from approximately 70 m above Australian High Datum (AHD) in the east to approximately 40 m AHD in the west. The landform conforms to intermittent tributaries of Jerry's Creek which meander from east to west to meet the Nepean River approximately 300 m west of site boundary. A number of farm dams are present within the site along the lengths of Jerry's Creek.

Topographic contours and watercourses within and surrounding the site are shown on Drawing 2 (Appendix A).

A search of the NSW Office of Water groundwater bore data was undertaken by DP on 30 May 2017 and identified four bores within 1km of the site as shown on Drawing 2 (Appendix A) and detailed in Appendix B. Table 2 below provides a summary of information for each bore.

Table 2: Summary of Groundwater Bore Search

Bore ID	Approx. Distance (m) / Direction from Site	Date of Installation	Bore Use	Total Depth (m)	Depth of Water Bearing Zones (m)
GW109120	South / 100 m	25/07/2008	Domestic Stock	180 m	None Provided
GW075144	Southwest / 400 m	14/07/2008	Monitoring Bore	10.6 m	None Provided
GW075161	Southwest / 450 m	06/08/2007	Test Bore – Town Water Supply	300 m	At 17-18 m and multiple below 126 m
GW075162	Southwest / 500 m	03/08/2007	Monitoring Bore	24 m	At 10.5 – 11 m

With the exception of GW109120, all wells are down hydraulic gradient of the site.

3.5 Regional Geology and Soils

Reference to the 1:100 000 Penrith Geological Series Sheet indicates that the majority of the site (as shown on Drawing 3, Appendix A) is underlain by Bringelly Shale (mapping unit Rwb) of the Wianamatta Group of Middle Triassic period. This formation typically comprises shale, carbonaceous claystone, claystone, laminate, fine to medium-grained lithic sandstone, rare coal and tuff. An area of fluvial sediments (mapping unit Qa1) of the Quaternary period is present within the south-western portion of the site associated with the alignment of a tributary of Jerry's Creek. This formation typically comprises fine grained sand, silt and clay.

The Penrith 1:100,000 Soils Landscape Sheet indicates that the majority of the site (as shown on Drawing 4, Appendix A) is within the Luddenham Soil Landscape which is associated with erosional processes. Limitations associated with the Luddenham Soil Landscape include high erosion hazard, localised impermeable plastic subsoil and moderate reactivity.

An area of the Richmond Soil Landscape is present in part of the southern-western portion of the site which is associated with alluvial processes and a tributary to Jerry's Creek. Limitations associated with the Richmond Soil Landscape include high erosion hazard on terrace edges and localised flooding. The south-western most portion of the site comprises the Blacktown Soil Landscape which is associated with residual soil processes. Limitations associated with the Blacktown Soil Landscape include moderately reactive highly plastic subsoil, low soil fertility and poor soil drainage.

3.6 Salinity

According to the Department of Infrastructure Planning and Natural Resources (DIPNR, 2002) 'Salinity Potential in Western Sydney' map, the study area is categorised as having 'Moderate Salinity Potential'. This zone is described as 'Areas on the Wianamatta Group Shales and Tertiary Alluvial Terraces. Scattered areas of scalding and indicator vegetation have been noted but no concentrations have been mapped. Saline areas may occur in this zone, which have not been identified or may occur if risk factors change adversely.'

3.7 Acid Sulphate Soils

Review of NSW Government Office of Environment and Heritage Acid Sulphate Soils Risk mapping indicates that the site is classified as having '*no known occurrence of acid sulphate soil*'.

3.8 Sensitive Receptors and Environments

The nearest sensitive receptors and environments have been identified as follows:

- The nearest residential properties are located on Park Road and Mulgoa Road immediately adjacent to the site's southern and western boundaries respectively;
- A school is located approximately 60m west of the south-western site boundary beyond Mulgoa Road;
- The primary environmental receptor down-gradient of the site is Jerry's Creek which flows to the Nepean River approximately 300 m west of the site boundary;
- Groundwater beneath the site;
- Current and future site workers; and
- Future site visitors.

4. Review of Site History Information

A review of site history information has been undertaken to identify PAEC and contaminants of concern which may arise from previous land uses. Given the reduced scope (based on the confidential nature of the assessment) the investigation was limited to a review of aerial photographs, NSW EPA data base searches and listing of other potential site contamination issues based on DP experience with sites of a similar nature and scale.

The following sections detail the methodology of the investigation.

4.1 Historical Aerial Photography

Historical aerial photographs were reviewed to assist in identifying the history of the site and the surrounding area. Images from 1942, 1961, 1975, 1986, 1998, 2002 and 2005 were sourced from NSW Land and Property Information. Additionally, a 2014 image was sourced from Nearmaps. All aerial photographs are provided in Drawings 5 to 12 respectively (Appendix A).

A summary of the review of historical aerial photography is detailed in the following table.

Table 3: Summary of Review of Historical Aerial Photographs

Year	Site / Surrounds	Description
1942	Site	<p>The majority of the site is vacant grass covered cleared land that appears to be used for grazing purposes. Two small shed like structures are located adjacent to the western boundary of the site.</p> <p>A creek runs through the western portion of the site in a south-north direction. Remnant native vegetation lines the banks of the creek. A cluster of remnant native vegetation with several larger trees exists in the north eastern portion of the site.</p>
	Surrounds	<p>North – The majority of land appears to be vacant cleared land used for grazing purposes</p> <p>East - The majority of land appears to be vacant cleared land used for grazing purposes</p> <p>South – Park Road has been constructed to the immediate south of the site. Land beyond to the south appears to be vacant cleared land used for grazing purposes</p> <p>West – Land to the immediate southwest of the site appears to have been developed for residential and commercial purposes and several dwellings have been constructed. Land to the immediate northwest appears to be vacant cleared land used for grazing purposes. Mulgoa Road has been developed beyond to the west with residential dwellings and vacant cleared land located beyond.</p>
1961	Site	<p>The site appears to have been developed into a golf course. A number of greens have been developed in the central and eastern portions of the site.</p> <p>A small shed like structure appears to have been constructed in the central portion of the site.</p> <p>The small shed structure in the central portion of the western boundary appears to have been demolished and removed from site.</p> <p>The small shed like structure in the far south western corner of the site appears to have had undergone extension works added adjacent to the eastern and northern walls of the structure.</p> <p>A large man made dam has been constructed in the north eastern portion of the site.</p> <p>The remainder of the site appears similar to the previous historical aerial photograph.</p>
	Surrounds	<p>North – A small shed like structure has been constructed adjacent to the northwest boundary of the site. The majority of the remainder of the land appears similar to the previous aerial photograph.</p> <p>East - The majority of the land appears similar to the previous</p>

Year	Site / Surrounds	Description
		<p>aerial photograph.</p> <p>South – The majority of the land appears similar to the previous aerial photograph.</p> <p>West – There appears to be further residential development adjacent to the western boundary of the site. The majority of the remainder of the land appears similar to the previous aerial photograph.</p>
1975	Site	<p>The small shed previously identified in the central portion of the site appears to have been demolished and removed from site.</p> <p>A number of trees appear to have been planted lining the fairways of the golf course.</p> <p>The remainder of the site appears similar to the previous historical aerial photograph.</p>
	Surrounds	<p>The majority of the land surrounding the site appears similar to the previous aerial photograph.</p>
1986	Site	<p>A manmade dam has been constructed in the north western portion of the site and another smaller manmade dam constructed in the north eastern portion of the site.</p> <p>The remainder of the site appears similar to the previous historical aerial photograph.</p>
	Surrounds	<p>A number of rural residential properties have been developed to the southeast of the site and further residential development has occurred to the southwest and west of the site.</p> <p>The majority of the remaining land surrounding the site appears similar to the previous aerial photograph.</p>
1998	Site	<p>A shed like structure appears to have been constructed in the central portion of the site. Areas of ground disturbance appear in the north eastern portions of the site.</p> <p>The remainder of the site appears similar to the previous historical aerial photograph.</p>
	Surrounds	<p>The majority of the land surrounding the site appears similar to the previous aerial photograph.</p>
2002	Site	<p>An area of ground disturbance appears in the north western portions of the site.</p> <p>The remainder of the site appears similar to the previous historical aerial photograph.</p>
	Surrounds	<p>A service station appears to have been constructed beyond Mulgoa Road to the west of the site.</p> <p>The majority of the remaining land surrounding the site appears similar to the previous aerial photograph.</p>
2005	Site	<p>Area of ground disturbance appears in the far northern and south</p>

Year	Site / Surrounds	Description
		western portions of the site. The remainder of the site appears similar to the previous historical aerial photograph.
	Surrounds	The majority of the land surrounding the site appears similar to the previous aerial photograph.
2014	Site	The site appears similar to the previous historical aerial photograph.
	Surrounds	An area to the immediate north of the central portion of the site appears to be used for cropping / market gardening purposes The majority of the remaining land surrounding the site appears similar to the previous aerial photograph.

4.2 Regulatory Notices Search

A search of the NSW EPA website on 22 May 2017 indicated that:

- No Licences have been issued for the site (or immediately adjacent sites) under the Protection of the Environment Operations Act, 1997;
- No Notices or Orders to investigate or remediate the site (or immediately adjacent sites) have been issued for the site under the Contaminated Land Management Act, 1997; and
- The site (or immediately adjacent sites) is not recorded on the list of NSW contaminated sites reported to the EPA.

Search results are presented in Appendix C.

4.3 Review of Previous Environmental Reports

No previous environmental reports incorporating the site were provided to DP for the purposes of the PSI.

5. Potential for Areas of Environmental Concern

Table 3 below lists the 15 PAEC identified during the review of historical aerial photographs and site inspection. The Caltex Service Station located on the western side of Mulgoa Road is also listed as a PAEC (PAEC 15) based on its proximity to the site and possibility that fuel leakage may occur or may have occurred in the past.

For each PAEC, the likelihood of occurrence and a hazard ranking has been estimated. For the purpose of this due diligence investigation hazard rankings are based on the potential areas across which the PAEC are estimated to occur, as outlined below.

Hazards Rankings:

- 1 = Potential impact area <100 m² (approx.)
- 2 = Potential impact area between 100 m² and 1000 m² (approx.)
- 3 = Potential impact area between 1000 m² and 1 ha (approx.)
- 4 = Potential impact area >1 ha (approx.)

It should be noted that hazard rankings are based primarily on potential area affected therefore a ranking of 4 represents a greater potential impacted hazard area than a rating of 1 or 2. The concentrations of potential contaminants of concern (PCOC) found in an area may also increase or decrease a hazard rating but have been given significantly less weighting in this calculation of potential hazard. The expected concentrations of PCOC cannot be given a more significant weighting in hazard calculations without further intrusive investigations.

Table 3: Summary of Identified Potential Areas of Environmental Concern

PAEC #	Identified from	Brief Description	Potential Environmental Concern	Potential Contaminants of Concern (PCOC)	Likelihood	Hazard
1	1947 AP	Structure (possible dwelling) – potentially demolished prior to 1961 or extended to form current building (golf course club house).	Impacted surface soil – construction and demolition debris (possibly including asbestos), and use of pesticides and lead based paints.	Metals, OCP, OPP and Asb.	50%	1
2	1947 AP	Former structure (possible shed) – demolished prior to 1975.	Impacted surface soil – construction and demolition debris (possibly including asbestos), use of pesticides and lead based paints, and storage of chemicals.	Metals, TRH, PAH, phenols, OCP, OPP and Asb.	50%	1
3	1961 AP	Potential former structure (type unknown) – not present in 1975 AP.	Impacted surface soil.	Metals, BTEX, TRH, PAH, phenols, OCP, OPP and Asb.	10%	1
4	1961 – 1986 AP	Former structures (small dwellings or sheds) – demolished prior to 1998.	Impacted surface soil – construction and demolition debris (possibly including asbestos), use of pesticides and lead based paints, and storage of chemicals.	Metals, BTEX, TRH, PAH, phenols, OCP, OPP and Asb.	75%	2
5-1	1975 – current AP	Golf course – existing in current.	Asbestos pipes.	Asb	75%	2
5-2			Application of pesticides herbicides and fertilisers to tees and greens.	Metals, fertilisers and OCPs	90%	2
5-3			Broad-scale application of fertilisers herbicides and pesticides*.	Metals and fertilisers, OCP and OPP	25%	2*

PAEC #	Identified from	Brief Description	Potential Environmental Concern	Potential Contaminants of Concern (PCOC)	Likelihood	Hazard
5-4			Filling of creeks and gullies with impacted material from an unknown source	Metals, BTEX, TRH, PAH, phenols, OCP, OPP, PCB and Asb.	50%	1-3
6	1975 – 2002 AP	Residential dwellings and sheds (two lots) developed between prior to 1975 and 2002. Western lot demolished prior to 2005 and converted to car-parking area.	Impacted surface soil – construction and demolition debris (possibly including asbestos), use of pesticides, herbicides and lead based paints, and storage of chemicals.	Metals, BTEX, TRH, PAH, phenols, OCP, OPP and Asb	75%	2
7	1986 – 1998 AP	Hardstand car parking area developed between prior to 1986 and 1998 – existing in current AP.	Elevated PAH concentrations in asphaltic concrete.	PAH	10%	2
8	1986 AP	Former structure (possible shed) – demolished prior to 1998.	Impacted surface soil – construction and demolition debris, use of pesticides and lead based paints, and storage of chemicals.	Metals, BTEX, TRH, PAH, phenols, OCP, OPP and Asb.	25%	1
9	1998 AP	Shed (golf course maintenance) - existing in current AP and observed during site inspection.	Impacted surface soil – use of pesticides, and storage of chemicals (two 1000L ASTs observed adjacent to shed).	Metals, BTEX, TRH, PAH, phenols, OCP and OPP.	50%	2
10	1998 AP	Ground disturbance.	Impacted filling from an unknown source	Metals, BTEX, TRH, PAH, phenols, OCP, OPP, PCB and Asb.	25%	1

PAEC #	Identified from	Brief Description	Potential Environmental Concern	Potential Contaminants of Concern (PCOC)	Likelihood	Hazard
11	2002 AP	Ground disturbance.	Impacted filling from an unknown source.	Metals, BTEX, TRH, PAH, phenols, OCP, OPP, PCB and Asb.	50%	1
12	2005 AP	Ground disturbance.	Impacted filling from an unknown source.	Metals, BTEX, TRH, PAH, phenols, OCP, OPP, PCB and Asb.	50%	2
13	2005 AP	Ground disturbance.	Impacted filling from an unknown source.	Metals, BTEX, TRH, PAH, phenols, OCP, OPP, PCB and Asb.	50%	2
14	Current AP	Adjacent potential market garden.	Application of fertilisers, pesticides and herbicides.	Metals, fertilisers, OCP and OPP.	35%	3
15	Proximity to the site.	Petrol Service Station (down hydraulic gradient of the site)	Migration of hydrocarbon impacted groundwater onto the site	Metals, BTEX and TRH.	<5%	1-2

Notes:

Metals = arsenic (As), cadmium (Cd), chromium (Cr), copper (Cu), lead (Pb), mercury (Hg), nickel (Ni) and zinc (Zn).

TRH = Total recoverable hydrocarbons.

BTEX = Benzene, toluene, ethylbenzene and xylenes.

PCB = Polychlorinated biphenyls.

PAH = Polycyclic aromatic hydrocarbons.

OCP = Organochlorine pesticides.

OPP = Organophosphorous pesticides.

Asb. = Asbestos.

AP = Aerial Photograph(s).

* = Hazard rating reduced due to low likelihood of broad scale application of pesticides given sites use as a golf course and not used for intensive agricultural purposes

6. Summary of Findings

A summary of the findings of the PSI, based on the completed scope of works is provided below:

- 15 PAEC were identified at the site and immediately surrounding areas (PAEC 1 to PAEC 15);
- Six PAEC were inferred to have hazard rating of 1 (potential impact area <100 m²);
- Ten PAEC were inferred to have hazard rating of 2 (potential impact area between 100 m² and 1000 m²); and
- Two PAEC were inferred to have hazard rating of 3 (potential impact area between 1000 m² and 1 ha).

The site is categorised as having a moderate salinity potential and no known or likely occurrence of acid sulphate soils.

7. Conclusions and Recommendations

The investigation identified 15 PAEC at the site and immediately surrounding areas. The majority of PAEC are associated with the identification of the following:

- Current onsite sheds and demolition / removal of several former sheds. The environmental concern is due to potential for chemical storage and hazardous building materials used within sheds;
- Possible burial of asbestos pipes given the age of the site and use as a golf course; and
- Areas of filling at the site.

The potential for contamination in PAEC associated with current / former sheds, pipe burial and filling is considered likely to be relatively localised in relation to the size of the site and presents a low to medium hazard rating (hazard rating of 1 to 2). Further intrusive investigation however is recommended to ascertain the extent of each PAEC and the presence or absence of related PCOC.

In addition given the site's use as a golf course for the past 40 years the use of fertilizers, pesticides and herbicides at the site is likely to have occurred. Whilst the likelihood of widespread fertilizer, pesticide and herbicide contamination at the site is considered to be low there is potential for localised hotspot contamination in the vicinity of former and current sheds due to storage / mixing malpractice and spillages; areas of spray equipment turning; tee boxes; and putting greens.

Noting the limited scope of works, DP considers that the potential risk of significant constraints to the proposed redevelopment of the site associated with land contamination, salinity and acid sulphate soils is low to medium.

With respect to site contamination the recommended further assessment should build on the information provided in this report with reference to National Environment Protection Council (NEPC, 1999) National Environment Protection Council (Assessment of Site Contamination) Measure 1999 (amended 2013) (NEPC, 2013). Further assessment should include intrusive investigations, sampling, analysis and assessment to determine land use suitability. Further investigations should focus principally on the identified PAEC.

8. References

1. Department of Infrastructure Planning and Natural Resources (DIPNR, 2002) '*Salinity Potential in Western Sydney*' map.
2. Nearmap website, <https://go.nearmap.com/>
3. NSW Department of Planning and Environment - Resources and Energy, Geological Survey of NSW 1:100 000 Penrith Geological Series Sheet 9030.
4. NSW Department of Primary Industries Office of Water website <http://allwaterdata.water.nsw.gov.au/water.stm>
5. NSW Government Office of Environment and Heritage Acid Sulphate Soils Risk Maps
6. NSW Land and Property Information, Historical Aerial Photographs for Wallacia for years 1942, 1961, 1975, 1986, 1998, 2002 and 2005.

9. Limitations

Douglas Partners (DP) has prepared this report (or services) for this project at 13 Park Road, Wallacia NSW in accordance with DP's proposal dated 15 May 2017 and acceptance received from dated 15 May 2017. The work was carried out under DP's Conditions of Engagement. This report is provided for the exclusive use of CMCT for this project only and for the purposes as described in the report. It should not be used by or relied upon for other projects or purposes on the same or other site or by a third party. Any party so relying upon this report beyond its exclusive use and purpose as stated above, and without the express written consent of DP, does so entirely at its own risk and without recourse to DP for any loss or damage. In preparing this report DP has necessarily relied upon information provided by the client and/or their agents.

The results provided in the report are indicative of the sub-surface conditions on the site only at the specific sampling and/or testing locations, and then only to the depths investigated and at the time the work was carried out. Sub-surface conditions can change abruptly due to variable geological processes and also as a result of human influences. Such changes may occur after DP's field testing has been completed.

DP's advice is based upon the conditions encountered during this investigation. The accuracy of the advice provided by DP in this report may be affected by undetected variations in ground conditions across the site between and beyond the sampling and/or testing locations. The advice may also be limited by budget constraints imposed by others or by site accessibility.

This report must be read in conjunction with all of the attachments/appendices and should be kept in its entirety without separation of individual pages or sections. DP cannot be held responsible for interpretations or conclusions made by others unless they are supported by an expressed statement, interpretation, outcome or conclusion stated in this report.

This report, or sections from this report, should not be used as part of a specification for a project, without review and agreement by DP. This is because this report has been written as advice and opinion rather than instructions for construction.

The contents of this report do not constitute formal design components such as are required, by the Health and Safety Legislation and Regulations, to be included in a Safety Report specifying the hazards likely to be encountered during construction and the controls required to mitigate risk. This design process requires risk assessment to be undertaken, with such assessment being dependent upon factors relating to likelihood of occurrence and consequences of damage to property and to life. This, in turn, requires project data and analysis presently beyond the knowledge and project role respectively of DP. DP may be able, however, to assist the client in carrying out a risk assessment of potential hazards contained in the Comments section of this report, as an extension to the current scope of works, if so requested, and provided that suitable additional information is made available to DP. Any such risk assessment would, however, be necessarily restricted to the (geotechnical / environmental / groundwater) components set out in this report and to their application by the project designers to project design, construction, maintenance and demolition.

Douglas Partners Pty Ltd


Appendix A

Drawings




Legend

 Site Boundary



CLIENT: Catholic Metropolitan Cemeteries Trust
 OFFICE: Macarthur DRAWN BY: GAR
 SCALE: As shown DATE: 25.5.2017

TITLE: **Site Locality and Boundary**
Preliminary Site Investigation
13 Park Road, Wallacia NSW



PROJ No: 76652.02.R1
 DRAWING No: 1
 REVISION: A




- Legend**
- Site Boundary
 - Water Course
 - 10 m contour
 - ▲ Groundwater Bore



CLIENT: Catholic Metropolitan Cemeteries Trust
 OFFICE: Macarthur DRAWN BY: GAR
 SCALE: As shown DATE: 25.5.2017

TITLE: Topography, Water Courses and Groundwater Bores
 Preliminary Site Investigation
 13 Park Road, Wallacia NSW




PROJ No: 76652.02.R1
 DRAWING No: 2
 REVISION: A



Legend

 Site Boundary



CLIENT: Catholic Metropolitan Cemeteries Trust


OFFICE: Macarthur

DRAWN BY: GAR

SCALE: As shown

DATE: 25.5.2017

TITLE: **Regional Geological Landscape
Preliminary Site Investigation
13 Park Road, Wallacia NSW**



PROJ No: 76652.02.R1


DRAWING No: 3

REVISION: A




Legend

 Site Boundary




CLIENT: Catholic Metropolitan Cemeteries Trust
 OFFICE: Macarthur DRAWN BY: GAR
 SCALE: As shown DATE: 25.5.2017

TITLE: Regional Soil Landscape
 Preliminary Site Investigation
 13 Park Road, Wallacia NSW




PROJ No: 76652.02.R1
 DRAWING No: 4
 REVISION: A




Legend

 Site Boundary




CLIENT: Catholic Metropolitan Cemeteries Trust
 OFFICE: Macarthur DRAWN BY: GAR
 SCALE: As shown DATE: 25.5.2017

TITLE: **Historical Aerial Photograph - 1961**
Preliminary Site Investigation
13 Park Road, Wallacia NSW



PROJ No: 76652.02.R1
 DRAWING No: 6
 REVISION: A




Legend

 Site Boundary




CLIENT: Catholic Metropolitan Cemeteries Trust
 OFFICE: Macarthur DRAWN BY: GAR
 SCALE: As shown DATE: 25.5.2017

TITLE: **Historical Aerial Photograph - 1975**
Preliminary Site Investigation
13 Park Road, Wallacia NSW




PROJ No: 76652.02.R1
 DRAWING No: 7
 REVISION: A



Legend

 Site Boundary



CLIENT: Catholic Metropolitan Cemeteries Trust


OFFICE: Macarthur

DRAWN BY: GAR

SCALE: As shown

DATE: 25.5.2017

TITLE: **Historical Aerial Photograph - 1986**
Preliminary Site Investigation
13 Park Road, Wallacia NSW



PROJ No: 76652.02.R1


DRAWING No: 8

REVISION: A



Legend

 Site Boundary



CLIENT: Catholic Metropolitan Cemeteries Trust


OFFICE: Macarthur

DRAWN BY: GAR

SCALE: As shown

DATE: 25.5.2017


TITLE: **Historical Aerial Photograph - 1998**
Preliminary Site Investigation
13 Park Road, Wallacia NSW



PROJ No: 76652.02.R1


DRAWING No: 9

REVISION: A



Legend

 Site Boundary



CLIENT: Catholic Metropolitan Cemeteries Trust


OFFICE: Macarthur

DRAWN BY: GAR

SCALE: As shown

DATE: 25.5.2017


TITLE: **Historical Aerial Photograph - 2002**
Preliminary Site Investigation
13 Park Road, Wallacia NSW



PROJ No: 76652.02.R1

DRAWING No: 10

REVISION: A




Legend

 Site Boundary



CLIENT: Catholic Metropolitan Cemeteries Trust
 OFFICE: Macarthur DRAWN BY: GAR
 SCALE: As shown DATE: 25.5.2017

TITLE: **Historical Aerial Photograph - 2005**
Preliminary Site Investigation
13 Park Road, Wallacia NSW




PROJ No: 76652.02.R1
 DRAWING No: 11
 REVISION: A




Legend

 Site Boundary




CLIENT: Catholic Metropolitan Cemeteries Trust
 OFFICE: Macarthur DRAWN BY: GAR
 SCALE: As shown DATE: 25.5.2017

TITLE: **Historical Aerial Photograph - 2014**
Preliminary Site Investigation
13 Park Road, Wallacia NSW



PROJ No: 76652.02.R1
 DRAWING No: 12
 REVISION: A




Legend
 Site Boundary



CLIENT: Catholic Metropolitan Cemeteries Trust
 OFFICE: Macarthur DRAWN BY: GAR
 SCALE: As shown DATE: 25.5.2017

TITLE: **Historical Aerial Photograph - 2014 (All AEC)**
Preliminary Site Investigation
13 Park Road, Wallacia NSW



PROJ No: 76652.02.R1
 DRAWING No: 13
 REVISION: A

Appendix B

NSW Office of Water Groundwater Bore Information



[close this window](#)

[home](#) · [help](#) · [login](#) · [contact](#) · [customise](#)

All Groundwater
find a site

- All Groundw...
- North Coa...
- Hunter Re...
- Greater S...
- Hawk...**
- George...
- Wollon...
- South Coa...
- Northwest...
- Central W...
- Southwes...
- Far West...
- Great Arte...
- Coal Basins


bandwidth high low

[glossary and metadata](#)

All Groundwater » All Groundwater Map » Greater Sydney Region
Hawkesbury River Basin [bookmark this page](#)

All data times are Eastern Standard Time

Map



Appendix C

NSW EPA Website Searches

[Home](#) [Contaminated land](#) [Record of notices](#)

Search results

Your search for:LGA: Penrith City Council

Matched 23 notices
relating to 7 sites.

[Search Again](#)
[Refine Search](#)

Suburb	Address	Site Name	Notices related to this site
BERKSHIRE PARK	(Northern end of Compartment 5) The Northern ROAD	Castlereagh State Forest	6 former
COLYTON	88 Great Western HIGHWAY	Ampol Service Station	1 current
JAMISONTOWN	92 Mulgoa ROAD	7-Eleven Service Station	2 current
LUDDENHAM	Lot 4 The Northern ROAD	Elura Liquid Waste Disposal Site	1 current
MULGOA	Mulgoa ROAD	Penrith Waste Services	2 former
PENRITH	Castlereagh ROAD	Crane Enfield Metals	3 current and 3 former
ST MARYS	Vallance STREET	Drum Recycler	5 former

Page 1 of 1

22 May 2017

Connect

Feedback

Contact

Government

About

[Web support](#)
[Public consultation](#)

[Contact us](#)
[Offices](#)
[Report pollution](#)

[NSW Government](#)
[jobs.nsw](#)

[Accessibility](#)
[Disclaimer](#)
[Privacy](#)
[Copyright](#)

[Home](#) > [Environment protection licences](#) > [POEO Public Register](#) > [Search for licences, applications and notices](#)

Search results

Your search for: **General Search** with the following criteria

Suburb - Wallacia

returned 23 results

[Export to excel](#)

1 of 2 Pages

[Search Again](#)

<u>Number</u>	<u>Name</u>	<u>Location</u>	<u>Type</u>	<u>Status</u>	<u>Issued date</u>	<u>Connect</u>	<u>Fee</u>
1501707	Bernard Fussell	665 Bents Basin Road, WALLACIA, NSW 2745	s.91 Clean Up Notice	Issued	11 Nov 2011		
3085769180	Bernard Fussell	665 Bents Basin Road, WALLACIA, NSW 2745	Penalty Notice	Issued	22 Feb 2013		
3085772021	Bernard Fussell	665 Bents Basin Road, WALLACIA, NSW 2745	Penalty Notice	Issued	05 Aug 2013		
1540640	DIB HANNA ABDALLAH HANNA	82 Park Road, WALLACIA, NSW 2745	s.91 Clean Up Notice	Issued	07 Sep 2016		
1516188	Hendrick Cornelis Mak	1600 Greendale Road, Wallacia , WALLACIA, NSW 2745	s.91 Clean Up Notice	Issued	12 Nov 2013		
3085774203	Hendrick Cornelis Mak	1600 Greendale Road, Wallacia , WALLACIA, NSW 2745	Penalty Notice	Issued	29 May 2014		
3085774212	Hendrick Cornelis Mak	1600 Greendale Road, Wallacia , WALLACIA, NSW 2745	Penalty Notice	Issued	29 May 2014		
1509036	Joseph and Karen Bugeja	470 Bents Basin Road, WALLACIA, NSW 2745	s.91 Clean Up Notice	Issued	25 Sep 2012		Wet Pub
1547023	Michael SUKKAR	1504 Mulgoa Road, WALLACIA, NSW 2745	s.91 Clean Up Notice	Issued	03 Feb 2017		
1547278	Michael SUKKAR	147 Park Road, WALLACIA, NSW 2745	s.91 Clean Up Notice	Issued	03 Feb 2017		
1508170	Rob Dorn	344 Park Road, WALLACIA, NSW 2745	s.91 Clean Up Notice	Issued	15 Aug 2012		
12235	SYDNEY WATER CORPORATION	including the STP at NORTONS BASIN ROAD, WALLACIA, NSW 2745	POEO licence	Issued	23 Dec 2004		
1074762	SYDNEY WATER CORPORATION	including the STP at NORTONS BASIN ROAD, WALLACIA, NSW 2745	s.58 Licence Variation	Issued	27 Jun 2007		
1081518	SYDNEY WATER CORPORATION	including the STP at NORTONS BASIN ROAD, WALLACIA, NSW 2745	s.58 Licence Variation	Issued	16 Sep 2008		
1116054	SYDNEY WATER CORPORATION	including the STP at NORTONS BASIN ROAD, WALLACIA, NSW 2745	s.58 Licence Variation	Issued	02 Jul 2010		
1129009	SYDNEY WATER CORPORATION	including the STP at NORTONS BASIN ROAD, WALLACIA, NSW 2745	s.58 Licence Variation	Issued	27 Jun 2011		
1504906	SYDNEY WATER CORPORATION	including the STP at NORTONS BASIN ROAD, WALLACIA, NSW 2745	s.58 Licence Variation	Issued	28 Jun 2012		
1512452	SYDNEY WATER CORPORATION	including the STP at NORTONS BASIN	Compliance Audit	Complete	27 Feb 2013		

<u>1528931</u>	SYDNEY WATER CORPORATION	ROAD, WALLACIA, NSW 2745 including the STP at NORTONS BASIN ROAD, WALLACIA, NSW 2745	s.58 Licence Issued Variation	23 Mar 2015
<u>1538209</u>	SYDNEY WATER CORPORATION	including the STP at NORTONS BASIN ROAD, WALLACIA, NSW 2745	s.58 Licence Issued Variation	19 Feb 2016

[12](#)

22 May 2017

Suburb	Site Name	Site Address	Contamination Activity Type	EPA Management Class	Latitude	Longitude
WAGGA WAGGA	Coles Express Wagga Wagga	357-359 Edward STREET	Service Station	Under assessment	-35.11606625	147.3509339
WAGGA WAGGA	Former Gasworks	54 Chaston STREET	Gasworks	Contamination currently regulated under CLM Act	-35.12262069	147.3482778
WAGGA WAGGA	Former Caltex Depot	60 Lake Albert DRIVE	Service Station	Regulation under CLM Act not required	-35.12316794	147.37724
WAGGA WAGGA	Caltex-branded (former Mobil) Service Station	7 Lake Albert ROAD	Service Station	Under assessment	-35.12239591	147.3769936
WAGGA WAGGA	Former Gasworks	Cnr Tarcutta Street and Cross STREET	Gasworks	Contamination currently regulated under CLM Act	-35.10871183	147.3737933
WAGGA WAGGA	Ashmont Autoport	Cnr Tobruk Street and Bardia STREET	Service Station	Regulation under CLM Act not required	-35.12517373	147.329919
WAGGA WAGGA	Caltex Service Station	Docker St Cnr Edward STREET	Service Station	Under assessment	-35.11737947	147.3558145
WAGGA WAGGA	Former Wiradjuri landfill	Narrung STREET	Landfill	Under assessment	-35.09628532	147.3619535
WAHROONGA	7-Eleven Service Station	1579 Pacific HIGHWAY	Service Station	Under assessment	-33.71974617	151.1168106
WAHROONGA	Coles Express Wahroonga	1601 Pacific HIGHWAY	Service Station	Regulation under CLM Act not required	-33.71945571	151.1163002
WAITARA	Caltex Service Station	59-61 Pacific HIGHWAY	Service Station	Regulation under CLM Act not required	-33.71064349	151.1024644
WALGETT	Former Shell Depot	Castlereagh HIGHWAY	Other Petroleum	Regulation under CLM Act not required	-30.00861179	148.1239938
WALLERAWANG	Wallerawang Power Station	1 Main STREET	Other Petroleum	Under assessment	-33.40339296	150.0855101
WALLERAWANG	Lidsdale Coal Loading Facility	Main STREET	Other Industry	Under assessment	-33.39996523	150.0737717
WALLSEND	Coles Express Wallsend East	15 Thomas STREET	Service Station	Regulation under CLM Act not required	-32.90719444	151.6693426
WALLSEND	Caltex Maryland Service Station Wallsend	41 Minmi ROAD	Service Station	Regulation under CLM Act not required	-32.88967866	151.6619253
WALLSEND	OneSteel Recycling	64-80 Sandgate ROAD	Metal Industry	Regulation under CLM Act not required	-32.89425477	151.6799648
WALLSEND	Ausgrid Wallsend Depot	Abbott STREET	Other Industry	Regulation under CLM Act not required	-32.90162796	151.6857267
WAMBERAL	Caltex Service Station	654 The Entrance ROAD	Service Station	Under assessment	-33.42338668	151.4375685
WANGI WANGI	Myuna Colliery	Wangi Point ROAD	Other Industry	Under assessment	-33.06139532	151.5697186
WARATAH	Waratah Area Health	Turton ROAD	Unclassified	Regulation under CLM Act not required	-32.90961233	151.7260867
WARILLA	Woolworths Petrol Warilla	43 -57 Shellharbour ROAD	Service Station	Regulation under CLM Act not required	-34.5470966	150.863748
WARKWORTH	United Collieries	134 Jerry Plain ROAD	Other Industry	Under assessment	-32.5654356	150.9916698
WARKWORTH	Emulsion Plant, Dyno Nobel Asia Pacific Pty Ltd	186 Long Point ROAD	Chemical Industry	Under assessment	-32.5781708	151.0834387
WARNERS BAY	7-Eleven (former Mobil) Service Station	393 Hillsborough ROAD	Service Station	Regulation under CLM Act not required	-32.9659363	151.6543264
WARNERS BAY	Historically Filled Land	41-43 Charles STREET	Unclassified	Regulation under CLM Act not required	-32.97340461	151.6464383
WARNERS BAY	Caltex Service Station	55 King STREET	Service Station	Under assessment	-32.97418806	151.6476184
WARNERVALE	Former Timber Treatment Plant	Aldenham and Railway ROADS	Other Industry	Contamination formerly regulated under the CLM Act	-33.24732018	151.4469037
WARRAGAMBA	Warragamba Dam Viewing Platform	Eighteenth STREET	Unclassified	Under assessment	-33.88546354	150.6024501
WARRAWONG	Caltex Service Station	75-77 King STREET	Service Station	Regulation under CLM Act not required	-34.49037817	150.888802

Appendix D

About this Report

About this Inspection Report

Douglas Partners



Introduction

These notes are provided to amplify DP's inspection report in regard to the limitations of carrying out inspection work. Not all notes are necessarily relevant to this report.

Standards

This inspection report has been prepared by qualified personnel to current engineering standards of interpretation and analysis.

Copyright and Limits of Use

This inspection report is the property of DP and is provided for the exclusive use of the client for the specific project and purpose as described in the report. It should not be used by a third party for any purpose other than to confirm that the construction works addressed in the report have been inspected as described. Use of the inspection report is limited in accordance with the Conditions of Engagement for the commission.

DP does not undertake to guarantee the works of the contractors or relieve them of their responsibility to produce a completed product conforming to the design.

Reports

This inspection report may include advice or opinion that is based on engineering and/or geological interpretation, information provided by the client or the client's agent, and information gained from:

- an investigation report for the project (if available to DP);
- inspection of the work, exposed ground conditions, excavation spoil and performance of excavating equipment while DP was on site;
- investigation and testing that was carried out during the site inspection;
- anecdotal information provided by authoritative site personnel; and

- DP's experience and knowledge of local geology.

Such information may be limited by the frequency of any inspection or testing that was able to be practically carried out, including possible site or cost constraints imposed by the client/contractor(s). For these reasons, the reliability of this inspection report is limited by the scope of information on which it relies.

Every care is taken with the inspection report as it relates to interpretation of subsurface conditions and any recommendations or suggestions for construction or design. However, DP cannot anticipate or assume responsibility for:

- unexpected variations in subsurface conditions that are not evident from the inspection; and
- the actions of contractors responding to commercial pressures.

Should these issues occur, then additional advice should be sought from DP and, if required, amendments made.

This inspection report must be read in conjunction with any attached information. This inspection report should be kept in its entirety without separation of individual pages or sections. DP cannot be held responsible for interpretations or conclusions from review by others of this inspection report or test data, which are not otherwise supported by an expressed statement, interpretation, outcome or conclusion stated in this inspection report.