

PENRITH CITY COUNCIL

NOTICE OF DETERMINATION

DESCRIPTION OF DEVELOPMENT

Application number:	DA17/1163.02
Description of development:	Modification to Consent for Detached Dual Occupancy. Modifications Include New First Floor Balcony, Front Window and Rear Doors on Dwelling A
Classification of development:	Class 1a

DETAILS OF THE LAND TO BE DEVELOPED

Legal description:	Lot 24 DP 1194171
Property address:	11 Macadamia Court, KINGSWOOD NSW 2747

DETAILS OF THE APPLICANT

Name & Address:	Mrz Designs Pty Ltd PO Box 170 ST CLAIR NSW 2759
-----------------	--

DECISION OF CONSENT AUTHORITY

In accordance with Sections 4.18(1) (a) and 4.55 of the Environmental Planning and Assessment Act 1979, consent is granted subject to the conditions listed in attachment 1.

Please note that this consent will lapse on the expiry date unless the development has commenced in that time.

Date from which consent operates	28 March 2018
Date the consent expires	28 March 2020
Date of this decision	27 March 2018 as amended on 8 August 2019 under Section 4.55 of the Environmental Planning and Assessment Act.

POINT OF CONTACT

If you have any questions regarding this determination you should contact:

Assessing Officer:	Mahbub Alam
Contact telephone number:	+612 4732 7693

NOTES

Reasons

The conditions in the attached schedule have been imposed in accordance with Section 4.17 of the Environmental Planning and Assessment Act 1979 as amended.

Conditions

Your attention is drawn to the attached conditions of consent in attachment 1.

Certification and advisory notes

You should also check if this type of development requires a construction certificate in addition to this development consent.

It is recommended that you read any Advisory Note enclosed with this notice of determination.

Review of determination

The applicant may request Council to review its determination pursuant to Division 8.2 of the Environmental Planning and Assessment Act 1979 within six months of receiving this Notice of Determination.

These provisions do not apply to designated development, complying development or crown development pursuant to Section 8.2(2) of the Environmental Planning and Assessment Act 1979.

Appeals in the Land and Environment Court

The applicant can appeal against this decision in the Land and Environment Court within six months of receiving this Notice of Determination.

There is no right of appeal to a decision of the Independent Planning Commission or matters relating to a complying development certificate pursuant to clause 8.6(3) of the Environmental Planning and Assessment Act 1979.

Designated development

If the application was for designated development and a written objection was made in respect to the application, the objector can appeal against this decision to the Land and Environment Court within 28 days after the date of this notice.

If the applicant appeals against this decision, objector(s) will be given a notice of the appeal and the objector(s) can apply to the Land and Environment Court within 28 days after the date of this appeal notice to attend the appeal and make submissions at that appeal.

Sydney Western City Planning Panels

If the application was decided by the Sydney Western City Planning Panel, please refer to Section 2.16 of the Environmental Planning and Assessment Act, 1979 (as amended) for any further regulations.

ATTACHMENT 1: CONDITIONS OF CONSENT

General

- 1 The development must be implemented substantially in accordance with the following plans stamped approved by Council, the application form, and any supporting information received with the application, except as may be amended in red on the attached plans and by the following conditions.

Drawing Title	Drawing Reference	Prepared by	Dated
Site plan	Job No: MRZ-17-190 (Page No: 2, Issue B)	MRZ Design & Building Consultant	10.01.18
Ground Floor Plan	Job No: MRZ-17-190 (Page No: 4, Issue B)	MRZ Design & Building Consultant	10.01.18
First Floor Plan	Job No: MRZ-17-190 (Page No: 5, Issue B)	MRZ Design & Building Consultant	10.01.18
Roof Plan	Job No: MRZ-17-190 (Page No: 6, Issue B)	MRZ Design & Building Consultant	10.01.18
Front/North Elevation and Right/West Elevation	Job No: MRZ-17-190 (Page No: 7, Issue B)	MRZ Design & Building Consultant	10.01.18
Rear/South Elevation and Left/East Elevation	Job No: MRZ-17-190 (Page No: 8, Issue B)	MRZ Design & Building Consultant	10.01.18
Right/West Elevation and Left/East Elevation	Job No: MRZ-17-190 (Page No: 9, Issue B)	MRZ Design & Building Consultant	10.01.18
Section	Job No: MRZ-17-190 (Page No: 10, Issue B)	MRZ Design & Building Consultant	10.01.18
Site Management Plan	Job No: MRZ-17-190 (Page No: 11, Issue B)	MRZ Design & Building Consultant	10.01.18
Site Analysis Plan	Job No: MRZ-17-190 (Page No: 12, Issue B)	MRZ Design & Building Consultant	10.01.18
Landscape Plan	Job No: MRZ-17-190 (Page No: 13, Issue B)	MRZ Design & Building Consultant	10.01.18
Shadow projections 21 st June 9Am, 12PM and 3PM	Job No: MRZ-17-190 (Page No: 14, 15 and 16, Issue B)	MRZ Design & Building Consultant	10.01.18
Schedule of Finishes	-	-	-
Waste Management Plan	-	MRZ Design & Building Consultant	13.11.17
BASIX Certificate	876656M	-	06 November 2017
Stormwater Drainage Plan and Details	17NL308 (Rev A)	Loka Consulting Engineering	Nov 17
As amended 08 August 2019 under Section 4.55 (1A) of the Environmental Planning Assessment Act 1979 (as amended) by the following plans:			
Site Plan	Job No: MRZ-17-190 (Page No: 2, Issue E)	MRZ Design & Building Consultant	31.05.19
Ground Floor Plan	Job No: MRZ-17-190 (Page No: 4, Issue E)	MRZ Design & Building Consultant	31.05.19
First Floor Plan	Job No: MRZ-17-190 (Page No: 5, Issue E)	MRZ Design & Building Consultant	31.05.19

Roof Plan	Job No: MRZ-17-190 (Page No: 6, Issue E)	MRZ Design & Building Consultant	31.05.19
Front/North Elevation and Right/West Elevation	Job No: MRZ-17-190 (Page No: 7, Issue E)	MRZ Design & Building Consultant	31.05.19
Rear/South Elevation and Left/East Elevation	Job No: MRZ-17-190 (Page No: 8, Issue E)	MRZ Design & Building Consultant	31.05.19
Right/West Elevation 2 and Left/East Elevation Section	Job No: MRZ-17-190 (Page No: 9, Issue E)	MRZ Design & Building Consultant	31.05.19
Site Management Plan	Job No: MRZ-17-190 (Page No: 10, Issue E)	MRZ Design & Building Consultant	31.05.19
Landscape Plan	Job No: MRZ-17-190 (Page No: 11, Issue E)	MRZ Design & Building Consultant	31.05.19
BASIX Certificate	876656M_02	-	31.05.19

1A. Prior to the issue of **any Occupation Certificate** appropriate privacy screening is to be installed along the rear / south elevation of the balcony area and is to extend 1.7m high from the finished floor level of the balcony as marked in red on to the stamped plans.

As amended 08 August 2019 under Section 4.55 (1A) of the Environmental Planning Assessment Act 1979 (as amended).

- 2 The work must be carried out in accordance with the requirements of the Building Code of Australia. If the work relates to a residential building and is valued in excess of \$20,000, then a contract of insurance for the residential development shall be in force in accordance with Part 6 of the Home Building Act 1989.

{Note: Residential building includes alterations and additions to a dwelling, and structures associated with a dwelling house/dwelling such as a carport, garage, shed, rural shed, swimming pool and the like}.

- 3 The development shall not be used or occupied until an Occupation Certificate has been issued.**

- 4 The finishes of all structures and buildings are to be maintained at all times and any graffiti or vandalism immediately removed/repaired.

- 5 A **Construction Certificate** shall be obtained prior to commencement of any building works.

Environmental Matters

6 No fill material shall be imported to the site until such time as a Validation Certificate (with a copy of any report forming the basis for the validation) for the fill material has been submitted to, considered and approved by Council. The Validation Certificate shall:

- state the legal property description of the fill material source site,
- be prepared by an appropriately qualified person (as defined in Penrith Contaminated Land Development Control Plan) with consideration of all relevant guidelines (e.g. EPA, ANZECC, NH&MRC), standards, planning instruments and legislation,
- clearly indicate the legal property description of the fill material source site,
- provide details of the volume of fill material to be used in the filling operations,
- provide a classification of the fill material to be imported to the site in accordance with the Environment Protection Authority's "Environmental Guidelines: Assessment, Classification & Management of Non-Liquid Wastes" 1997, and
- (based on the fill classification) determine whether the fill material is suitable for its intended purpose and land use and whether the fill material will or will not pose an unacceptable risk to human health or the environment.

{Note: Penrith Contaminated Land Development Control Plan defines an appropriately qualified person as "a person who, in the opinion of Council, has a demonstrated experience, or access to experience in hydrology, environmental chemistry, soil science, eco-toxicology, sampling and analytical procedures, risk evaluation and remediation technologies. In addition, the person will be required to have appropriate professional indemnity and public risk insurance."}

If the Principal Certifying Authority or Penrith City Council is not satisfied that suitable fill materials have been used on the site, further site investigations or remediation works may be requested. In these circumstances the works shall be carried out prior to any further approved works.

7 All waste materials stored on-site are to be contained within a designated area such as a waste bay or bin to ensure that no waste materials are allowed to enter the stormwater system or neighbouring properties. The designated waste storage areas shall provide at least two waste bays / bins so as to allow for the separation of wastes, and are to be fully enclosed when the site is unattended.

8 All excavated material and other wastes generated as a result of the development are to be re-used, recycled or disposed of in accordance with the approved waste management plan.

Waste materials not specified in the approved waste management plan are to be disposed of at a lawful waste management facility. Where the disposal location or waste materials have not been identified in the waste management plan, details shall be provided to the Certifying Authority as part of the waste management documentation accompanying the Construction Certificate application.

All receipts and supporting documentation must be retained in order to verify lawful disposal of materials and are to be made available to Penrith City Council on request.

BCA Issues

9 All aspects of the building design shall comply with the applicable performance requirements of the Building Code of Australia so as to achieve and maintain acceptable standards of structural sufficiency, safety (including fire safety), health and amenity for the on-going benefit of the community. Compliance with the performance requirements can only be achieved by:

(a) complying with the deemed to satisfy provisions, or

(b) formulating an alternative solution which:

- complies with the performance requirements, or
 - is shown to be at least equivalent to the deemed to satisfy provision, or
- (c) a combination of (a) and (b).

Health Matters and OSSM installations

10 The rainwater tank must be maintained so as not to create a nuisance and it must be protected against mosquito infestation.

Utility Services

11 A Section 73 Compliance Certificate under the Sydney Water Act 1994 shall be obtained from Sydney Water. The application must be made through an authorised Water Servicing Coordinator. Please refer to “Your Business” section of Sydney Water’s website at www.sydneywater.com.au then the “e-developer” icon, or telephone 13 20 92.

The Section 73 Compliance Certificate must be submitted to the Principal Certifying Authority prior to the issue of an Occupation Certificate.

12 Prior to the issue of a Construction Certificate, a written clearance is to be obtained from Endeavour Energy stating that electrical services have been made available to the development or that arrangements have been entered into for the provision of services to the development.

In the event that a pad mounted substation is necessary to service the development, Penrith City Council shall be consulted over the proposed location of the substation before the Construction Certificate for the development is issued as the location of the substation may impact on other services and building, driveway or landscape design already approved by Council.

13 **Prior to the issue of a Construction Certificate**, the Principal Certifying Authority shall be satisfied that telecommunications infrastructure may be installed to service the premises which complies with the following:

- The requirements of the Telecommunications Act 1997:
- For a fibre ready facility, the NBN Co’s standard specifications current at the time of installation; and
- For a line that is to connect a lot to telecommunications infrastructure external to the premises, the line shall be located underground.

Unless otherwise stipulated by telecommunications legislation at the time of construction, the development must be provided with all necessary pits and pipes, and conduits to accommodate the future connection of optic fibre technology telecommunications.

Prior to the issue of an Occupation Certificate, written certification from all relevant service providers that the telecommunications infrastructure is installed in accordance with the requirements above and the applicable legislation at the time of construction, must be submitted to the Principal Certifying Authority.

Construction

14 Stamped plans, specifications, a copy of the development consent, the Construction Certificate and any other Certificates to be relied upon shall be available on site at all times during construction.

The following details are to be displayed in a maximum of 2 signs to be erected on the site:

- the name of the Principal Certifying Authority, their address and telephone number,
- the name of the person in charge of the work site and telephone number at which that person may be contacted during work hours,
- that unauthorised entry to the work site is prohibited,
- the designated waste storage area must be covered when the site is unattended, and
- all sediment and erosion control measures shall be fully maintained until completion of the construction phase.

Signage but no more than 2 signs stating the above details are to be erected:

- at the commencement of, and for the full length of the, construction works onsite, and
- in a prominent position on the work site and in a manner that can be easily read by pedestrian traffic.

All construction signage is to be removed when the Occupation Certificate has been issued for the development.

15 Prior to the commencement of construction works:

(a) Toilet facilities at or in the vicinity of the work site shall be provided at the rate of one toilet for every 20 persons or part of 20 persons employed at the site. Each toilet provided must be:

- a standard flushing toilet connected to a public sewer, or
- if that is not practicable, an accredited sewage management facility approved by the council, or
- alternatively, any other sewage management facility approved by council.

(b) All excavations and backfilling associated with the erection or demolition of a building must be executed safely and in accordance with the appropriate professional standards. All excavations associated with the erection or demolition of a building must be properly guarded and protected to prevent them from being dangerous to life or property.

(c) If an excavation associated with the erection or demolition of a building extends below the level of the base of the footings of a building on an adjoining allotment of land, the person causing the excavation to be made:

- must preserve and protect the building from damage, and
- if necessary, must underpin and support the building in an approved manner, and
- must, at least 7 days before excavating below the level of the base of the footings of a building on an adjoining allotment of land, give notice of intention to do so to the owner of the adjoining allotment of land and furnish particulars of the excavation to the owner of the building being erected or demolished. The owner of the adjoining allotment of land is not liable for any part of the cost of work carried out for the purposes of this condition, whether carried out on the allotment of land being excavated or on the adjoining allotment of land, (includes a public road and any other public place).

(d) If the work involved in the erection or demolition of a building is likely to cause pedestrian or vehicular traffic in a public place to be obstructed or rendered inconvenient, or involves the enclosure of a public place, a hoarding or fence must be erected between the work site and the public place:

- if necessary, an awning is to be erected, sufficient to prevent any substance from, or in connection with, the work falling into the public place,
- the work site must be kept lit between sunset and sunrise if it is likely to be hazardous to persons in the public place, and
- any such hoarding, fence or awning is to be removed when the work has been completed.

16 The building shall be set out by a registered surveyor. A Survey Certificate shall be undertaken and submitted to the Principal Certifying Authority when the building is constructed to ground floor slab level.

17 The rainwater tank(s) is to be:

- erected on a self-supporting base in the approved location on the property in accordance with the stamped-approved site plans for the development,
- structurally sound and constructed in accordance with AS/NZS 3500 1.2- 1998: National Plumbing and Drainage - Water Supply - Acceptable Solutions,
- fully enclosed and all openings sealed to prevent access by mosquitoes,
- fitted with a first flush device,
- fitted with a trickle system to top up from mains water,
- provided with an air gap, and
- installed by a licensed plumber in accordance with Sydney Water's "Plumbing requirements Information for rainwater tank suppliers and plumbers April 2003" and the NSW Code of Practice: Plumbing and Drainage.

Additionally, the following are to be provided:

- A back flow prevention device shall be provided at the water meter in accordance with Sydney Water

requirements.

- In the event of a power failure, a back up supply of mains water shall be provided to at least one toilet in the dwelling.
- The rainwater tank(s) and associated piping is to be labelled 'Rainwater - Not for Drinking' in accordance with Sydney Water requirements.
- The rainwater tank and pipework is to be painted in colours matching the external finishes of the dwelling and is to be of non-reflective finish.
- The overflow for the rainwater tank is to be connected into the existing stormwater disposal system on the site.

Before a rainwater tank(s) can be used, a certificate or suitable document is to be submitted to the Principal Certifying Authority stating that the rainwater tank has been installed in accordance with:

- the Manufacturer's Specifications, and
- Sydney Water and NSW Health requirements.

This certificate or documentation is to be provided by the licensed plumber who installed the rainwater tank on the property, and is to be submitted prior to the issue of the Occupation Certificate.

- 18 The catchment area (for the rainwater tank) includes the parts of the roof of the dwelling(s) from which water is collected and includes gutters. To ensure a safe supply of water:
- roof catchment areas must be kept clear of overhanging vegetation,
 - gutters must have sufficient fall to downpipes to prevent pooling of water,
 - overflow, discharge from bleed off pipes from roof mounted appliances such as airconditioners, hot water services and solar heaters must not discharge into the rainwater catchment area,
 - for roofs containing lead based, tar based or asbestos material the tank supply must not be connected to drinking, bathing and gardening tap water outlets,
 - appropriate measures must be installed to prevent foreign materials from contaminating the water which enters the rainwater tank.
- 19 The rainwater tank supply must not be connected to drinking and bathing water tap outlets.
- 20 The rainwater tank pump must not exceed 5dBA above ambient background noise level at the nearest residential property boundary. The provisions of the Protection of the Environment Operations Act 1997 apply to the development, in terms of regulating offensive noise.
- 21 Construction works or subdivision works that are carried out in accordance with an approved consent that involve the use of heavy vehicles, heavy machinery and other equipment likely to cause offence to adjoining properties shall be restricted to the following hours in accordance with the NSW Environment Protection Authority Noise Control Guidelines:
- Mondays to Fridays, 7am to 6pm
 - Saturdays, 7am to 1pm (if inaudible on neighbouring residential premises), otherwise 8am to 1pm
 - No work is permitted on Sundays and Public Holidays.

Other construction works carried out inside a building/tenancy and do not involve the use of equipment that emits noise are not restricted to the construction hours stated above.

The provisions of the Protection of the Environment Operations Act, 1997 in regulating offensive noise also apply to all construction works.

Engineering

- 22 All roadworks, stormwater drainage works, associated civil works and dedications, required to effect the consented development shall be undertaken at no cost to Penrith City Council.
- 23 An Infrastructure Restoration Bond is to be lodged with Penrith City Council for development involving works around Penrith City Council's Public Infrastructure Assets. The bond is to be lodged with Penrith City Council prior to commencement of any works on site or prior to the issue of any Construction Certificate, whichever occurs first. The bond and applicable fees are in accordance with Council's adopted Fees and Charges.

An application form together with an information sheet and conditions are available on Council's website.

Contact Penrith City Council's City Works Department on (02) 4732 7777 or visit Penrith City Council's website for more information.

- 24 Prior to the issue of any Construction Certificate, a Section 138 Roads Act applications, including payment of application and inspection fees, shall be lodged and approved by Penrith City Council (being the Roads Authority for any works required in a public road). These works may include but are not limited to the following:
- a) Vehicular crossings (including kerb reinstatement of redundant vehicular crossings)
 - b) Road opening for utilities and stormwater (including stormwater connection to Penrith City Council roads and other Penrith City Council owned drainage)
 - c) Road occupancy or road closures
 - d) The placement of hoardings, structures, containers, waster skips, signs etc. in the road reserve
 - e) Temporary construction access

All works shall be carried out in accordance with the Roads Act approval, the development consent, including the stamped approved plans, and Penrith City Council's specifications, guidelines and best engineering practice.

Contact Penrith City Council's City Works Department on (02) 4732 7777 or visit Penrith City Council's website for more information.

Note:

- a) Where Penrith City Council is the Certifying Authority for the development, the Roads Act approval for the above works may be issued concurrently with the Construction Certificate.
- b) All works associated with the Roads Act approval must be completed prior to the issue of any Occupation Certificate or Subdivision Certificate as applicable.

- 25 Stormwater drainage from the site shall be discharged to the street drainage system.

The proposed development and stormwater drainage system shall be designed to ensure no adverse impact on adjoining properties by the diversion, damming or concentration of stormwater flows.

The proposed method of stormwater discharge shall be detailed in the Construction Certificate issued by the Certifying Authority.

- 26 Prior to the issue of any Construction Certificate, the Certifying Authority shall ensure that vehicular access, circulation, manoeuvring, pedestrian and parking areas associated with the subject development are in accordance with AS 2890.1 and Penrith City Council's Development Control Plan.
- 27 Prior to commencement of any works associated with the development, sediment and erosion control measures shall be installed in accordance with the approved Construction Certificate and to ensure compliance with the Protection of the Environment Operations Act 1997 and Managing Urban Stormwater series from the Office of Environment and Heritage.
- The erosion and sediment control measures shall remain in place and be maintained until all disturbed areas have been rehabilitated and stabilised.
- 28 Upon completion of all works in the road reserve, all verge areas fronting and within the development are to be turfed. The turf shall extend from the back of kerb to the property boundary, with the exception of concrete footpaths, service lids or other infrastructure which is not to be turfed over. Turf laid up to concrete footpaths, service lids or other infrastructure shall finish flush with the edge.
- 29 All existing (aerial) and proposed services for the development, including those across the frontage of the development are to be located or relocated underground in accordance with the relevant authorities regulations and standards.
- 30 Prior to the issue of any Occupation Certificate, the Principal Certifying Authority shall ensure that all works associated with a S138 Roads Act approval or S68 Local Government Act approval have been inspected and signed off by Penrith City Council.

Landscaping

- 31 All landscape works are to be constructed in accordance with the stamped approved plan and Penrith Council's Development Control Plan.

Landscaping shall be maintained:

- in accordance with the approved plan, and
- in a healthy state, and in perpetuity by the existing or future owners and occupiers of the property.

If any of the vegetation comprising that landscaping dies or is removed, it is to be replaced with vegetation of the same species and, to the greatest extent practicable, the same maturity as the vegetation which died or was removed.

- 32 The approved landscaping for the site must be constructed by a suitably qualified and experienced landscape professional.
- 33 All plant material associated with the construction of approved landscaping is to be planted in accordance with the Tree Planting Specification prescribed in Penrith Council's Development Control Plan.
- 34 All landscape works are to meet industry best practice and the following relevant Australian Standards:
- AS 4419 Soils for Landscaping and Garden Use,
 - AS 4454 Composts, Soil Conditioners and Mulches, and
 - AS 4373 Pruning of Amenity Trees.
- 35 No trees are to be removed, ringbarked, cut, topped or lopped or wilfully destroyed (other than those within

the proposed building footprint or as shown on the approved plans) without the prior consent of Penrith City Council and in accordance with Council's Tree Preservation Order and Policy.

Section 94

- 36 This condition is imposed in accordance with Penrith City Council's Section 94 Contributions Plan(s) for **Cultural Facilities**. Based on the current rates detailed in the accompanying schedule attached to this Notice, **\$480.00** is to be paid to Council **prior to a Construction Certificate being issued for this development** (the rates are subject to quarterly reviews). If not paid within the current quarterly period, this contribution will be reviewed at the time of payment in accordance with the adopted Section 94 plan. The projected rates of this contribution amount are listed in Council's Fees and Charges Schedule.

Council should be contacted prior to payment to ascertain the rate for the current quarterly period. The S94 invoice accompanying this consent should accompany the contribution payment.

The Section 94 Contributions Plan for Cultural Facilities may be inspected at Council's Civic Centre, 601 High Street, Penrith.

- 37 This condition is imposed in accordance with Penrith City Council's Section 94 Contributions Plan(s) for **District Open Space**. Based on the current rates detailed in the accompanying schedule attached to this Notice, **\$5,908.00** is to be paid to Council **prior to a Construction Certificate being issued for this development** (the rates are subject to quarterly reviews). If not paid within the current quarterly period, this contribution will be reviewed at the time of payment in accordance with the adopted Section 94 plan. The projected rates of this contribution amount are listed in Council's Fees and Charges Schedule.

Council should be contacted prior to payment to ascertain the rate for the current quarterly period. The S94 invoice accompanying this consent should accompany the contribution payment.

The Section 94 Contributions Plan for District Open space may be inspected at Council's Civic Centre, 601 High Street, Penrith.

- 38 This condition is imposed in accordance with Penrith City Council's Section 94 Contributions Plan(s) for **Local Open Space**. Based on the current rates detailed in the accompanying schedule attached to this Notice, **\$2,136.00** is to be paid to Council **prior to a Construction Certificate being issued for this development** (the rates are subject to quarterly reviews). If not paid within the current quarterly period, this contribution will be reviewed at the time of payment in accordance with the adopted Section 94 plan. The projected rates of this contribution amount are listed in Council's Fees and Charges Schedule.

Council should be contacted prior to payment to ascertain the rate for the current quarterly period. The S94 invoice accompanying this consent should accompany the contribution payment.

The Section 94 Contributions Plan for Local Open Space may be inspected at Council's Civic Centre, 601 High Street, Penrith

Payment of Fees

39 All roadworks, dedications and drainage works are to be carried out at the applicant's cost.

Certification

- 40 Prior to the commencement of any earthworks or construction works on site, the proponent is to:
- (a) employ a Principal Certifying Authority to oversee that the said works carried out on the site are in accordance with the development consent and related Construction Certificate issued for the approved development, and with the relevant provisions of the Environmental Planning and Assessment Act and accompanying Regulation, and
 - (b) submit a Notice of Commencement to Penrith City Council.

The Principal Certifying Authority shall submit to Council an "Appointment of Principal Certifying Authority" in accordance with Section 81A of the Environmental Planning and Assessment Act 1979.

Information to accompany the Notice of Commencement

Two (2) days before any earthworks or construction/demolition works are to commence on site (including the clearing site vegetation), the proponent shall submit a "Notice of Commencement" to Council in accordance with Section 81A of the Environmental Planning and Assessment Act 1979.

- 41 An Occupation Certificate is to be obtained from the Principal Certifying Authority on completion of all works and prior to the occupation.

The Certificate shall not be issued if any conditions of this consent, but not the conditions relating to the operation of the development, are outstanding.

A copy of the Occupation Certificate and all necessary documentation supporting the issue of the Certificate is to be submitted to Penrith City Council, if Council is not the Principal Certifying Authority.

SIGNATURE

Name:	Mahbub Alam
Signature:	

For the Development Services Manager