

CUT & FILL BUILDING AREA TO RL 19.615 APPROX. TO CREATE LEVEL BUILDING PLATFORM FOR **WAFFLE POD SLAB**

CUT - / INE

NOTE: THIS SITING IS SUBJECT TO THE DEVELOPERS APPROVAL. BUILDER TO OBTAIN PRIOR TO PERMIT APPLICATION.

NOTE: THIS SITING HAS BEEN PREPARED BASED ON THE ADJOINING PROPERTIES/Y BEING VACANT. SHOULD A SIGNIFICANT AMOUNT OF TIME PASS BEFORE THE BUILDING PERMIT IS APPLIED FOR, AN UPDATED SURVEY MAY BE REQUIRED TO CONFIRM THE ADJOINING PROPERTIES/Y STATUS. THE RESCODE REQUIREMENTS MAY NEED TO BE RE-EVALUATED AND MAY CAUSE CHANGES TO THE SITING/HOUSE.

NOTE: THIS SITING HAS BEEN PREPARED BASED ON THE AVAILABLE INFORMATION FROM THE RELEVANT LOCAL COUNCIL AND/OR OTHER AUTHORITIES THAT IS NOT COMPLETE OR HAVE NOT BEEN FINALISED DUE TO THE TITLES NOT YET BEEN RELEASED IN THIS SUBDIVISION. ONCE THIS INFORMATION IS RELEASED IT WILL BE EXAMINED. THIS MAY REVEAL THE REQUIREMENT FOR ADDITIONAL WORKS AND THE SITING MAY CHANGE.

NOTE: ALL EXISTING STREET TREES AND VERGE PLANTING TO BE PROTECTED DURING CONSTRUCTION

SITE COVERAGE ANALYSIS

Roof Area	256.0	sqm	68.1	%
Ground Floor	174.9	sqm		
Garage	36.2	sqm		
Porch	5.4	sqm		
Alfresco	12.9	sqm		
Building	229.4	sqm	61.0	%
Hard Surface	32.1	sqm	8.5	%
Permeable	114.3	sqm	30.5	%
Total Area	375.8	sqm	100.0	%

PRELIMINARY DRAWINGS

GARAGE FLOOR

3.10.12 REV A PRELIM PLANS JS DATE REVISION DRAWN

KERB INVERT

18%

C Henley Arch P/L All rights reserved - this set of drawings is COPYRIGHT. Apart from use by the party to whom these drawings are addressed for the purpose for which it was requested and any fair dealing as permitted under the Copyright Act, no part may be used, reproduced or copied by an means or in any form without prior

permission of HENLEY ARCH P/L

SITE PLAN DRAWN XXXXXXX JS JOB No. 200028 CHECKED (CHKBY) 1:2001:200 Date: 09/10/2012 LH **DIAL BEFORE YOU DIG** www.1100.com.au

Greffin Luca 4 For EDGEWATER HOMES LOT 2132 ILLOURA WAY JORDAN SPRINGS

EDGEWATER HOMES

PO Box 550 Moorebank NSW 1875 Ph: 9623 7526 Fax:9673 5560

TABLE OF BASIX COMMITMENTS

PROJECT ADDRESS: LOT 2132 ILLOURA WAY JORDAN SPRINGS

CERTIFICATE NO .: S

WATER


- DEVELOPMENT TO BE CONNECTED TO 2,000LT RAINWATER TANK.
 RAINWATER TANK CONFIGURED TO COLLECT AT LEAST 200m2
 ROOF RUN OFF.
- TOILETS, WASHING MACHINE AND I OUTDOOR TAP TO BE CONNECTED TO THE RAINWATER TANK.
- ALL SHOWER HEADS, TOILETS, KITCHEN TAPS AND BASIN TAPS TO BE 3 STAR RATED.

THERMAL

- ROOF INSULATION: NONE.
- CEILING INSULATION: R2.5
- WALL INSULATION: R1.5
- EXTERNAL WALL: BRICK VENEER COLOUR: DARK
- ROOFING: TILED COLOUR: DARK
- GLAZING: ALL ALUMINIUM WINDOWS TO BE SINGLE CLEAR GLAZED WITH U VALUE OF 6.57 & SHGC OF 0.74
- TIMBER WINDOWS TO MASTER SUITE AND REAR FAMILY / DINING STACKER DOORS TO BE SINGLE, CLEAR GLAZED, TIMBER FRAMED WITH A U VALUE OF 5.55 AND SHGC OF 0.73

ENERGY

- HOT WATER SYSTEM: GAS INSTANTANEOUS HWS WITH A
 PERFORMANCE OF 5 STARS OR BETTER.
- DEVELOPMENT WILL NOT INCORPORATE ANY COOLING/HEATING SYSTEM.
- KITCHEN: INDIVIDUAL FAN, DUCTED (RANGEHOOD). OPERATION CONTROL, MANUAL SWITCH.
- BATHROOM (1): INDIVIDUAL FAN, NOT DUCTED. OPERATION CONTROL, MANUAL SWITCH.
- LAUNDRY: NATURAL VENTILATION.
- WINDOW AND/OR SKYLIGHT TO KITCHEN FOR NATURAL LIGHTING. WINDOW AND/OR SKYLIGHT TO BATHROOMS (2)/TOILET (S) FOR
- NATURAL LIGHTING.
 GAS COOKTOP AND ELECTRIC OVEN TO BE INSTALLED IN THE KITCHEN.





Association of Building Sustainability Assessors Certification Number 1005097124 Certification Date 10/03/2013 Assessor Name Brad Hoad Assessor Number 20731 Assessor Signature Simulated Energy: HEATING: 643 MJ/m² pa Simulated Energy: COOLING: 50.8 MJ/m² pa Nathers Rating 114.9 MJ/m² pa

PRELIMINARY DRAWINGS

9.10.12 REV A PRELIM PLANS JS
DATE REVISION DRAWN


C Henley Arch P/L


All rights reserved - this set of drawings is COPYRIGHT. Apart from use by the party to whom these drawings are addressed for the purpose for which it was requested and any fair dealing as permitted under the Copyright Act, no part may be used, reproduced or copied by an means or in any form without prior permission of HENLEY ARCH P/L

ELEVATIONS		LH IHS	3	Luca 4		Griffin
DRAWN JS				For	EDGEWATER HOMES	
CHECKED (CHKBY) JOB No. 200028				A 1	The second of the second secon	
SCALE 1:100 Date: 09/10/2012	*			At	LOT 2132 ILLOURA WAY JORDAN SPRINGS	


EDGEWATER HOMES


PO Box 550 Moorebank NSW 1875 Ph: 9623 7526 Fax:9673 5560





TYPICAL_SECTION





PRELIMINARY DRAWINGS

Please note the following:

Coloured concrete driveway & path including steps to P.C.C specs, vehicle crossover in plain concrete to P.C.C spec. If required by edgewater.

Plain concrete crossover to P.C.C specification max 5000mm wide.

All existing street trees and verge planting are to be protected during construction.

Letterbox to complement the design of the house and in accordance with the fencing design guidelines.

PLANT SCHEDULE

Code	Botanical name	Common Name	Height (mm)	Width (mm)	Quantity	Pot Size @ Planting
CO*	Correa alba	White Correa	1000	1200	5	140mm
EU*	Eucalyptus pauciflora 'Little Snowman'	Little Snowman	6500	4000	2	300mm
LL*	Lomandra longifolia 'Tanika'	Tanika Lomandra	700	700	10	140mm

^{*} Native plant selection

		-
9.10.12	REV A PRELIM PLANS	JS
DATE	REVISION	DRAWN

C Henley Arch P/L

All rights reserved - this set of drawings is COPYRIGHT. Apart from use by the party to whom these drawings are addressed for the purpose for which it was requested and any fair dealing as permitted under the Copyright Act, no part may be used, reproduced or copied by an means or in any form without prior permission of HENLEY ARCH P/L

LANDSCAPING		HAND	LH	SHT	1B	Luca 4		Griffin		
DRAWN	JS						For	EDGEWATER HOMES		l
CHECKED	(CHKBY)	JOB No. 200028					4.	EBGETWIT EITTIGHTEG		
SCALE	1:100	Date: 09/10/2012					At	LOT 2132 ILLOURA WAY JORDAN SPRINGS		

EDGEWATER HOMES

PO Box 550 Moorebank NSW 1875 Ph: 9623 7526 Fax:9673 5560