

STANDARD SPECIFICATION

BE ADVISED : SOME CLAUSES IN THIS SPECIFICATION MAY NOT BE RELEVANT TO THIS PROJECT

1.0 GENERAL

- 1.1 ALL DIMENSIONS SHALL BE CHECKED ON SITE PRIOR TO COMMENCEMENT OF ANY WORK
- 1.2 ALL MATERIALS SHALL COMPLY WITH RELEVANT CURRENT AUSTRALIAN STANDARDS AND UNLESS OTHERWISE STATED ON THE PLANS SHALL BE NEW AND THE BEST OF THE THEIR RESPECTIVE KIND AND SUITABLE FOR THEIR INTENDED PURPOSES.
- 1.3 ALL WORKMANSHIP SHALL COMPLY WITH RELEVANT CURRENT AUSTRALIAN STANDARDS AND TO GOOD TRADE PRACTICES
- 1.4 ALL WORK SHALL BE IN ACCORDANCE WITH REQUIREMENTS OF THE RESPECTIVE AUTHORITY HAVING JURISDICTION OVER THE WORKS.
- 1.5 THE ARCHITECTURAL DRAWINGS SHOULD BE READ IN CONJUNCTION WITH THE SPECIFICATION, SCHEDULES AND CONSULTANTS DRAWINGS THAT FORM PART OF THE CONSTRUCTION DOCUMENTS REFERRED TO IN THE "BUILDING CONTRACT".
- 1.6 DO NOT SCALE FROM DRAWINGS. NOTIFY OF ANY ERRORS OR OMISSIONS BEFORE PROCEEDING WITH ANY WORKS
- 1.7 ENSURE THAT SUBSTRATES ARE SUITABLE FOR THE INTENDED SUBSEQUENT FINISHES. COMMENCEMENT OF WORK ON THE SUBSTRATES IMPLIES ACCEPTANCE BY THE SUBCONTRACTOR OF THE SUBSTRATES ON WHICH FINISHES ARE APPLIED.
- 1.8 CONTRACTOR IS TO SUPPLY ALL EQUIPMENT NECESSARY FOR THE COMPLETION OF THE RESPECTIVE WORKS.
- 1.9 CONTRACTOR IS RESPONSIBLE FOR THE PROGRESSIVE CLEAN UP DURING AND AFTER THE COMPLETION OF RESPECTIVE WORKS

2.0 EARTHWORKS

- 2.1 UNLESS OTHERWISE STATED, REMOVE TOPSOIL TO A MINIMUM DEPTH OF 200mm INCLUDING ALL ROOTS, AND OTHER MATTER, AND REQUIRED BY THE SOIL CONDITION AND/OR BUILDER. PROVIDE SUITABLE CLEAN FILL AND COMPACT IN LAYERS NOT GREATER THAN 300mm TO REDUCE LEVELS AS SHOWN.
- 2.2 DO NOT EXCAVATE SERVICES TRENCHES WITHIN AN ANGLE OF 45 DEGREES DOWN FROM THE BOTTOM EDGE OF THE FOOTING.
- 2.3 ALL RETAINING WALLS TO BE TREATED WITH "BITKOTE" WATERPROOFING AGENT

3.0 CONCRETE

- 3.1 ALL CONCRETE REINFORCEMENT AND FORMWORK SHALL BE TO STRUCTURAL ENGINEERS DETAILS, RELEVANT BUILDING CODES AND STANDARDS
- 3.2 THE FOOTING AND SLAB CONSTRUCTION IS TO COMPLY WITH AS 2870
- 3.3 PROVIDE A PROPRIETARY VAPOUR BARRIER WHICH CONSISTS OF HIGH IMPACT RESISTANT POLYTHENE FILM MIN 0.2mm THICK WHICH HAS BEEN PIGMENTED AND BRANDED BY THE MANUFACTURER.

4.0 TERMITE PROTECTION:

- 4.1 PROVIDE ANTI-TERMITE TREATMENT UNDER THE BUILDING AREAS IN ACCORDANCE WITH AS 2057, AS 3660.1 AND APPENDIX D, FOR RETICULATED SYSTEMS.
- 4.2 BUILDER SHALL PROVIDE "BIFLEX" OR SIMILAR APPROVED ANTI-TERMITE TREATMENT IN ACCORDANCE WITH RELEVANT AUSTRALIAN STANDARD CODES

5.0 BRICKWORK

- 5.1 BRICK WORK SHALL COMPLY WITH :
 - AS 3700 MASONRY CODE
 - AS A123 MASONRY CODE
 - MORTAR FOR MASONRY CONSTRUCTION
- 5.2 BRICK GAUGE 7 STANDARD COURSES = 600mm.
- 5.3 TIES SHALL BE 3.5mm DIAMETER GALVANIZED WIRE KINKED FOR AND BUILT IN EVERY 5TH COURSE AT APPROXIMATELY 900mm CENTRES, WITH ADDITIONAL TIES AT THE RATE OF 1 TIE/300mm HEIGHT OF OPENINGS AND VERTICAL CONTROL JOINTS AND WITHIN 150mm OF OPENINGS. BUILD TIES INTO EACH LEAF AT LEAST 50mm.
- 5.4 VERTICAL CONTROL JOINTS SHALL BE 12mm WIDE FILLED AT COMPLETION WITH A CONTINUOUS FILLER STRIP.
- 5.5 CAVITIES TO BE KEPT CLEAR OF MORTAR. PROVIDE CAVITY BOARDS. TEMPORARILY OMIT BRICKS TO PERMIT RAKING OUT OF CAVITY BOTTOMS.
- 5.6 FORM WEEP HOLES EVERY FOURTH PERPEND ABOVE FLASHING AND CAVITY FILL KEEP CLEAR OF MORTAR. DO NOT LOCATE WEEPHOLES CLOSER THAN 500mm TO JOINTS IN DAMP PROOF COURSES OR FLASHING.
- 5.7 PROVIDE DAMP PROOF COURSES (DPC) IN THE BOTTOM 3 COURSES OF BRICK WORK AND SLAB AND/OR FOOTINGS. DPC ADDITIVE SHALL BE CLEAR IN ALL FACEWORK.
- 5.8 SETOUT BRICKWORK ACCURATELY, PLUMP, LEVEL AND PROPERLY BONDED. RISING WORK TO BE RAKED BACK, JAMBS, REVEALS, CORNERS, PERPENDS, ETC TO BE TRUE, PLUMB AND IN LINE WITH PERPENDS TRUE LINE. SETOUT DOOR FRAMES NEAR PERPENDICULAR WALL WITH A MARGIN OF 12mm OR GREATER THAN 50mm
- 5.9 PROVIDE 12mm PLASTERING MARGIN BETWEEN WINDOW FRAME AND INTERNAL BRICKWORK TO BE PLASTERED.
- 5.10 WHERE NECESSARY REINFORCE BELOW AND OVER OPENINGS WITH GALVANISED WOVEN WIRE FABRIC 75mm WIDE IN CENTRE OF EACH LEAF EXTENDING ALUMINIUM OF 600mm BEYOND THE OPENING.

5.11 BUILD IN ALCOR/PGI FLASHINGS AS FOLLOWS:

- WHEREVER SHOWN ON DRAWINGS
 - CAVITY WALLS BUILT OF SLAB ON GROUND (WHERE NOT PARGED)
 - OVER LINTELS TO EXPOSED OPENINGS - EXTEND THE FULL WIDTH OF OUTER LEAF CONTINUOUS ACROSS CAVITY 50mm INTO INNER LEAF 2c ABOVE
 - OVER ROOF - EXTEND THE FULL WIDTH OF EXTERNAL LEAF, STEPPED TO ROOF SLOPE TURNED DOWN MIN. 50mm OVER BASE FLASHING. TURN UP IN CAVITY SLOPING INWARDS AND BUILT INTO INNER LEAF 1c ABOVE.
 - DOOR/WINDOW STILES - EXTEND THE FULL HEIGHT 150mm WIDE FIXED TO FRAMES INTERLEAVED WITH SILL AND HEAD FLASHING AT EACH END.
 - STRUCTURE OR SERVICES WITHIN 30mm OF OUTER BRICK LEAF IN CAVITY: VERTICAL FLASHING CONTINUOUS 1c BELOW FL TO ABOVE STRUCTURE OR FRAME. NOMINAL 300m WIDE.
 - FOR HORIZONTAL STRUCTURES/SERVICES: CONTINUOUS FLASHING BUILT IN AS FOR OVER LINTELS
 - AT CAVITY WALLS WITH GLASS BLOCK 300mm WIDE FIXED TO GLASS BLOCK FRAME AND TURNED AWAY IN CAVITY FROM INNER LEAF.
- 5.12 WHERE NECESSARY REINFORCE BELOW AND OVER OPENINGS WITH GALVANISED WOVEN WIRE FABRIC 75mm WIDE IN CENTRE OF EACH LEAF OPENING EXTENDING ALUMINIUM OF 600mm BEYOND THE OPENING.
 - 5.13 UNLESS OTHERWISE SHOWN ON DRAWINGS EXTERNAL FACE WORK: 230x110x76mm WINDOW SILLS: 2c FACE BRICK SPLAYED SILLS WINDOW HEADS: SOLID FACEBRICK COURSE

6.0 LINTELS

MAX SPAN (mm)	LINTELS SIZE (VERT x HORIZ x THICK)	BEARING EACH END (mm)
900	75x10	150
1200	75x75x8	150
1500	90x90x8	150
1800	100x75x8	230
2100	125x75x8	230
2400	125x75x10	230
2500	100x100x8	230
3000	150x90x10	230

7.0 CARPENTRY WORK

- 7.1 ROOF AND CEILING FRAMING SHOULD COMPLY WITH AS 1684 LIGHT TIMBER FRAMING CODE. DRAW STRAP FIRMLY OVER WALL PLATES AND SECURELY FIX TO TOP OF PLATE BY 2x30mm GALV. CLOUTS/STRAP.
- 7.2 REFER TO AS 1684 FOR ROOF FRAMING SIZES UNLESS SPECIFIED ON DRAWINGS.
- 7.3 SUPPLY AND FIX ALL BULKHEADS & FALSE CEILINGS AS SHOWN ON THE DRAWINGS.

8.0 ROOFING

- 8.1 SELECTED ROOFING MATERIAL SHALL BE INSTALLED AND FIXED IN ACCORDANCE WITH MANUFACTURERS SPECIFICATION AND RELEVANT BUILDING CODES
- 8.2 GUTTER, FASCIA, DOWNPIPES, FLASHING SHALL BE IN LONGEST POSSIBLE LENGTHS
- 8.3 ALLOW FOR ALL JOINTS AND JOINING MATERIALS, COLLARS, STRAPS & FASTENINGS NECESSARY TO COMPLETE WORK.
- 8.4 ALLOW FOR ALL ROOF PENETRATIONS, ROOF COWLS, FLASHING, FLUMES THROUGH ROOF
- 8.5 FIX GUTTERS & FLASHING TO PERMIT THERMAL MOVEMENT IN THEIR FULL LENGTH
- 8.6 SEAL BETWEEN OVERLAPPING FLASHING; FLASHING TURNED DOWN OVER BASE OR APRON FLASHING; FLASHING OVER METAL ROOF; FLASHING OVER SECRET GUTTERS; AROUND ROOF PENETRATIONS ETC.

9.0 WINDOWS/GLAZING

- 9.1 UNLESS OTHERWISE STATED ON THE DRAWINGS WINDOW FRAMES SHALL BE ALUMINIUM RESIDENTIAL OR COMMERCIAL IN SECTION WITH POWDERCOAT FINISH AS SELECTED BY OWNER.
- 9.2 ALLOW FOR FLYSCREENS TO BE FITTED TO ALL WINDOWS.
- 9.3 ANGLED WINDOW UNITS SHALL BE FACTORY MADE AND FIXED AND DELIVERED ON SITE AS A COMPLETE UNIT.
- 9.4 WHERE RELEVANT WINDOWS ARE TO COMPLY WITH THE SPECIFICATIONS PROVIDED BY THE THERMAL PERFORMANCE ASSESSOR.
- 9.5 CLEAR GLASS GENERALLY: OBSCURE GLASS TO BATHROOMS, REFER TO DRAWINGS.
- 9.6 WHERE GLASS BLOCKS HAVE BEEN NOMINATED, THEY SHALL BE IN FRAMES AND INSTALLED TO MANUFACTURERS SPECIFICATIONS

10.0 JOINERY

- 10.1 ALL JOINERY SHALL BE OF HIGHEST QUALITY MATERIALS TO BEST TRADE PRACTICES AND HIGH QUALITY FINISH.
- 10.2 EXTERNAL DOOR FRAMES SHALL BE: 110x40 DOUBLE REBATED FRAME WITH 130x40 WEATHERED THRESHOLD U.N.O.
- 10.3 SUPPLY AND BUILD IN TIMBER DOOR FRAMES TO EXTERNAL LOCATIONS AS SHOWN ON ARCHITECTURAL DRAWINGS.

11.11.0 CEILINGS

- 11.2 CEILINGS SHALL BE RECESSED EDGE, MINIMUM 8.0mm PLASTERGLASS OR GYPROCK.
- 11.3 FLUSH JOINTS, SCREW HEADS, AND OTHER BLEMISHES IN THE SHEETS USING APPROVED SYSTEMS TO PROVIDE FLUSH SMOOTH CONTINUOUS SURFACE
- 11.4 PROVIDE AND FIX ALL FLUSH STOP BEADS & CASING BEADS TO ALL CORNERS & EDGES PROVIDE ALL SELECTED MOLDINGS AND CORNICES TO ALL CEILINGS AS SHOWN ON THE DRAWINGS.

12.0 PLASTERING

- 12.1 INTERNAL WALL FINISHES INCLUDING CUPBOARD, BIN & FRIDGE RECESSES ETC SHALL BE (OTHER THAN FACE FINISHES OR WHERE COVERED BY FEATURE MATERIALS) FLOAT AND SET IN HARDWALL PLASTER U.N.O.
- 12.2 PLASTERED WALLS SHALL BE NOMINAL 12mm THICK CONSISTING OF 1:1:9, CEMENT:LIME:SAND RENDER, AND FINISHED WITH NOMINALLY 3mm
- 12.3 HARDWALL PLASTER
- 12.4 SUPPLY AND FIX EXTERNAL CORNER BEADS TO ALL EXTERNAL CORNERS. PROVIDE STOP BEADS WHERE PLASTER WORK ABUTS TIMBER FRAMES, OR FACEWORK
- 12.5 EXTERNAL RENDER WHEN APPLICABLE SHALL BE 2 COAT SAND FINISH. (FOR PAINTING).
- 12.6 NIBS IN INTERNAL CORNERS ADJACENT TO DOOR FRAMES GREATER THAN 40mm SHALL NOT BE FLUSHED UP WITH FRAMES.
- 12.7 PROVIDE V-JOINTS IN RENDER & FINISHING PLASTER WHERE BRICK WORK ABUTS OR JOINS ONTO CONCRETE WORK.

13.0 FLOORING FINISHES

- 13.1 CARPET FLOOR COVERINGS TO NOMINATED AREAS COMPLETE WITH SELECTED UNDERLAY SMOOTH EDGE, DIMINISHING STRIPS ETC, TO COMPLETE THE WORKS: REFER TO DRAWINGS AND FINISHES SCHEDULE
- 13.2 PROVIDE TILED FLOOR FINISHES TO NOMINATED AREAS COMPLETE WITH ALL MATERIALS, ANGLE TRIMS ETC. TO COMPLETE THE WORKS: REFER TO DRAWINGS AND FINISHES SCHEDULE
- 13.3 PROVIDE TIMBER FLOOR FINISHES TO NOMINATED AREAS COMPLETE WITH ALL MATERIALS, DIMINISHING BOARDS ETC TO COMPLETE THE WORKS: FLOOR BOARDS TO BE SANDED AND POLISHED TO HIGH STANDARD WITH PREMIUM QUALITY SEALER (2 COATS). REFER TO DRAWINGS AND FINISHES SCHEDULE.

14.0 SIGNAGE

- 14.1 WHERE NECESSARY SUPPLY & FIX SELECTED UNIT AND HOUSE NUMBERS TO EACH UNIT AND TO LETTERBOXES AS SCHEDULED.
- 14.2 "SUPERDRAFT" RESERVES THE RIGHT TO ERECT A BUILDERS SIGN ON THE PROPERTY FACING THE STREET FRONTAGE IN COMPLIANCE WITH AUTHORITY REQUIREMENTS.

15.0 PAVING

- 15.1 GENERALLY: WHEN PAVING IS INCLUDED IN THE BUILDING CONTRACT THE FOLLOWING SHALL APPLY AS A MINIMUM STANDARD
 - SUPPLY AND LAY ALL PAVING TO EXTERNAL AREAS AS SHOWN ON WORKING DRAWINGS.
 - CUT, FILL & COMPACT SAND TO REQUIRED LEVELS. SCREED TO UNIFORM THINNESS AND LEVELS
 - PROVIDE BRICK EDGE RETAINING FOOTING EMBEDDED IN MORTAR BENEATH THE PAVING BRICK
 - TO DRIVEWAY AREAS, PROVIDE NOMINAL 300x150mm CONCRETE FOOTING ALONG PERIMETER OF DRIVEWAY AND BED EDGE BRICK IN MORTAR.
- 15.2 PROVIDE 100mm COMPACTED LIMESTONE BASE TO DRIVEWAY TOPPED WITH 50mm CLEAN SAND AND GRADE TO FALLS.
- 15.3 UNLESS NOTED PAVING PATTERN IS TO CLIENTS DETAIL
- 15.4 BRICK PAVERS SHALL BE: TRAFFICABLE AREAS: MIN. 65mm SOLID CLAY OR CONCRETE PEDESTRIAN AREAS: MIN. 43mm SOLID CLAY OR CONCRETE

16.0 ENERGY EFFICIENCY

- 16.1 INSULATION MUST FORM A CONTINUOUS BARRIER WITH CEILINGS, WALLS AND FLOORS BY ABUTTING OR OVERLAPPING ADJOINING INSULATION
- 16.2 INSULATION MUST NOT ADVERSELY AFFECT DOMESTIC SERVICES OR FITTINGS
- 16.3 REFLECTIVE INSULATION IS TO BE PROVIDED WITH A MINIMUM 25mm AIRSPACE AND IS FITTED CLOSE TO OPENINGS SUCH AS WINDOWS/DOORS ETC. AND IS PROVIDED WITH ADEQUATE SUPPORT.
- 16.4 BULK INSULATION MUST MAINTAIN ITS POSITION, THICKNESS.
- 16.5 ENSURE THAT CEILING INSULATION OVERLAPS UN-INSULATED WALLS CONSTRUCTION JOINTS, SUCH AS BETWEEN WALL AND FLOOR, ARE TO BE TIGHT FITTING OR SEALED USING CAULKING OR JOINERY ITEMS SUCH AS SKIRTING OR CORNICES
- 16.6 EXHAUST FANS ARE TO BE FITTED WITH A SELF CLOSING DAMPER
- 16.7 ROOF LIGHTS MUST BE SEALED WITH WEATHERPROOF SEALS
- 16.8 HEATED WATER PIPING MUST BE THERMALLY INSULATED AND PROTECTED AGAINST THE WEATHER AND SUN
- 16.9 INTERNAL HEATED WATER PIPING TO HAVE AN R VALUE OF 0.2
- 16.10 ENCLOSED SUB-FLOOR AND ROOF SPACE TO HAVE AN R VALUE OF 0.45

FEMME BUILD

NEW CONSTRUCTION
REMODELS
ADDITIONS
RENOVATIONS

0403 132 106
info@femmebuild.com.au

REPRODUCTION OF THE WHOLE OR PART OF THIS DOCUMENT CONSTITUTES AND INFRINGES COPYRIGHT. THE INFORMATION, IDEAS AND CONCEPTS CONTAINED IN THIS DOCUMENT IS / ARE CONFIDENTIAL. THE RECIPIENTS OF THIS DOCUMENT IS / ARE PROHIBITED FROM DISCLOSING SUCH INFORMATION IDEAS AND CONCEPTS TO ANY PERSON WITHOUT PRIOR WRITTEN CONSENT OF THE COPYRIGHT HOLDER. CONTRACTOR TO CHECK AND VERIFY ALL LEVELS, DIMENSIONS AND DIMENSIONS ON SITE AND SHALL REPORT ANY DISCREPANCIES OR OMISSIONS TO THIS OFFICE PRIOR TO START OF WORK & DURING THE CONSTRUCTION PHASE. THIS DRAWING IS TO BE READ AND UNDERSTOOD IN CONJUNCTION WITH STRUCTURAL, MECHANICAL, ELECTRICAL AND OR ANY OTHER CONSULTANTS DOCUMENTATION AS MAY BE APPLICABLE TO THE PROJECT PRIOR TO START OF WORK & ITS OPERATION. MEASUREMENT SCALING OF THIS DRAWING SHALL ONLY BE PERMITTED IN ITS DIGITAL FORM.

DRAWING SCHEDULE

A.00	ARCHITECTURAL SPECIFICATION
A.01.1	PROPOSED DEMOLITION PLAN
A.01.2	PROPOSED SITE PLAN
A.01.3	PROPOSED SITE ANALYSIS PLAN
A.01.4	PROPOSED EROSION CONTROL PLAN
A.02.1	PROPOSED GROUND FLOOR PLAN
A.02.2	PROPOSED FIRST FLOOR PLAN
A.02.3	PROPOSED ROOF PLAN
A.03.1	PROPOSED ELEVATIONS
A.03.2	PROPOSED ELEVATIONS
A.04.1	PROPOSED SECTION & DETAILS
A.06.1	PROPOSED SHADOW DIAGRAMS
A.06.2	PROPOSED SHADOW DIAGRAMS
A.06.3	PROPOSED SHADOW DIAGRAMS

01	DEVELOPMENT APPLICATION	SK	16.12.21
REV	AMENDMENT DETAILS	BY	DATE

PROJECT STAGE DEVELOPMENT APP.

PROJECT DETAILS TOWNHOUSE DEVELOP.

83-85 CANBERRA STREET,
OXLEY PARK, NSW 2760

CLIENT DETAILS AHMET YESIL

DRAWING TITLE TITLE1 TITLE2

DRAWN	SK
DESIGNED	FB
CHECK	FB
DATE DRAWN	DEC 2021
DRAWING SCALE	SCALE
SHEET SIZE	SS

bdada
**ACCREDITED
BUILDING DESIGNER**


ACCREDITATION NUMBER: 6613 - MEMBER NUMBER 6763-21

PROJECT NUMBER	DRAWING NUMBER	REVISION
FB0053	A.00	01

SITE NOTES

- CONFIRM ALL DIMENSIONS ON SITE TO EXISTING RESIDENCE PRIOR TO COMMENCEMENT OF ANY WORK.
- EXISTING PLUMBING AND ELECTRICAL WORKS TO BE REMOVED AND MADE GOOD AS NECESSARY.
- THIS PLAN DOES NOT PROVIDE SPECIFIC LANDSCAPE PLANTING LOCATIONS.
- THE EXACT LOCATION OF UNDERGROUND AND ABOVEGROUND SERVICES SHALL BE PROVEN ON SITE. NO GUARANTEE IS GIVEN THAT ALL EXISTING SERVICES ARE SHOWN.
- THIS DRAWING SET TO BE READ IN CONJUNCTION WITH THE SPECIFICATION PROVIDED.
- BEWARE OF EXISTING SERVICES. CONFIRM LOCATIONS PRIOR TO EXCAVATION. TAKE EXTREME CARE.
- REFER ALL MAJOR WORKS TO RAMPS, WALKWAYS, DRIVEWAYS ETC (INCLUDING CARPARK WORKS, LEVELS & DATUMS) REFER TO CIVIL ENGINEERS DOCUMENTATION.

REPRODUCTION OF THE WHOLE OR PART OF THIS DOCUMENT CONSTITUTES AN INFRINGEMENT OF COPYRIGHT. THE INFORMATION, IDEAS AND CONCEPTS CONTAINED IN THIS DOCUMENT ARE CONFIDENTIAL AND THE PROPERTY OF FEMME BUILD. ANY UNAUTHORIZED REPRODUCTION OR DISCLOSURE OF SUCH INFORMATION, IDEAS AND CONCEPTS TO ANY PERSON WITHOUT PRIOR WRITTEN CONSENT OF THE COPYRIGHT HOLDER. CONTRACTOR TO CHECK AND VERIFY ALL LEVELS, DATUMS & DIMENSIONS ON SITE AND SHALL REPORT ANY DISCREPANCIES OR OMISSIONS TO THIS OFFICE PRIOR TO START OF WORK & DURING THE CONSTRUCTION PHASE. THIS DRAWING IS TO BE READ AND UNDERSTOOD IN CONJUNCTION WITH STRUCTURAL, MECHANICAL, ELECTRICAL AND/OR ANY OTHER CONSULTANT'S DOCUMENTATION AS MAY BE APPLICABLE TO THE PROJECT PRIOR TO START OF WORK & ITS DURATION. MEASUREMENT SCALING OF THIS DRAWING SHALL ONLY BE PERMITTED IN ITS DIGITAL FORM.



SITE INFORMATION

SITE AREA	2,194.40m²
UNITS 1-5	
PROPOSED RESIDENCE G. FLOOR	37m²
GARAGE	17.05m²
ALFRESCO	11m²
PROPOSED RESIDENCE F.FLOOR	70.69m²
TOTAL FLOOR AREA	107.69m²
PRIVATE OPEN SPACE	31.75m² MIN
CAR PARKING	2
UNIT 6	
PROPOSED RESIDENCE G. FLOOR	51.92m²
GARAGE	17.05m²
ALFRESCO	9m²
PROPOSED RESIDENCE F.FLOOR	70.69m²
TOTAL FLOOR AREA	122.61m²
PRIVATE OPEN SPACE	92.63m²
CAR PARKING	2
UNIT 7	
PROPOSED RESIDENCE G. FLOOR	47.92m²
GARAGE	17.05m²
ALFRESCO	7.92m²
PROPOSED RESIDENCE F.FLOOR	70.69m²
TOTAL FLOOR AREA	118.61m²
PRIVATE OPEN SPACE	85.22m²
CAR PARKING	2
UNITS 8-12	
PROPOSED RESIDENCE G. FLOOR	37m²
GARAGE	17.05m²
ALFRESCO	11m²
PROPOSED RESIDENCE F.FLOOR	70.69m²
TOTAL FLOOR AREA	107.69m²
PRIVATE OPEN SPACE	31.75m² MIN
CAR PARKING	2
TOTAL FLOOR AREA	1,210.43m²
PERMEABILITY	38%
MAX BUILDING HEIGHT	7m

01	DEVELOPMENT APPLICATION	SK	16.12.21
REV	AMENDMENT DETAILS	BY	DATE

PROJECT STAGE
 DEVELOPMENT APP.
PROJECT DETAILS
 TOWNHOUSE DEVELOP.

83-85 CANBERRA STREET,
 OXLEY PARK, NSW 2760

CLIENT DETAILS
AHMET YESIL

DRAWING TITLE
PROPOSED SITE PLAN


DRAWN
 SK
 DESIGNED
 FB
 CHECK
 FB

DATE DRAWN
 DEC 2021
 DRAWING SCALE
 1 : 125
 SHEET SIZE
 A1




ACCREDITATION NUMBER: 6613 - MEMBER NUMBER 6763-21

PROJECT NUMBER	DRAWING NUMBER	REVISION
FB0053	A.01.1	01



PROPOSED SITE PLAN
 SCALE - 1 : 250

REPRODUCTION OF THE WHOLE OR PART OF THIS DOCUMENT CONSTITUTES AND INFRINGES COPYRIGHT. THE INFORMATION, IDEAS AND CONCEPTS CONTAINED IN THIS DOCUMENT IS / ARE CONFIDENTIAL. THE RECIPIENTS OF THIS DOCUMENT IS / ARE PROHIBITED FROM DISCLOSING SUCH INFORMATION IDEAS AND CONCEPTS TO ANY PERSON WITHOUT PRIOR WRITTEN CONSENT OF THE COPYRIGHT HOLDER. CONTRACTOR TO CHECK AND VERIFY ALL LEVELS, DATUMS, & DIMENSIONS ON SITE AND SHALL REPORT ANY DISCREPANCIES OR OMISSIONS TO THIS OFFICE PRIOR TO START OF WORK & DURING THE CONSTRUCTION PHASE. THIS DRAWING IS TO BE READ AND UNDERSTOOD IN CONJUNCTION WITH STRUCTURAL, MECHANICAL, ELECTRICAL AND/OR ANY OTHER CONSULTANT'S DOCUMENTATION AS MAY BE APPLICABLE TO THE PROJECT PRIOR TO START OF WORK & ITS DURATION. MEASUREMENT SCALING OF THIS DRAWING SHALL ONLY BE PERMITTED IN ITS DIGITAL FORM.



PROPOSED SITE ANALYSIS PLAN
 SCALE - 1 : 250


01	DEVELOPMENT APPLICATION	SK	16.12.21
REV	AMENDMENT DETAILS	BY	DATE
PROJECT STAGE			
DEVELOPMENT APP.			
PROJECT DETAILS			
TOWNHOUSE DEVELOP.			
83-85 CANBERRA STREET, OXLEY PARK, NSW 2760			
CLIENT DETAILS			
AHMET YESIL			
DRAWING TITLE			
PROPOSED SITE ANALYSIS PLAN			



ACCREDITATION NUMBER: 6613 - MEMBER NUMBER 6763-21

DRAWN	SK
DESIGNED	FB
CHECK	FB
DATE DRAWN	DEC 2021
DRAWING SCALE	1 : 125
SHEET SIZE	A1


PROJECT NUMBER	DRAWING NUMBER	REVISION
FB0053	A.01.2	01



CONSTRUCTION NOTES

- CONFIRM ALL DIMENSIONS ON SITE TO EXISTING RESIDENCE PRIOR TO COMMENCEMENT OF ANY WORK.
- SUPPLY AND INSTALL 'BIFLEX' CHEMICAL TERMITE TREATMENT (UNLESS OTHERWISE APPROVED) TO COMPLY WITH AS3660.1 AND MANUFACTURER'S SPECIFICATIONS
- ALL BRICKWORK (INCLUDING BRICK VENEER) SHALL BE IN ACCORDANCE WITH AS3700- MASONRY CODE
- ALL TIMBER FRAMING SHALL BE IN ACCORDANCE WITH AS1684. - UNLESS OTHERWISE APPROVED ROOF FRAMING SHALL BE OF TRADITIONAL TIMBER FRAMED CONSTRUCTION
- FOR ALL STRUCTURAL MEMBERS, FOOTINGS, & LOAD BEARING WALLS REFER TO STRUCTURAL DOCUMENTATION PREPARED BY ENGINEERS.

REPRODUCTION OF THE WHOLE OR PART OF THIS DOCUMENT CONSTITUTES AND INFRINGES COPYRIGHT. THE INFORMATION, IDEAS AND CONCEPTS CONTAINED IN THIS DOCUMENT IS/ARE CONFIDENTIAL. THE RECIPIENT(S) OF THIS DOCUMENT IS/ARE PROHIBITED FROM DISCLOSING SUCH INFORMATION IDEAS AND CONCEPTS TO ANY PERSON WITHOUT PRIOR WRITTEN CONSENT OF THE COPYRIGHT HOLDER. CONTRACTOR TO CHECK AND VERIFY ALL LEVELS, DATUMS & DIMENSIONS ON SITE AND SHALL REPORT ANY DISCREPANCIES OR OMISSIONS TO THIS OFFICE PRIOR TO START OF WORK & DURING THE CONSTRUCTION PHASE. THIS DRAWING IS TO BE READ AND UNDERSTOOD IN CONJUNCTION WITH STRUCTURAL, MECHANICAL, ELECTRICAL AND OR ANY OTHER CONSULTANT'S DOCUMENTATION AS MAY BE APPLICABLE TO THE PROJECT PRIOR TO START OF WORK & ITS DURATION. MEASUREMENT SCALING OF THIS DRAWING SHALL ONLY BE PERMITTED IN ITS DIGITAL FORM.



WALL SCHEDULE
 WALL SARKING & BULK INSULATION AS REQUIRED BY ENERGY ASSESSMENT

- BRICK VENEER WALL.**
 SELECTED. EXPOSED FACE BRICK (RE-USE RECYCLED BRICK FROM DEMOLITION).
 INTERIOR FINISH OTHER - PROVIDE FLUSH PLASTER FINISH.
- EXTERIOR TIMBER STUD WALL.**
 SELECTED. HORIZONTAL WEATHERBOARDS FIXED TO TIMBER STUD. INTERIOR FINISH TO BE FLUSH PLASTERBOARD UNLESS SPECIFIED OTHERWISE.
- INTERIOR TIMBER STUD WALL.**
 SELECTED PLASTERBOARD SHEETING TO BOTH SIDES. BUILDER TO PROVIDE WATERPROOF FIBRE CEMENT SHEETING TO ALL WET AREAS FOR SELECTED TILES.



01	DEVELOPMENT APPLICATION	SK	16.12.21
REV	AMENDMENT DETAILS	BY	DATE

PROJECT STAGE
 DEVELOPMENT APP.

PROJECT DETAILS
 TOWNHOUSE DEVELOP.

83-85 CANBERRA STREET,
 OXLEY PARK, NSW 2760

CLIENT DETAILS
 AHMET YESIL

DRAWING TITLE
 PROPOSED GROUND FLOOR PLAN

DRAWN: SK
 DESIGNED: FB
 CHECKED: FB

DATE DRAWN: DEC 2021
 DRAWING SCALE: 1:125
 SHEET SIZE: A1



PROJECT NUMBER	DRAWING NUMBER	REVISION
FB0053	A.02.1	01

ACCREDITATION NUMBER: 6613 - MEMBER NUMBER 6763-21

0 1m 2m 3m 4m 5m 7.5m 10m 12.5m
 1:125 @ A1 1:250 @ A3 1:707 @ A4

PROPOSED GROUND FLOOR PLAN
 SCALE - 1 : 125

CONSTRUCTION NOTES

- CONFIRM ALL DIMENSIONS ON SITE TO EXISTING RESIDENCE PRIOR TO COMMENCEMENT OF ANY WORK.
- SUPPLY AND INSTALL 'BIFLEX' CHEMICAL TERMITE TREATMENT (UNLESS OTHERWISE APPROVED) TO COMPLY WITH AS3660.1 AND MANUFACTURER'S SPECIFICATIONS
- ALL BRICKWORK (INCLUDING BRICK VENEER) SHALL BE IN ACCORDANCE WITH AS3700- MASONRY CODE
- ALL TIMBER FRAMING SHALL BE IN ACCORDANCE WITH AS1684. - UNLESS OTHERWISE APPROVED ROOF FRAMING SHALL BE OF TRADITIONAL TIMBER FRAMED CONSTRUCTION
- FOR ALL STRUCTURAL MEMBERS, FOOTINGS, & LOAD BEARING WALLS REFER TO STRUCTURAL DOCUMENTATION PREPARED BY ENGINEERS.

FEMME BUILD

NEW CONSTRUCTION
REMODELS
ADDITIONS
RENOVATIONS



0403 132 106
info@femmebuild.com.au

REPRODUCTION OF THE WHOLE OR PART OF THIS DOCUMENT CONSTITUTES AN INFRINGEMENT OF COPYRIGHT. THE INFORMATION, IDEAS AND CONCEPTS CONTAINED IN THIS DOCUMENT IS/ARE CONFIDENTIAL. THE RECIPIENT(S) OF THIS DOCUMENT IS/ARE PROHIBITED FROM DISCLOSING SUCH INFORMATION IDEAS AND CONCEPTS TO ANY PERSON WITHOUT PRIOR WRITTEN CONSENT OF THE COPYRIGHT HOLDER. CONTRACTOR TO CHECK AND VERIFY ALL LEVELS, DATUMS & DIMENSIONS ON SITE AND SHALL REPORT ANY DISCREPANCIES OR OMISSIONS TO THIS OFFICE PRIOR TO START OF WORK & DURING THE CONSTRUCTION PHASE. THIS DRAWING IS TO BE READ AND UNDERSTOOD IN CONJUNCTION WITH STRUCTURAL, MECHANICAL, ELECTRICAL AND/OR ANY OTHER CONSULTANT'S DOCUMENTATION AS MAY BE APPLICABLE TO THE PROJECT PRIOR TO START OF WORK & ITS DURATION. MEASUREMENT SCALING OF THIS DRAWING SHALL ONLY BE PERMITTED IN ITS DIGITAL FORM.

WALL SCHEDULE

WALL SARKING & BULK INSULATION AS REQUIRED BY ENERGY ASSESSMENT

- BRICK VENEER WALL.**
SELECTED. EXPOSED FACE BRICK (RE-USE RECYCLED BRICK FROM DEMOLITION).
INTERIOR FINISH OTHER - PROVIDE FLUSH PLASTER FINISH.
- EXTERIOR TIMBER STUD WALL.**
SELECTED. HORIZONTAL WEATHERBOARDS FIXED TO TIMBER STUD. INTERIOR FINISH TO BE FLUSH PLASTERBOARD UNLESS SPECIFIED OTHERWISE.
- INTERIOR TIMBER STUD WALL.**
SELECTED PLASTERBOARD SHEETING TO BOTH SIDES. BUILDER TO PROVIDE WATERPROOF FIBRE CEMENT SHEETING TO ALL WET AREAS FOR SELECTED TILES.



ELEVATION DIRECTION

01	DEVELOPMENT APPLICATION	SK	16.12.21
REV	AMENDMENT DETAILS	BY	DATE

PROJECT STAGE
DEVELOPMENT APP.

PROJECT DETAILS
TOWNHOUSE DEVELOP.

**83-85 CANBERRA STREET,
OXLEY PARK, NSW 2760**

CLIENT DETAILS
AHMET YESIL

DRAWING TITLE
PROPOSED FIRST FLOOR PLAN

DRAWN
SK

DESIGNED
FB

CHECK
FB

DATE DRAWN
DEC 2021


DRAWING SCALE
1:125

SHEET SIZE
A1





ACCREDITATION NUMBER: 6613 - MEMBER NUMBER 6763-21

PROJECT NUMBER	DRAWING NUMBER	REVISION
FB0053	A.02.2	01




PROPOSED FIRST FLOOR PLAN
SCALE - 1:125

COPYRIGHT 2021 FEMME BUILD
REPRODUCTION OF THE WHOLE OR PART OF THE DOCUMENT CONSTITUTES AND INFRINGES COPYRIGHT. THE INFORMATION, IDEAS AND CONCEPTS CONTAINED IN THIS DOCUMENT IS / ARE CONFIDENTIAL. THE RECIPIENTS OF THE DOCUMENT IS / ARE PROHIBITED FROM DISCLOSING SUCH INFORMATION IDEAS AND CONCEPTS TO ANY PERSON WITHOUT PRIOR WRITTEN CONSENT OF THE COPYRIGHT HOLDER. CONTRACTOR TO CHECK AND VERIFY ALL LEVELS, DATUMS, & DIMENSIONS ON SITE AND SHALL REPORT ANY DISCREPANCIES OR OMISSIONS TO THIS OFFICE PRIOR TO START OF WORK & DURING THE CONSTRUCTION PHASE. THIS DRAWING IS TO BE READ AND UNDERSTOOD IN CONJUNCTION WITH STRUCTURAL, MECHANICAL, ELECTRICAL AND OR ANY OTHER CONSULTANT'S DOCUMENTATION AS MAY BE APPLICABLE TO THE PROJECT PRIOR TO START OF WORK & ITS DURATION. MEASUREMENT SCALING OF THIS DRAWING SHALL ONLY BE PERMITTED IN ITS DIGITAL FORM.



1. PROPOSED WESTERN ELEVATION
SCALE - 1 : 100



2. PROPOSED SOUTHERN ELEVATION
SCALE - 1 : 100

01	DEVELOPMENT APPLICATION	SK	16.12.21
REV	AMENDMENT DETAILS	BY	DATE

PROJECT STAGE
DEVELOPMENT APP.

PROJECT DETAILS
TOWNHOUSE DEVELOP.

**83-85 CANBERRA STREET,
OXLEY PARK, NSW 2760**

CLIENT DETAILS
AHMET YESIL


DRAWING TITLE
**PROPOSED
ELEVATIONS 1 & 2**





ACCREDITATION NUMBER: 6613 - MEMBER NUMBER 6763-21

DRAWN
SK
DESIGNED
FB
CHECK
FB
DATE DRAWN
DEC 2021
DRAWING SCALE
1 : 100
SHEET SIZE
A1


PROJECT NUMBER	DRAWING NUMBER	REVISION
FB0053	A.03.1	01



COPYRIGHT 2021 FEMME BUILD
 REPRODUCTION OF THE WHOLE OR PART OF THIS DOCUMENT CONSTITUTES AND INFRINGES COPYRIGHT. THE INFORMATION, IDEAS AND CONCEPTS CONTAINED IN THIS DOCUMENT IS / ARE CONFIDENTIAL. THE RECIPIENTS OF THIS DOCUMENT IS / ARE PROHIBITED FROM DISCLOSING SUCH INFORMATION IDEAS AND CONCEPTS TO ANY PERSON WITHOUT PRIOR WRITTEN CONSENT OF THE COPYRIGHT HOLDER. CONTRACTOR TO CHECK AND VERIFY ALL LEVELS, DATUMS, & DIMENSIONS ON SITE AND SHALL REPORT ANY DISCREPANCIES OR OMISSIONS TO THIS OFFICE PRIOR TO START OF WORK & DURING THE CONSTRUCTION PHASE. THIS DRAWING IS TO BE READ AND UNDERSTOOD IN CONJUNCTION WITH STRUCTURAL, MECHANICAL, ELECTRICAL AND/OR ANY OTHER CONSULTANT'S DOCUMENTATION AS MAY BE APPLICABLE TO THE PROJECT PRIOR TO START OF WORK & ITS DURATION. MEASUREMENT SCALING OF THIS DRAWING SHALL ONLY BE PERMITTED IN ITS DIGITAL FORM.



3. PROPOSED EASTERN ELEVATION
 SCALE - 1 : 100



4. PROPOSED NORTHERN ELEVATION
 SCALE - 1 : 100

01	DEVELOPMENT APPLICATION	SK	16.12.21
REV	AMENDMENT DETAILS	BY	DATE

PROJECT STAGE
DEVELOPMENT APP.

PROJECT DETAILS
TOWNHOUSE DEVELOP.

**83-85 CANBERRA STREET,
 OXLEY PARK, NSW 2760**

CLIENT DETAILS
AHMET YESIL

DRAWING TITLE
**PROPOSED
 ELEVATIONS 3 & 4**

DRAWN
 SK
 DESIGNED
 FB
 CHECK
 FB

DATE DRAWN
DEC 2021


DRAWING SCALE
1 : 100


SHEET SIZE
A1



ACCREDITATION NUMBER: 6613 - MEMBER NUMBER 6763-21

PROJECT NUMBER	DRAWING NUMBER	REVISION
FB0053	A.03.2	01





9:00 AM

9:00 AM

9:00 AM

9:00 AM

9:00 AM

01	DEVELOPMENT APPLICATION	SK	16.12.21
REV	AMENDMENT DETAILS	BY	DATE

PROJECT STAGE
DEVELOPMENT APP.

PROJECT DETAILS
TOWNHOUSE DEVELOP.

**83-85 CANBERRA STREET,
OXLEY PARK, NSW 2760**

CLIENT DETAILS
AHMET YESIL

DRAWING TITLE
**PROPOSED SHADOW
DIAGRAMS - 9AM JUNE 21**

DRAWN
SK

DESIGNED
FB

CHECK
FB

DATE DRAWN
DEC 2021


DRAWING SCALE
1:250


SHEET SIZE
A3



ACCREDITATION NUMBER: 6613 - MEMBER NUMBER 6763-21

PROJECT NUMBER	DRAWING NUMBER	REVISION
FB0053	A.06.1	01





01	DEVELOPMENT APPLICATION	SK	16.12.21
REV	AMENDMENT DETAILS	BY	DATE

PROJECT STAGE
DEVELOPMENT APP.

PROJECT DETAILS
TOWNHOUSE DEVELOP.

**83-85 CANBERRA STREET,
OXLEY PARK, NSW 2760**

CLIENT DETAILS
AHMET YESIL

DRAWING TITLE
**PROPOSED SHADOW
DIAGRAMS - 12PM JUNE 21**

DRAWN
SK

DESIGNED
FB

CHECK
FB

DATE DRAWN
DEC 2021



DRAWING SCALE
1:250

SHEET SIZE
A3




ACCREDITATION NUMBER: 6613 - MEMBER NUMBER 6763-21

PROJECT NUMBER	DRAWING NUMBER	REVISION
FB0053	A.06.2	01



COPYRIGHT 2021 FEMME BUILD
 REPRODUCTION OF THE WHOLE OR PART OF THIS DOCUMENT CONSTITUTES AND
 INFRINGES COPYRIGHT. THE INFORMATION, IDEAS AND CONCEPTS CONTAINED IN THIS
 DOCUMENT IS / ARE CONFIDENTIAL. THE RECIPIENTS OF THIS DOCUMENT IS / ARE
 PROHIBITED FROM DISCLOSING SUCH INFORMATION IDEAS AND CONCEPTS TO ANY
 PERSON WITHOUT PRIOR WRITTEN CONSENT OF THE COPYRIGHT HOLDER.
 CONTRACTOR TO CHECK AND VERIFY ALL LEVELS, DATUMS, & DIMENSIONS ON SITE AND
 SHALL REPORT ANY DISCREPANCIES OR OMISSIONS TO THIS OFFICE PRIOR TO START OF
 WORK & DURING THE CONSTRUCTION PHASE. THIS DRAWING IS TO BE READ AND
 UNDERSTOOD IN CONJUNCTION WITH STRUCTURAL, MECHANICAL, ELECTRICAL AND OR
 ANY OTHER CONSULTANT'S DOCUMENTATION AS MAY BE APPLICABLE TO THE PROJECT
 PRIOR TO START OF WORK & ITS DURATION. MEASUREMENT SCALING OF THIS
 DRAWING SHALL ONLY BE PERMITTED IN ITS DIGITAL FORM.



01	DEVELOPMENT APPLICATION	SK	16.12.21
REV	AMENDMENT DETAILS	BY	DATE

PROJECT STAGE
DEVELOPMENT APP.

PROJECT DETAILS
TOWNHOUSE DEVELOP.

83-85 CANBERRA STREET,
 OXLEY PARK, NSW 2760

CLIENT DETAILS
AHMET YESIL

DRAWING TITLE
**PROPOSED SHADOW
 DIAGRAMS - 3PM JUNE 21**

DRAWN
 SK

DESIGNED
 FB

CHECK
 FB

DATE DRAWN
 DEC 2021

DRAWING SCALE
 1:250

SHEET SIZE
 A3

ACCREDITATION NUMBER: 6613 - MEMBER NUMBER 6763-21

PROJECT NUMBER
FB0053

DRAWING NUMBER
A.06.3

REVISION
01

0 1m 2m 3m 4m 5m 7.5m 10m 12.5m
 1:125 @ A1 1:250 @ A3 1:707 @ A4

