

## EAST TO WEST AND NORTH TO SOUTH OPEN CHANNEL


# Jordan Springs Openspace Development

Landscape Drawings



DRAWING S Drawing	Title	JUNE 14 Issue
Drawing	General	13346
3306-GE01	Key Plan	D
3306-GE02	Tree Retention and Removal Plan	D
3306-GE03	Legends and Notes	D
	East to West Open Channel	
3306-EW01	Construction Works Plan - Area 1	D
3306-EW02	Construction Works Plan - Area 2	D
3306-EW03	Construction Works Plan - Area 3	D
3306-EW04	Planting and Revegetation Plan - Area 1	D
3306-EW05	Planting and Revegetation Plan - Area 2	D
3306-EW06	Planting and Revegetation Plan - Area 3	D
	North to South Open Channel	1000
3306-NS01	Construction Works Plan - Area 1 & 2	D
3306-NS02	Construction Works Plan - Area 3	D
3306-NS03	Planting and Revegetation Plan - Area 1 & 2	D
3306-NS04	Planting and Revegetation Plan - Area 3	D
	Landscape Works Details	
3306-D01	Riparian Corridor Details - sheet 1	C
3306-D02	Riparian Corridor Details - sheet 2	C
3306-D03	Riparian Corridor Details - sheet 3	C
3306-D04	Riparian Corridor Details - sheet 4	CCCC
3306-D05	Riparian Corridor Details - sheet 5	C





### **LEGEND**

#### Generally



Existing trees to be protected



Existing trees to be removed Note: Harvest felled tree trunks and locate to revegetation areas as directed by the Superintendent



Spot tree plantings

Setout and Levels

Proposed 0.5m design contours Refer Engineers drawings

Dimensions in millimetres - setout on



site and request approval by Superintendent prior proceeding with

FL 35.50 Finished levels

Setout coordinates - refer setout schedule GE.03

Nominal 1:80 fall to pavement Note where no fall indicated all pathways to have nominal 1:80 crossfall

 Existing contours will be supeceded by road (kerbline) design levels along edge of corridor. Junction of open space design (proposed) contours with kerbline are based on kerb design



Channel Base Zone

Revegetation Zone

 Planted and stabilised channel base ("MaxBio" erosion control matting)

## Embankment Zone



 Groundcovers at 6 / m2 Scattered spot tree planting

Groundcovers at 4 / m2

"Jutemaster thick" erosion control matting

## Refer plan labels for plant species



Scattered spot tree plantings

Scattered shrubs planting in groups Refer plan labels for plant species



Rock lined area - Refer engineers drawings

Turfed area - Refer detail 05, drawing D05

## **Built Elements**



Proposed concrete path - 1.5m wide typically - Refer detail 01, drawing D01 Post & cable fencing - refer detail 03, drawing D01

Proposed shared concrete path - 2.5m wide

tvpically - Refer detail 01, drawing D01

Note grade 1:25 fall maximum



Concrete edge - refer detail 02, drawing D01



Refer detail 04, drawing D01 Picnic shelter - Refer detail 04, drawing D02

Rip rap retaining wall



& detail 01, drawing D03 Picnic tables - Refer detail 02, drawing D02




Backed seat on 1.0x2.0m approx. concrete pad



- Refer detail 01, drawing D02



- Refer detail 03, drawing D02 Removable steel bollards



- Refer detail 03, drawing D02 Proposed lighting locations



Extent of works

Fixed steel bollards

#### **GENERAL NOTES**

- 1. Existing survey boxes and marks disturbed during construction shall be replaced to new positions as directed by Superintendent.
- 2. Do not use vibratory equipment, except for hand held machines, over the subsurface services. It is the Contractor's responsibility to ensure there is no damage to existing services during the works. Replace all materials/ surface damaged to private/ public property. Ensure dated photographs are taken to kerbs and gutters to clearly indicate the existing conditions or any other structures before commencement of construction supply one set of photographs to The Principal and retain one
- 3. The Contractor is to provide temporary silt barriers such as gravel bags/roll, around all stormwater inlet pits to minimise silt and contaminants entering the stormwater lines. During construction the silt traps are to be regularly maintained and any accumulated silt and debris is to be removed from such devices to maintain at least 60% of their capacities.
- 4. All existing service access pits, inspection pits and valve covers conflicting with finished surface levels are to be raised or lowered. The Contractor is to ensure that these adjustments are undertaken in accordance with engineer's details. Confirm treatment of unknown owner covers with Superintendent prior to undertaking adjustment.
- 5. Drawings to be read in conjunction with Survey drawings

#### SET OUT

- All dimensions are in milimetres
- 2. Running measurements may be provided along main setout lines
- 3. Do not scale off drawings where setout points and dimensions are provided.
- 4. Setout alignment and levels of all paths, walls and edges for approval by Superintendent prior to commencement of works. If any discrepancy is found or doubt exists between setout and levels as indicated on dwgs and site conditions this shall be referred to the superintendent with adequate notice for provision of advice prior to the continuation of works.
- 5. Benchmarks will be clearly marked on site by the Contractor. Benchmark shall be maintained by the Contractor during the course of the project
- 6. All setting out shall be established by the contractor who will be responsible for the accuracy of lines and levels of finished work. If any discrepancy is found or doubt exists between setout and levels as indicated on dwgs and site conditions this shall be referred to the superintendent with adequate notice for provision of advice prior to the continuation of works.
- 7. Setout of all new tree plantings is to be verified on site by the Superintendent prior to planting.
- 8. Any setout not approved by the Superintendent may be subject to relocation at the contractors cost.
- 9. Setout locations of furniture items are to be verified on site by Superintendent prior to the excavation of footings and installation

- 1. Setout all levels for construction and approval on site with marker stakes to which levels are notated and
- 2. Adjust all levels as instructed prior to final construction works
- 3. All falls are to be established as uniform grades
- between spot heights and contours 4. Paving to be profiled to provide minimum 1:80 fall (unless otherwise noted on plans) for stormwater over land flow.

#### **EROSION AND SEDIMENT CONTROL**

- 1. All work shall be generally carried out in accordance with (a) Council specifications and requirements,
- (b) EPA Pollution control manual for urban stormwater 2. The contractor shall provide an Erosion and Sediment Control Plan for the works prior to commencement on-site for approval by the superintendent.
- 3. Maintain all erosion and sediment control devices to the
- satisfaction of the Superintendent and Council. 4. When stormwater pits are constructed prevent site runoff entering the pits unless silt fences are erected around pits.
- Minimise the area of site being disturbed at any one time. 6. Protect all stockpiles of materials from scour and erosion. Do not stockpile loose material in roadways, near drainage pits or
- 7. All soil and water control measures are to be put back in place at the end of each working day, and modified to best suit site
- 8. Control water from upstream of the site such that it does not enter the disturbed site.
- 9. All construction vehicles shall enter and exit the site via the designated construction entry / exit.
- 10. All vehicles entering the site shall be cleaned and inspected before leaving.
- 11. Maintain all stormwater pipes and pits clear of debris and sediment. Inspect stormwater system and clean out after
- 12. Clean out all erosion and sediment control devices after each

#### SEQUENCE OF WORKS

- 1. Prior to commencement of excavation the following soil
- management devices must be installed. 1.1 Construct silt fences below the site and across all potential runoff sites.
- 1.2 Construct temporary construction entry / exit and divert runoff to suitable control systems.
- 1.3 Construct measures to divert upstream flows into existing
- stormwater system. 1.4 Construct sedimentation traps / basins including outlet control
- and overflow. 1.5 Construct turf lined swales.
- 1.6 Provide sandbag sediment traps upstream of existing pits. 2. Construct geotextile filter pit surround around all proposed
- pits as they are constructed. 3. On completion of pavement provide sand bag kerb inlet sediment traps around pits.

- Extent of excavations if shown on drawings is indicative only refer levels, and drainage plans for detailed information.
- 2. Existing items noted for stockpile and removed without breakage shall be stockpiled and transported to the Delfin storage by the Contractor. Damaged items shall be removed from site and disposed of by the Contractor.
- 3. Existing trees to be removed shall be marked on site following approval of setout by superintendent. No trees other than those marked and approved shall be removed or damaged.
- 4. Trees not indicated on the survey or demolition plans shall be retained - seek advise and approval from superintendent prior to removal of any tree not shown on plans.
- 5. Provide protective fencing to all trees to be retained adjoining the works area of the canopy line of these trees. To trees as marked provide timber batten buffer to 1.8m height from base of tree - wire fix on outside for duration of works

	289547625	6265546673
EW09	289528925	6265559400
EW10	289582860	6265568594
EW11	289460558	6265571897
EW12	289445704	6265563893
EW13	289418351	6265557015
EW14	289395991	6265548125
EW15	289375692	6265543220
EW16	289621250	6265565125
EW17	289629537	6265554115
EW18	289658300	6265565668
EW19	289658403	6265555728
EW20	289684140	6265569860
EW20	289707850	6265570650
		F 100 1000 1000 1000 1000 1000 1000 100
EW22	289719150	6265569900
EW23	289712476	6265575111
EW23	289718282	6265576337
EW24	289716468	6265574857
EW24	289711150	6265576303
EW25	289745200	6265565450
EW26	289754036	6265551664
EW27	289781000	6265555248
EW28	289811900	6265550700
EW29		6265550180
	289834755	NAME OF THE PARTY OF THE PARTY.
EW30	289841788	6265555893
EW31	289847384	6265578556
EW32	289846507	6265564726
EW33	289847863	6265553449
EW34	289856209	6265547975
EW35	289870290	6265542251
EW36	289881493	6265541288
EW37	289860150	6265539900
SD119C 6 3514 (Spinory 619	MAN AND AND AND AND AND AND AND AND AND A	Description of the second
EW38	289852510	6265541200
EW39	289905322	6265530194
EW40	289927700	6265521300
EW41	289960851	6265513687
EW42	290001560	6265512840
EW43	290029400	6265517300
EW44	290055828	6265521431
EW45	290093139	6265524499
EW46	290130775	6265528525
579.275078A507575	A CONTRACTOR OF THE PROPERTY O	
EW47	290152754	6265533843
EW48	290142099	6265528406
EW49	290151649	6265527104
EW50	290157651	6265522316
EW51	290159800	6265526600
EW52	290161982	6265534134
EW53	290190775	6265548837
EW54	290220040	6265565160
EW55	290247300	6265575700
EW56	290261650	6265582392
The state of the s		Displacement of the
EW57	290278439	6265593261
EW58	290281716	6265596803
EW59	290185300	6265613700
EW60	290168850	6265611931
EW61	290150000	6265605950
EW62	290136000	6265601450
EW63	290109486	6265597370
EW64	290067145	6265601840
EW65	289941868	6265610313
EW66	289927946	6265610541
EW67	289914278	
		6265607879
EW68	289898400	6265606030
EW69	289894800	6265611800
EW70	289888600	6265613100
EW71	289886760	6265606580
EW72	289889523	6265611016
EW73	289893515	6265610762
EW74	289874625	6265608925
EW75	289858180	6265615200
EW75	289845140	6265623260
EW77	289837338	6265626008
EW78	289847733	6265618063
EW79	289852430	6265609650
EW80	289852185	6265598070
EW81	289855613	6265601422
EW82	289860415	6265607471
EW83	289868435	6265608165
EW84	289850523	6265591255
8-312-C-101-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1		
EW85	289943887	6265580746
EW86	289947776	6265575610
EW87	289967405	6265571628
EW88	289972898	6265572813
EW89	290084716	6265576793
EW90	290089632	6265573555
EW91	290098153	6265575191
EW92	290101889	6265580426
NS01	289571031	6265969037
NS02	289545588	6266007368
NS03	289535875	6266024156
	289529503	6266052259
NS04	289528697	6266117925
NS04 NS05	289527056	6266138798
100,000,000,000		6266156375
NS05 NS06	289522900	
NS05 NS06 NS07	289522900 289514300	
NS05 NS06 NS07 NS08	289514300	6266185650
NS05 NS06 NS07		

Coordinate Marker ID X Position

289504992

289485910

289500055

289513794

289527630

289537556

289547625

EW02

EW03

EW04

EW05

EW06

EW07

**EW08** 

Y Position 6265549471

6265551352

6265535107

6265546042

6265541549

6265544860

6265547883

6265546673

1. Do not scale of drawings. Follow written dimensions. If in doubt obtain written advice from the Superintendent. Verify all dimensions on site. Refer to legend for all symbol and code keys

**GENERAL NOTES:** 

Read in conjunction with the specifications Read in conjunction with all associated drawings

DRAWN: DATE: MINOR UPDATES FOR CC BL 19.06.14 FEB 14 FOR CC BL 09.04.14 LIGHTING LOCATIONS ADDED 05.03.14 CHECKED: DATE: FOR REVIEW 18.02.14 FEB 14 DRAWN DATE ISSUE **AMENDMENT** 

DESIGNED: DATE:

FEB 14

APPROVED:

APPROVED:

EP

APPROVED: PREPARED FOR: **Lend Lease**  LANDSCAPE ARCHITECTS AND URBAN DESIGNERS: **Environmental Partnership** 

Email: admin@epnsw.com.au ABN 53 088 175 437

-A-R

JORDAN

SPRINGS

East to West and North to South Open Channel **Jordan Springs Openspace Development** 

DRAWING TITLE:

Legend and Notes


**JUNE 2014** SCALE: ISSUE:


1:2000 (@A1)


DRAWING NO:


3306.GE03

Document Set ID: 6017577 Version: 1. Version Date: 30/06/2014























DESIGNED: DATE:

CHECKED: DATE:

FEB 14

FEB 14

FEB 14

DATE:

EP

DRAWN:

19.06.14

09.04.14

05.03.14

18.02.14

DRAWN DATE

MINOR UPDATES FOR CC

LIGHTING LOCATIONS ADDED

FOR CC

ISSUE

FOR REVIEW

**AMENDMENT** 



**GENERAL NOTES:** 

Do not scale of drawings. Follow written dimensions. If in doubt obtain written advice from the Superintendent.
Verify all dimensions on site.
Refer to legend for all symbol and code keys.
Read in conjunction with the specifications.
Read in conjunction with all associated drawings



ID	Qty	Common Name	Botanical Name	Size	Mature Height	Mature Spread	Spacing
Trees							
TAS	24	Broad Leaved Apple	Angophora subvelutina	5L	15 - 20m	6 - 10m	as shown
TEA	27	Cabbage Gum	Eucalyptus amplifolia	5L	25 - 30m	3.5 - 6m	as shown
TEB	14	Blue Box	Eucalyptus bauerana	5L	25 - 30m	3.5 - 6m	as shown
TWF	10	Weeping Lilly Pilly	Waterhousia floribunda	5L	5 - 6m	3.5 - 6m	as shown
Shrubs							
BS	31	Blackthorn	Bursaria spinosa	150mm	5 - 10m	0.3 - 0.6m	1500mm
CC	113	Scarlet Bottlebrush	Callistemon citrinus	150mm	3 - 5m	2.0 - 3.5m	1500mm
DO	105	Common Hop Bush	Dodonaea triquetra	150mm	1.5 - 3m	1.2 - 2.0m	1500mm
GJ	52	Prickly Grevillea	Grevillea juniperina	150mm	0.6 - 0.75m	2.0 - 3.5m	1500mm
Native Gr	asses & (	Ground Covers					
JU	15060	Common Rush	Juncus usitatus	viro tube	0.9 - 1.5m	0.6 - 0.9m	6 per m2
CX	14478	Tall Sedge	Carex appressa	viro tube	0.9 - 1.5m	0.3 - 0.6m	4 /6 per m2
CE	10039	Tall flat segde	Cyperus exalatus	viro tube	0.45 - 0.6m	0.3 - 0.6m	6 per m2
LL	27821	Spiny-headed Mat-Rush	Lomandra longifolia	viro tube	0.75 - 0.9m	0.9 - 1.2m	4 per m2
GS	5019	Ghania	Ghania sieberiana	viro tube	0.75 - 0.9m	0.3 - 0.6m	6 per m2
TA	17782	Kangaroo Grass	Themeda australis	viro tube	0.9 - 1.5m	0.3 - 0.6m	4 per m2
CR	8887	Barbed Wire Grass	Cymbopogon refractus	viro tube	0.6 - 0.75m	0.3 - 0.6m	4 per m2
DA	8887	Long leaved Wallaby Grass	Danthonia longifolia	viro tube	0.9 - 1.5m	0.3 - 0.6m	4 per m2
EE	8887	Lavender Grass	Eragrostis elongata	viro tube	0.3 - 0.45m	0.0 - 0.3m	4 per m2
PL	8887	Tussock Grass	Poa labillardieri	viro tube	0.75 - 0.9m	0.6 - 0.9m	4 per m2
CS	8887	Scented-top Grass	Capillipedium spicigerum	viro tube	0.9 - 1.5m	0.3 - 0.6m	4 per m2
MI	4439	Weeping Grass	Microlaena stipoides	viro tube	0.6 - 0.75m	0.6 - 0.9m	4 per m2

DESIGNED: DATE:

CHECKED: DATE:

FEB 14

FEB 14

FEB 14

EP

DRAWN:

BL 19.06.14

DRAWN DATE

09.04.14

05.03.14

18.02.14

MINOR UPDATES FOR CC

LIGHTING LOCATIONS ADDED


FOR CC

FOR REVIEW

**AMENDMENT** 

APPROVED: PREPARED FOR:

APPROVED:



**GENERAL NOTES:** 

Do not scale of drawings. Follow written dimensions. If in doubt obtain written advice from the Superintendent.
Verify all dimensions on site.
Refer to legend for all symbol and code keys.
Read in conjunction with the specifications.
Read in conjunction with all associated drawings