


COMMERCIAL DEVELOPMENT 243 FORRESTER RD, ST MARYS NSW CIVIL ENGINEERING WORKS



GENERAL NOTES:

- ALL WORK TO BE CARRIED OUT IN ACCORDANCE WITH PENRITH COUNCIL'S SPECIFICATION. CONTRACTOR TO OBTAIN AND RETAIN A COPY ON SITE DURING THE COURSE OF THE WORKS.
- ALL NEW WORKS ARE TO MAKE A SMOOTH JUNCTION WITH EXISTING CONDITIONS AND MARRY IN A 'WORKMANLIKE' MANNER.
- THE CONTRACTOR IS TO VERIFY THE LOCATION OF ALL SERVICES WITH EACH RELEVANT AUTHORITY. ANY DAMAGE TO SERVICES SHALL BE RECTIFIED BY THE CONTRACTOR OR THE RELEVANT AUTHORITY AT THE CONTRACTOR'S EXPENSE. SERVICES SHOWN ON THESE PLANS ARE ONLY THOSE EVIDENT AT THE TIME OF SURVEY OR AS DETERMINED FROM SERVICE DIAGRAMS. H & H CONSULTING ENGINEERS PTY. LTD CANNOT GUARANTEE THE INFORMATION SHOWN NOR ACCEPT ANY RESPONSIBILITY FOR INACCURACIES OR INCOMPLETE DATA.
- SERVICES & ACCESSES TO THE EXISTING PROPERTIES ARE TO BE MAINTAINED IN WORKING ORDER AT ALL TIMES DURING CONSTRUCTION.
- ADJUST EXISTING SERVICE COVERS TO SUIT NEW FINISHED LEVELS TO RELEVANT AUTHORITY REQUIREMENTS WHERE NECESSARY.
- REINSTATE AND STABILISE ALL DISTURBED LANDSCAPED AREAS.
- MINIMUM GRADE OF SUBSOIL SHALL BE 0.5% (1:200) FALL TO OUTLETS.
- ALL TEMPORARY SEDIMENT AND EROSION CONTROL DEVICES ARE TO BE CONSTRUCTED, PLACED AND MAINTAINED IN ACCORDANCE WITH THE TECHNICAL SPECIFICATIONS, EROSION AND SEDIMENTATION CONTROL PLAN AND PENRITH COUNCIL'S REQUIREMENTS WHERE APPLICABLE.
- CONTRACTOR TO CHECK AND CONFIRM SITE DRAINAGE CONNECTIONS ACROSS THE VERGE PRIOR TO COMMENCEMENT OF SITE DRAINAGE WORKS.
- PROPERTIES AFFECTED BY THE WORKS ARE TO BE NOTIFIED IN ADVANCE WHERE DISRUPTION TO EXISTING ACCESS IS LIKELY.

EXISTING SERVICES & FEATURES

- THE CONTRACTOR SHALL ALLOW FOR THE CAPPING OFF, EXCAVATION AND REMOVAL (IF REQUIRED) OF ALL EXISTING SERVICES IN AREAS AFFECTED BY WORKS WITHIN THE CONTRACT AREA OR AS SHOWN ON THE DRAWINGS UNLESS DIRECTED OTHERWISE BY THE SUPERINTENDENT.
- THE CONTRACTOR SHALL ENSURE THAT AT ALL TIMES SERVICES TO ALL BUILDINGS NOT AFFECTED BY THE WORKS ARE NOT DISRUPTED.
- PRIOR TO COMMENCEMENT OF ANY WORKS THE CONTRACTOR SHALL GAIN APPROVAL OF HIS PROGRAM FOR THE RELOCATION/ CONSTRUCTION OF TEMPORARY SERVICES.
- CONTRACTOR SHALL CONSTRUCT TEMPORARY SERVICES TO MAINTAIN SUPPLY TO EXISTING BUILDING REMAINING IN OPERATION DURING WORKS TO THE SATISFACTION AND APPROVAL OF THE SUPERINTENDENT. ONCE DIVERSION IS COMPLETE AND COMMISSIONED, THE CONTRACTOR SHALL REMOVE ALL SUCH TEMPORARY SERVICES AND MAKE GOOD TO THE SATISFACTION OF THE SUPERINTENDENT.
- INTERRUPTION TO SUPPLY OF EXISTING SERVICES SHALL BE DONE SO AS NOT TO CAUSE ANY INCONVENIENCE TO THE PRINCIPAL. CONTRACTOR TO GAIN APPROVAL FROM THE SUPERINTENDENT FOR TIME OF INTERRUPTION.
- EXISTING SERVICES, BUILDINGS, EXTERNAL STRUCTURES AND TREES SHOWN ON THESE DRAWINGS ARE EXISTING FEATURES PRIOR TO ANY DEMOLITION WORKS.
- EXISTING SERVICES UNLESS SHOWN ON SURVEY PLAN HAVE BEEN PLOTTED FROM SERVICES SEARCH PLANS AND AS SUCH THEIR ACCURACY CANNOT BE GUARANTEED. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO COMPLETE A 'DIAL BEFORE YOU DIG' SEARCH AND TO ESTABLISH THE LOCATION AND LEVEL OF ALL EXISTING SERVICES PRIOR TO THE COMMENCEMENT OF ANY WORK. ANY DISCREPANCIES SHALL BE REPORTED TO THE SUPERINTENDENT. CLEARANCES SHALL BE OBTAINED FROM THE RELEVANT SERVICE AUTHORITY.
- ALL BRANCH GAS AND WATER SERVICES UNDER DRIVEWAYS AND BRICK PAVING SHALL BE LOCATED IN Ø80 uPVC SEWER GRADE CONDUITS EXTENDING A MINIMUM OF 500mm BEYOND EDGE OF PAVING.



LOCALITY SKETCH

SCALE: NTS

DRAWING SCHEDULE

NO.	DESCRIPTION
20G21_DA_C000	COVER SHEET, DRAWING SCHEDULE, NOTES AND LOCALITY SKETCH
20G21_DA_C100	GENERAL ARRANGEMENT PLAN
20G21_DA_C101	DETAIL PLAN, SHEET 1 OF 2
20G21_DA_C102	DETAIL PLAN, SHEET 2 OF 2
20G21_DA_C200	STORMWATER MISCELLANEOUS DETAILS AND PIT LID SCHEDULE
20G21_DA_SE01	SEDIMENT AND EROSION CONTROL PLAN
20G21_DA_SE02	SEDIMENT AND EROSION CONTROL DETAILS

SITWORKS NOTES



- DATUM : A.H.D.
- ORIGIN OF LEVELS : REFER TO BENCH OR STATE SURVEY MARKS WHERE SHOWN ON PLAN.
- CONTRACTOR MUST VERIFY ALL DIMENSIONS AND EXISTING LEVELS ON SITE PRIOR TO THE COMMENCEMENT OF WORK.
- ALL WORKS TO BE UNDERTAKEN IN ACCORDANCE WITH THE DETAILS SHOWN ON THE DRAWINGS & THE DIRECTIONS OF THE SUPERINTENDENT.
- EXISTING SERVICES UNLESS SHOWN ON THE SURVEY PLAN HAVE BEEN PLOTTED FROM SERVICES SEARCH PLANS AND AS SUCH THEIR ACCURACY CANNOT BE GUARANTEED. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO ESTABLISH THE LOCATION AND LEVEL OF ALL EXISTING SERVICES PRIOR TO THE COMMENCEMENT OF ANY WORK. ANY DISCREPANCIES SHALL BE REPORTED TO THE SUPERINTENDENT. CLEARANCES SHALL BE OBTAINED FROM THE RELEVANT SERVICE AUTHORITY.
- WHERE NEW WORKS ABUT EXISTING THE CONTRACTOR SHALL ENSURE THAT A SMOOTH EVEN PROFILE, FREE FROM ABRUPT CHANGES IS ACHIEVED.
- THE CONTRACTOR SHALL ARRANGE ALL SURVEY SETOUT TO BE CARRIED OUT BY A REGISTERED SURVEYOR.
- CARE IS TO BE TAKEN WHEN EXCAVATING NEAR EXISTING SERVICES. NO MECHANICAL EXCAVATION IS TO BE UNDERTAKEN OVER TELSTRA OR ELECTRICAL SERVICES. HAND EXCAVATE IN THESE AREAS.
- CONTRACTOR TO OBTAIN AUTHORITY APPROVALS WHERE APPLICABLE.
- MAKE SMOOTH TRANSITION TO EXISTING SURFACES AND MAKE GOOD.
- THESE PLANS SHALL BE READ IN CONJUNCTION WITH APPROVED LANDSCAPE, ARCHITECTURAL, STRUCTURAL, HYDRAULIC AND MECHANICAL DRAWINGS AND SPECIFICATIONS OR WRITTEN INSTRUCTIONS THAT MAY BE ISSUED RELATING TO DEVELOPMENT AT THE SITE.
- TRENCHES THROUGH EXISTING ROAD AND CONCRETE PAVEMENTS SHALL BE SAWCUT TO FULL DEPTH OF CONCRETE AND A MINIMUM OF 50mm IN BITUMINOUS PAVING.
- ALL BRANCH GAS AND WATER SERVICES UNDER DRIVEWAYS AND BRICK PAVING SHALL BE LOCATED IN Ø80 uPVC SEWER GRADE CONDUITS EXTENDING A MINIMUM OF 500mm BEYOND EDGE OF PAVING.
- GRADES TO PAVEMENTS TO BE AS IMPLIED BY RL'S ON PLAN. GRADE EVENLY BETWEEN NOMINATED RL'S. AREAS EXHIBITING PONDING GREATER THAN 5mm DEPTH WILL NOT BE ACCEPTED UNLESS IN A DESIGNATED SAG POINT.
- ALL COVERS AND GRATES ETC TO EXISTING SERVICE UTILITIES ARE TO BE ADJUSTED TO SUIT NEW FINISHED SURFACE LEVELS WHERE APPLICABLE.

SURVEY NOTES


THE EXISTING SITE CONDITIONS SHOWN ON THE FOLLOWING DRAWINGS HAVE BEEN INVESTIGATED BY THE SURVEYOR SPECIFIED IN THE TITLE BLOCK. THE INFORMATION IS SHOWN TO PROVIDE A BASIS FOR DESIGN. HENRY AND HYMAS PTY. LTD. DOES NOT GUARANTEE THE ACCURACY OR COMPLETENESS OF THE SURVEY BASE OR ITS SUITABILITY AS A BASIS FOR CONSTRUCTION DRAWINGS. SHOULD DISCREPANCIES BE ENCOUNTERED DURING CONSTRUCTION BETWEEN THE SURVEY DATA AND ACTUAL FIELD DATA, CONTACT HENRY AND HYMAS PTY. LTD. THE FOLLOWING NOTES HAVE BEEN TAKEN DIRECTLY FROM ORIGINAL SURVEY DOCUMENTS.

FOR DA ONLY



SURVEY INFORMATION		Client		Project		Drawn		Designed		Date	
SURVEYED BY REAL SERVE		HOME CO.		COMMERCIAL DEVELOPMENT		M.Cerna		T.Chan		DEC 20	
DATUM: AHD		Architect		243 FORRESTER RD, ST MARYS NSW		Checked		Approved		Scale: B/A1	
ORIGIN OF LEVELS: PM 41946		BUCHAN		Title		T.Rozejnal		A.Francis		1:500	
01 PRELIMINARY		This drawing and design remains the property of Henry & Hymas and may not be copied in whole or in part without the prior written approval of Henry & Hymas.		COVER SHEET, DRAWING SCHEDULE, NOTES AND LOCALITY SKETCH		Drawing number		Revision		20G21_DA_C000 01	
REVISION	AMENDMENT	MC	TC	11.12.2020							
		DRAWN	DESIGNED	DATE	AMENDMENT	DRAWN	DESIGNED	DATE			




GENERAL ARRANGEMENT PLAN
SCALE: 1:500



FOR DA ONLY

SURVEY INFORMATION SURVEYED BY REAL SERVE DATUM: AHD ORIGIN OF LEVELS: PM 41946				Client HOME CO. Architect BUCHAN				Suite 2.01 828 Pacific Highway Gordon NSW 2072 		Telephone +61 2 9417 8400 Facsimile +61 2 9417 8337 Email email@thiconsult.com.au Web www.henryandhymas.com.au 		Project COMMERCIAL DEVELOPMENT 243 FORRESTER RD, ST MARYS NSW Title GENERAL ARRANGEMENT PLAN		Drawn M.Cerna Checked T.Rozehnal Designated T.Chan Approved A.Francis Date DEC 20 Scale A1 1:500 Drawing number 20G21_DA_C100		Revision 01	
01	PRELIMINARY	MC	TC	11.12.2020													
	AMENDMENT																

Document Set ID: 9426370
Version: 1, Version Date: 23/12/2020



LEGEND

- EXISTING BOUNDARY
- PROPOSED JUNCTION PITS
- PROPOSED SURFACE INLET PITS
- PROPOSED GRATED DRAIN
- LINE LETTER
- PROPOSED PIT TAG
- STORMWATER UPSTREAM INVERT RL
- STORMWATER PIPE DIAMETER & CLASS
- STORMWATER PIPE LENGTH
- STORMWATER PIPE GRADE
- STORMWATER DOWNSTREAM INVERT RL
- PROPOSED STORMWATER PIPE
- EXISTING SPOT LEVEL
- PROPOSED SPOT LEVEL
- EXISTING STORMWATER PIT
- EXISTING STORMWATER PIPE
- PROPOSED RIDGE LINE
- PROPOSED VALLEY LINE
- PROPOSED RETAINING WALL
- OVERLAND FLOW PATH
- PROPOSED LIMIT OF WORK
- PROPOSED KERB ONLY



CONNECT TO EXISTING PIT. ENSURE SMOOTH CONNECTION

EXISTING RWT TO BE RELOCATED

EXTENT OF WORKS

TRANSITION FROM 150mm HIGH KERB TO FLUSH KERB


ADJUST EXISTING PIT TO SUIT NEW LEVELS CONVERT TO SEALED LID

PROPOSED WHEEL STOPS TO ARCH. DESIGN

CONNECT TO EXISTING PIT ENSURE SMOOTH CONNECTION

EXISTING DOWNPIPES INFRONT OF PROPOSED DRIVEWAY TO BE RELOCATED. REFER TO HYDRAULIC DRAWINGS FOR DETAILS.

DETAIL PLAN
SCALE: 1:200



REFER TO C102 DRAWING FOR CONTINUATION

FOR DA ONLY

REVISION	AMENDMENT	DRAWN	DESIGNED	DATE	REVISION	AMENDMENT	DRAWN	DESIGNED	DATE
01	PRELIMINARY	MC	TC	11.12.2020					

Client
HOME CO.

Architect
BUCHAN

This drawing and design remains the property of Henry & Hymas and may not be copied in whole or in part without the prior written approval of Henry & Hymas.

Suite 2.01
828 Pacific Highway
Gordon NSW 2072


Telephone
+61 2 9417 8400
Facsimile
+61 2 9417 8337
Email
email@hhconsult.com.au
Web
www.henryandhymas.com.au



Project
**COMMERCIAL DEVELOPMENT
243 FORRESTER RD, ST MARYS NSW**

Title
**DETAIL PLAN
SHEET 1 OF 2**

Drawn	Designed	Date
M.Cerna	T.Chan	DEC 20
Checked	Approved	Scale
T.Rozehnal	A.Francis	B/A1 1:200
Drawing number	Revision	
20G21_DA_C101	01	



- LEGEND**
- EXISTING BOUNDARY
 - PROPOSED JUNCTION PITS
 - PROPOSED SURFACE INLET PITS
 - PROPOSED GRATED DRAIN
 - PROPOSED PIT TAG
 - IL21.17 STORMWATER UPSTREAM INVERT RL
 - Ø100 uPVC STORMWATER PIPE DIAMETER & CLASS
 - 15m STORMWATER PIPE LENGTH
 - 1% STORMWATER PIPE GRADE
 - IL21.02 STORMWATER DOWNSTREAM INVERT RL
 - PROPOSED STORMWATER PIPE
 - EXISTING SPOT LEVEL
 - PROPOSED SPOT LEVEL
 - EXISTING STORMWATER PIT
 - EXISTING STORMWATER PIPE
 - PROPOSED RIDGE LINE
 - PROPOSED VALLEY LINE
 - PROPOSED RETAINING WALL
 - OVERLAND FLOW PATH
 - PROPOSED LIMIT OF WORK
 - PROPOSED KERB ONLY
 - PROPOSED KERB & GUTTER
 - PROPOSED FLUSH ONLY
 - PROPOSED RAINWATER OUTLET

DETAIL PLAN
SCALE: 1:200




FOR DA ONLY

<p>SURVEY INFORMATION SURVEYED BY REAL SERVE DATUM: AHD ORIGIN OF LEVELS: PM 41946</p>					<p>Client HOME CO.</p> <p>Architect BUCHAN</p>	<p>Suite 2.01 828 Pacific Highway Gordon NSW 2072</p> <p>Telephone +61 2 9417 8400 Facsimile +61 2 9417 8337 Email email@hthconsult.com.au Web www.henryandhymas.com.au</p>	<p>Project COMMERCIAL DEVELOPMENT 243 FORRESTER RD, ST MARYS NSW</p> <p>Title DETAIL PLAN SHEET 2 OF 2</p>	<p>Drawn M.Cerna</p> <p>Checked T.Rozehnal</p> <p>Drawing number 20G21_DA_C102</p>	<p>Designed T.Chan</p> <p>Approved A.Francis</p> <p>Scale @A1 1:200</p> <p>Revision 01</p>	<p>Date DEC 20</p>														
	<table border="1"> <thead> <tr> <th>REVISION</th> <th>AMENDMENT</th> <th>DRAWN</th> <th>DESIGNED</th> <th>DATE</th> <th>REVISION</th> <th>AMENDMENT</th> <th>DRAWN</th> <th>DESIGNED</th> <th>DATE</th> </tr> </thead> <tbody> <tr> <td>01</td> <td>PRELIMINARY</td> <td>MC</td> <td>TC</td> <td>11.12.2020</td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </tbody> </table>	REVISION	AMENDMENT	DRAWN	DESIGNED	DATE	REVISION	AMENDMENT	DRAWN	DESIGNED	DATE	01	PRELIMINARY	MC	TC	11.12.2020						<p>This drawing and design remains the property of Henry & Hymas and may not be copied in whole or in part without the prior written approval of Henry & Hymas.</p>		<p>henry&hymas</p>
REVISION	AMENDMENT	DRAWN	DESIGNED	DATE	REVISION	AMENDMENT	DRAWN	DESIGNED	DATE															
01	PRELIMINARY	MC	TC	11.12.2020																				

TYPICAL PIT CHAMBER SIZES
IT IS THE CONTRACTORS RESPONSIBILITY TO SELECT PIT CHAMBER SIZE WITH REGARDS TO PIPE SIZE, DEPTH TO INVERT AND SKEW ANGLE. REFER SKETCHES BELOW.

1. SELECT PIT CHAMBER USING THE STEPS BELOW.
2. SELECT PIT CHAMBER SIZE DEPENDING ON THE PIPE DIAMETERS.
3. CHECK PIT CHAMBER SIZE TO SATISFY DEPTH TO INVERT REQUIREMENTS.
4. CHECK PIT CHAMBER DIMENSIONS TO SATISFY THE SKEW ANGLE IN THE TABLE.

FOR B = 600mm - MAX. SIDE ENTRY PIPE AT 45° SKEW = 225mm
 FOR B = 900mm - MAX. SIDE ENTRY PIPE AT 45° SKEW = 375mm
 FOR B = 1200mm - MAX. SIDE ENTRY PIPE AT 45° SKEW = 600mm
 FOR B = 1500mm - MAX. SIDE ENTRY PIPE AT 45° SKEW = 825mm
 FOR B = 1900mm - MAX. SIDE ENTRY PIPE AT 45° SKEW = 1050mm




*A = 600 FOR PIPES UP TO 375 DIA.


1. PIT CHAMBER DIMENSIONS FOR PIPES UP TO 600 DIA.

2. PIT SIZE & DEPTH REQUIREMENTS

H = 0-900mm - Ax B = 600x600mm
 H = 900-1200mm - Ax B = 900x600mm
 H = >1200mm - Ax B = 900x900mm



3. PIT CHAMBER FOR SIDE ENTRY ON SKEW




HAUNCH DETAIL - TYPICAL
 SCALE 1:10

PIT LID SCHEDULE


PIT/STRUCTURE NUMBER	DESCRIPTION
(A-1) (A-2) (A-3) (A-4)	PROPOSED INLET PIT WITH 600x600 HINGED MEDIUM DUTY CLASS 'C' HEELPROOF LID IN ACCORDANCE WITH PENRITH CITY COUNCIL'S REQUIREMENT.
(B-1) (C-1)	PROPOSED INLET PIT WITH 600x600 HINGED LIGHT DUTY CLASS 'B' HEELPROOF/CHILDPROOF LID IN ACCORDANCE WITH PENRITH CITY COUNCIL'S REQUIREMENT.
(C-2) (C-3)	PROPOSED INLET PIT WITH 900x900 HINGED LIGHT DUTY CLASS 'B' HEELPROOF/CHILDPROOF LID IN ACCORDANCE WITH PENRITH CITY COUNCIL'S REQUIREMENT.

DRAINAGE NOTES:


1. ALL STORMWATER WORK TO COMPLY WITH AS 3500 PART 3.
2. CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING THE MINIMUM COVER OF 600mm ON ALL PIPES.
3. PROTECTION OF PIPES DUE TO LOADS EXCEEDING W7 WHEEL LOAD SHALL BE THE CONTRACTOR'S RESPONSIBILITY.
4. BEDDING TYPE SHALL BE TYPE H2 FOR RCP. WHERE NECESSARY THE OVERLAY ZONE SHALL BE REDUCED TO ACCOMMODATE PAVEMENT REQUIREMENTS. REFER TO THIS DRAWING FOR DETAILS.
5. MINIMUM COVER OVER EXISTING PIPES FOR PROTECTION DURING CONSTRUCTION SHALL BE 800mm.
6. NO CONSTRUCTION LOADS SHALL BE APPLIED TO PLASTIC PIPES.
7. FINISHED SURFACE LEVELS SHOWN ON LAYOUT PLAN DRGS TAKE PRECEDENCE OVER DESIGN DRAINAGE SURFACE LEVELS.
8. ALL PIPES UP TO AND INCLUDING 300 DIA. SHALL BE SOLVENT OR RUBBER RING JOINTED PVC CLASS SH PIPE TO AS1260. ALL OTHER PIPES TO BE RCP USING CLASS 2 RUBBER RING JOINTED PIPE. HARDIES FRC PIPE MAY BE USED IN LIEU OF RCP IF DESIRED IN GROUND. ALL AERIAL PIPES TO BE PVC CLASS SH.
9. ALL PITS IN NON TRAFFICABLE AREAS TO BE PREFABRICATED POLYESTER CONCRETE 'POLYCRETE' WITH 'LIGHT DUTY' CLASS B GALV. MILD STEEL GRATING AND FRAME. ALL PITS IN TRAFFICABLE AREAS (CLASS 'D' LOADING MAX) TO HAVE 150mm THICK CONCRETE WALLS AND BASE CAST IN-SITU $f_c=32$ MPa. REINFORCED WITH N12-200 BOTH LOADING WAYS CENTRALLY PLACE U.N.O. ON SEPARATE DESIGN DRAWINGS IN THIS SET. GALV. MILD STEEL GRATING AND FRAME TO SUIT DESIGN LOADING. PRECAST PITS, RECTANGULAR OR CIRCULAR IN SHAPE, MAY BE USED IN LIEU AND SHALL COMPLY WITH RELEVANT AUSTRALIAN STANDARDS.
10. ALL PITS, GRATINGS AND FRAMES SHALL BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURERS SPECIFICATION AND TO BE IN ACCORDANCE WITH AS3500.3 AND AS3996.
11. PIT CHAMBER DIMENSIONS ARE TO BE SELECTED TO SATISFY THE FOLLOWING:
 - PIPE SIZE
 - DEPTH TO INVERT
 - SKEW ANGLE
 REFER TYPICAL PIT CHAMBER DETAILS BELOW
 IF PIT LID SIZE IS SMALLER THAN THE PIT CHAMBER SIZE THEN THE PIT LID IS TO BE CONSTRUCTED ON THE CORNER OF THE PIT CHAMBER WITH THE STEP IRONS DIRECTLY BELOW. ALTERNATIVELY THE PIT LID TO BE USED, IS TO BE THE SAME SIZE AS THE PIT CHAMBER.
12. FOR PIPE SIZES GREATER THAN Ø300mm, PIT FLOOR IS TO BE BENCHED TO FACILITATE FLOW.
13. GALVANISED STEP IRONS SHALL BE PROVIDED AT 300 CTS FOR PITS HAVING A DEPTH EXCEEDING 1200mm. SUBSOIL DRAINAGE PIPE SHALL BE PROVIDED IN PIPE TRENCHES ADJACENT TO INLET PIPES. (MINIMUM LENGTH 3m).
14. ALL SUBSOIL PIPES SHALL BE 100mm SLOTTED PVC IN A FILTER SOCK, UNO, WITH 3m INSTALLED UPSTREAM OF ALL PITS.
15. ALL PIPEWORK SHALL HAVE MINIMUM DIAMETER 100.
16. MINIMUM GRADE FOR ROOFWATER DRAINAGE LINES SHALL BE 1%.
17. ALL PIPE JUNCTIONS AND TAPER UP TO AND INCLUDING 300 DIA. SHALL BE VIA PURPOSE MADE FITTINGS.
18. ALL ROOF DRAINAGE TO BE INSTALLED IN ACCORDANCE WITH AS3500, PART 3. TESTING TO BE UNDERTAKEN AND REPORTS PROVIDED TO THE SUPERINTENDENT.
19. LOCATION OF THE DIRECT DOWN PIPE CONNECTIONS MAY VARY ON SITE TO SUIT SITE CONDITIONS, WHERE CONNECTION SHOWN ON LONG SECTIONS CHAINAGES ARE INDICATIVE ONLY.
20. PITS IN EXCESS OF 1.5 m DEEP TO HAVE WALL AND FLOOR THICKNESS INCREASED TO 200mm. REINFORCED WITH N12@200 CTS CENTRALLY PLACED BOTH WAYS THROUGHOUT U.N.O. ON SEPARATE DESIGN DRAWINGS IN THIS SET. IF DEPTH EXCEEDS 5m CONTACT ENGINEER.
21. SUBSOIL DRAINAGE LINES FOR LANDSCAPE AREA NOT SHOWN ON THESE DRAWINGS. REFER TO LANDSCAPING PLANS FOR DETAILS.
22. ALL STORMWATER PITS TO HAVE Ø100 uPVC SLOTTED SUBSOIL PIPES CONNECTED TO THEM. THESE SUBSOILS TO EXTEND 3m UPSTREAM OF THE PIT AT A MINIMUM GRADE.




INTERMEDIATE RISER (IR)
 SCALE 1:10
 NOTE: SLOTTED RIGID PVC PIPE AND FITTINGS MAY BE USED




FLUSHING POINT (FP)
 SCALE 1:10
 NOTE: SLOTTED RIGID PVC PIPE AND FITTINGS MAY BE USED




PIPE TRENCH INSTALLATION BENEATH PAVEMENT
 (H1 & H2 SUPPORT)
 SCALE 1:20



PIPE TRENCH INSTALLATION IN LANDSCAPE AREAS
 (H1 & H2 SUPPORT)
 SCALE 1:20




TYPICAL STEP IRON DETAIL
 SCALE 1:10






FOR DA ONLY

SURVEY INFORMATION SURVEYED BY REAL SERVE DATUM: AHD ORIGIN OF LEVELS: PM 41946					Client HOME CO.	Suite 2.01 828 Pacific Highway Gordon NSW 2072	Telephone +61 2 9417 8400 Facsimile +61 2 9417 8337 Email email@hhconsult.com.au Web www.henryandhymas.com.au		Project COMMERCIAL DEVELOPMENT 243 FORRESTER RD, ST MARYS NSW	Drawn M.Cerna	Designed T.Chan	Date DEC 20
					Architect BUCHAN		Title COVER SHEET, DRAWING SCHEDULE, NOTES AND LOCALITY SKETCH		Checked T.Rozehnal	Approved A.Francis	Scale @A1 1:500	Drawing number 20G21_DA_C200



**SEDIMENT AND EROSION CONTROL PLAN-
INSET A**
SCALE: 1:200





**SEDIMENT AND EROSION CONTROL PLAN-
INSET B**
SCALE: 1:200



FOR DA ONLY


SURVEY INFORMATION SURVEYED BY REAL SERVE DATUM: AHD ORIGIN OF LEVELS: PM 41946				Client HOME CO. Architect BUCHAN				Suite 2.01 828 Pacific Highway Gordon NSW 2072 Telephone +61 2 9417 8400 Facsimile +61 2 9417 8337 Email email@thiconsult.com.au Web www.henrydhymas.com.au				Project COMMERCIAL DEVELOPMENT 243 FORRESTER RD, SANTA MARYS NSW		Drawn M.Cerna Checked T.Rozehnal		Designed T.Chan Approved A.Francis		Date DEC 20 Scale @A1 1:200	
Title SEDIMENT AND EROSION CONTROL PLAN		Drawing number 20G21_DA_SE01		Revision 01		This drawing and design remains the property of Henry & Hymas and may not be copied in whole or in part without the prior written approval of Henry & Hymas.													
01	PRELIMINARY	MC	TC	11.12.2020	REVISION	AMENDMENT	AMENDMENT	AMENDMENT	AMENDMENT	AMENDMENT	AMENDMENT	AMENDMENT	AMENDMENT	AMENDMENT	AMENDMENT	AMENDMENT			




SEDIMENT/SECURITY FENCE
SCALE N.T.S.

SEDIMENT FENCE CONSTRUCTION NOTES:

1. CONSTRUCT SEDIMENT FENCES AS CLOSE AS POSSIBLE TO BEING PARALLEL TO THE CONTOURS OF THE SITE, BUT WITH SMALL RETURNS AS SHOWN IN THE DRAWING TO LIMIT THE CATCHMENT AREA OF ANY ONE SECTION. THE CATCHMENT AREA SHOULD BE SMALL ENOUGH TO LIMIT WATER FLOW IF CONCENTRATED AT ONE POINT TO 50 LITRES PER SECOND IN THE DESIGN STORM EVENT, USUALLY THE 10-YEAR EVENT.
2. CUT A 150mm DEEP TRENCH ALONG THE UPSLOPE LINE OF THE FENCE FOR THE BOTTOM OF THE FABRIC TO BE ENTRENCHED.
3. DRIVE 1.5m LONG STAR PICKETS INTO GROUND @ 2.5m INTERVALS (MAX.) AT THE DOWNSLOPE EDGE OF THE TRENCH. ENSURE ANY STAR PICKETS ARE FITTED WITH SAFETY CAPS.
4. FIX SELF-SUPPORTING GEOTEXTILE TO THE UPSLOPE SIDE OF THE POSTS ENSURING IT GOES TO THE BASE OF THE TRENCH. FIX THE GEOTEXTILE WITH WIRE TIES OR AS RECOMMENDED BY THE MANUFACTURER. ONLY USE GEOTEXTILE SPECIFICALLY PRODUCED FOR SEDIMENT FENCING. THE USE OF SHADE CLOTH FOR THIS PURPOSE IS NOT SATISFACTORY.
5. JOIN SECTIONS OF FABRIC AT A SUPPORT POST WITH A 150mm OVERLAP. 6. BACKFILL THE TRENCH OVER THE BASE OF THE FABRIC AND COMPACT IT THOROUGHLY OVER THE GEOTEXTILE.



SECTION DETAIL



MESH & GRAVEL INLET FILTER CONSTRUCTION NOTES:

1. FABRICATE A SLEEVE MADE FROM GEOTEXTILE OR WIRE MESH LONGER THAN THE LENGTH OF THE INLET PIT AND FILL IT WITH 25mm TO 50mm GRAVEL.
2. FORM AN ELLIPTICAL CROSS-SECTION ABOUT 150mm HIGH x 400mm WIDE.
3. PLACE THE FILTER AT THE OPENING LEAVING AT LEAST A 100mm SPACE BETWEEN IT AND THE KERB INLET. MAINTAIN THE OPENING WITH SPACER BLOCKS.
4. FORM A SEAL WITH THE KERB TO PREVENT SEDIMENT BYPASSING THE FILTER.
5. SANDBAGS FILLED WITH GRAVEL CAN SUBSTITUTE FOR THE MESH OR GEOTEXTILE PROVIDING THEY ARE PLACED SO THAT THEY CAN FIRMLY ABUT EACH OTHER AND SEDIMENT / LADEN WATERS CANNOT PASS BETWEEN.

MESH & GRAVEL INLET FILTER

SCALE N.T.S.

SEDIMENT & EROSION CONTROL NOTES

- ALL SEDIMENT CONTROL DEVICES ARE TO BE CONSTRUCTED, PLACED AND MAINTAINED IN ACCORDANCE PENRITH CITY COUNCIL COUNCIL'S SPECIFICATIONS AND LANDCOM'S 'SOIL AND CONSTRUCTION' MANUAL.
- ALL PERIMETER & SILTATION CONTROL MEASURES ARE TO BE PLACED PRIOR TO, OR AS THE FIRST STEP IN EARTH WORKS AND/OR CLEARING.
- THE SEDIMENT & EROSION CONTROL PLAN MAY REQUIRE FUTURE ADJUSTMENT TO REFLECT CONSTRUCTION STAGING. IT IS ALSO THE CONTRACTORS RESPONSIBILITY TO PREPARE THEIR OWN SEDIMENT AND EROSION CONTROL PLAN WHICH SUITS THE DESIGNED CONSTRUCTION STAGING.
- FILTRATION BUFFER ZONES ARE TO BE FENCED OFF AND ACCESS PROHIBITED TO ALL PLANT AND MACHINERY.
- ALL TEMPORARY EARTH BERMS, DIVERSIONS & SILT DAM EMBANKMENTS ARE TO BE MACHINE COMPACTED, SEEDED & MULCHED FOR TEMPORARY VEGETATION COVER AS SOON AS THEY HAVE BEEN FORMED.
- ALL SEDIMENT TRAPPING STRUCTURES AND DEVICES ARE TO BE INSPECTED AFTER STORMS FOR STRUCTURAL DAMAGE OR CLOGGING. TRAPPED MATERIAL IS TO BE REMOVED TO A SAFE LOCATION.
- ALL TOPSOIL IS TO BE STOCKPILED ON SITE FOR REUSE (AWAY FROM TREES AND DRAINAGE LINES). MEASURES SHALL BE APPLIED TO PREVENT EROSION OF THE STOCKPILES.
- ALL EARTHWORK AREAS SHALL BE ROLLED EACH EVENING TO SEAL THE EARTHWORKS.
- ALL FILLS ARE TO BE LEFT WITH A LIP AT THE TOP OF THE SLOPE AT THE END. ALL CUT AND FILL SLOPES ARE TO BE SEEDED AND STRAW MULCHED WITHIN 14 DAYS OF COMPLETION OF FORMATION U.N.O. BY LANDSCAPE ARCHITECTS.
- UPON COMPLETION OF ALL EARTHWORKS OR AS DIRECTED BY COUNCIL SOIL CONSERVATION TREATMENTS SHALL BE APPLIED SO AS TO RENDER AREAS THAT HAVE BEEN DISTURBED, EROSION PROOF WITHIN 14 DAYS.
- EROSION AND SILT PROTECTION MEASURES ARE TO BE MAINTAINED AT ALL TIMES.
- THESE DRAWINGS SHOW THE INITIAL STAGES OF THE SITE CONSTRUCTION AND EROSION CONTROLS. AS CONSTRUCTION CONTINUES IT IS THE CONTRACTOR'S RESPONSIBILITY TO ENSURE THAT ALL PITS ARE PROGRESSIVELY FITTED WITH MESH AND GRAVEL INLET FILTERS AS REQUIRED.
- ALL EXISTING COUNCIL PITS WITHIN 50m OF THE SITE BOUNDARIES ARE TO BE FITTED WITH MESH AND GRAVEL INLET FILTERS.

FOR DA ONLY

<p>SURVEY INFORMATION SURVEYED BY REAL SERVE DATUM: AHD ORIGIN OF LEVELS: PM 41946</p>											<p>Client HOME CO.</p> <p>Architect BUCHAN</p>	<p>Suite 2.01 828 Pacific Highway Gordon NSW 2072</p> <p>Telephone +61 2 9417 8400 Facsimile +61 2 9417 8337 Email email@thconsult.com.au Web www.henryandhymas.com.au</p>		<p>Project COMMERCIAL DEVELOPMENT 243 FORRESTER RD, SANTA MARYS NSW</p> <p>Title SEDIMENT AND EROSION CONTROL DETAILS</p>	<p>Drawn M.Cerna</p> <p>Checked T.Rozezmal</p> <p>Design T.Chan</p> <p>Approved A.Francis</p> <p>Date DEC 20</p> <p>Scale B/A1</p> <p>NTS</p>	<p>Revision</p>																
	<table border="1"> <thead> <tr> <th>01</th> <th>DESCRIPTION</th> <th>INITIALS</th> <th>INITIALS</th> <th>DATE</th> </tr> <tr> <th>REVISION</th> <th>AMENDMENT</th> <th>DRAWN</th> <th>DESIGNED</th> <th>DATE</th> </tr> </thead> <tbody> <tr> <td> </td> <td> </td> <td> </td> <td> </td> <td> </td> </tr> <tr> <td> </td> <td> </td> <td> </td> <td> </td> <td> </td> </tr> </tbody> </table>	01	DESCRIPTION	INITIALS	INITIALS	DATE	REVISION	AMENDMENT	DRAWN	DESIGNED	DATE											<p>This drawing and design remains the property of Henry & Hymas and may not be copied in whole or in part without the prior written approval of Henry & Hymas.</p>										<p>Drawing number 20G21_DA_SE02</p>
01	DESCRIPTION	INITIALS	INITIALS	DATE																												
REVISION	AMENDMENT	DRAWN	DESIGNED	DATE																												