

CONCEPT STORMWATER DRAWINGS FOR 170 DERBY STREET, PENRITH NSW 2750

SYMBOLS

RL	PIT SURFACE LEVEL
IL	INVERT LEVEL
TK	TOP OF KERB
B.O.W	BOTTOM OF WALL
T.O.W	TOP OF WALL
	STORMWATER DRAINAGE PIPE
	DOWNPIPE TO RAINWATER TANK
	OVERFLOW PIPE FROM RAINWATER TANK
	Ø100 SUBSOIL PIPE
	Ø100 SUBSOIL PIPE
	FLOOR WASTE 150X150
	FLOOR WASTE 150Ø
	RAINWATER OUTLET 300Ø
	PLANTER GRATE
	DOWN PIPE
	CLEAN OUT
	INSPECTION OPENING
	VERTICAL DROP
	VERTICAL RISER
	CONCRETE COVER JUNCTION PIT
	GRATED INLET PIT
	WIDE GRATED DRAIN
	OVERLAND FLOW PATH
	CAST IN SLAB PIPE

NOTES

- ALL LINES ARE TO BE MIN. 100Ø UPVC @ MIN 1.0% GRADE UNLESS NOTED OTHERWISE.
- IT IS THE CONTRACTORS RESPONSIBILITY TO LOCATE & LEVEL ALL EXISTING SERVICES PRIOR TO THE COMMENCEMENT OF ANY EARTHWORKS. ALL DESIGN LEVELS SHOWN ON PLAN SHALL BE VERIFIED ON SITE PRIOR TO THE COMMENCEMENT OF ANY WORK.
- ALL PIPES TO HAVE MIN 200mm COVER IF LOCATED WITHIN PROPERTY.
- ALL PITS IN DRIVEWAYS BE HEAVY DUTY GRATES. DIRECT SURFACE FLOW TO ALL GRATED SURFACE INLET PITS.
- ALL WORK DO BE DONE IN ACCORDANCE WITH AS/NZ 3500.3 (CURRENT EDITION) AND COUNCIL SPECIFICATIONS.
- LOCATION OF DOWNPIPES & FLOOR WASTES ARE INDICATIVE ONLY. DOWNPIPE & FLOOR WASTE SIZE, LOCATION & QUANTITY TO BE DETERMINED BY BUILDER & IN ACCORDANCE WITH RELEVANT AUSTRALIAN STANDARDS.
- THIS PLAN IS TO BE READ IN CONJUNCTION WITH THE ARCHITECTURAL, LANDSCAPE AND STRUCTURAL AND ALL OTHER RELEVANT CONSULTANT'S PLANS.
- ALL RAINWATER TANKS TO BE FITTED WITH A FIRST FLUSH DEVICE TO PREVENT POTENTIAL CONTAMINANTS FROM ENTERING THE TANKS.
- ANY DISCREPANCIES OR OMISSIONS SHALL BE REFERRED TO THE DESIGN ENGINEER FOR RESOLUTION.
- ALL PITS OR GRATES IN TRAFFICABLE AREAS TO BE HEAVY DUTY.
- ALL GUTTERS WILL BE FITTED WITH LEAF GUARDS AND SHOULD BE INSPECTED AND CLEANED TO ENSURE LEAF LITTER CANNOT ENTER THE DOWNPIPES
- PROVIDE EMERGENCY OVERFLOW TO ALL PLANTER BOX AND BALCONIES.
- ALL PITS WITH DEPTH MORE THAN 1M MUST HAVE IRON STEPS AND TO BE BENCHED AND STREAMLINED
- PROVIDE STORMWATER GRATE 200Wx200D AT THE BASE OF ALL MECHANICAL SHAFTS AND UNCOVERED STAIRS OR OPENINGS.
- ENSURE ALL DRAINAGE WORKS ARE AWAY FROM TREE ROOTS
- SERVICES SHOWN ON THESE PLANS HAVE BEEN LOCATED FROM INFORMATION SUPPLIED BY THE RELEVANT AUTHORITIES AND FIELD INVESTIGATION AND ARE NOT GUARANTEED COMPLETE NOR CORRECT. IT IS THE CLIENT AND CONTRACTOR'S RESPONSIBILITY TO LOCATE ALL PRIOR TO CONSTRUCTION.
- ALL VARIATIONS TO THE WORKS AS SHOWN ON THE APPROVED DRAWINGS ARE TO BE CONFIRMED BY SMART STRUCTURES AUSTRALIA PRIOR TO COMMENCEMENT OF WORKS.
- THE MINIMUM SIZES OF THE STORMWATER DRAINS SHALL NOT BE LESS THAN DN80 FOR CLASS 1 BUILDINGS AND DN100 FOR OTHER CLASSES OF BUILDING OR AS REQUIRED BY THE REGULATORY AUTHORITY

AS 3500.3- TABLE 8.2
SIZE OF MINIMUM INTERNAL DIMENSIONS
FOR STORMWATER AND INLET PITS


DEPTH OF INVERT OF OUTLET	MINIMUM INTERNAL DIMENSIONS (mm)		
	RECTANGULAR WIDTH	RECTANGULAR LENGTH	CIRCULAR DIAMETER
≤600	450	450	600
>600 ≤900	600	600	900
>900 ≤1200	600	900	1000
>1200	900	900	1000

DRAWING LIST	
DRAWING NUMBER	DRAWING NAME
D00	COVER SHEET, LEGEND & DRAWING SCHEDULE
D01	BASEMENT STORMWATER DRAINAGE PLAN
D02	GROUND FLOOR STORMWATER DRAINAGE PLAN
D03	FIRST FLOOR STORMWATER DRAINAGE PLAN
D04	ROOF STORMWATER DRAINAGE PLAN
D05	STORMWATER DRAINAGE SECTIONS AND DETAILS SHEET 1
D06	STORMWATER DRAINAGE SECTIONS AND DETAILS SHEET 2
D07	PRE & POST DEVELOPMENT CATCHMENT ANALYSIS AND MUSIC MODEL RESULTS
D08	CALCULATIONS SHEET
D10	EROSION AND SEDIMENT CONTROL PLAN AND DETAILS SHEET 1
D11	EROSION AND SEDIMENT CONTROL PLAN AND DETAILS SHEET 2



IMPORTANT:
CONTRACTOR TO OBTAIN CURRENT SET OF "DIAL BEFORE YOU DIG" PLANS ON SITE ALL TIMES AND PRIOR TO CONSTRUCTION WORKS

SCALE BARS



CLIENT:

MONTESSORI ACADEMY

ARCHITECT:

CULLEN FENG ARCHITECTS



SUIT 2.04, L2, BLDG 3,
35 WATERLOO RD., MACQUARIE PARK, NSW, 2113
info@smartstrucs.com.au | www.smartstrucs.com.au

DRAWING TITLE

COVER SHEET, LEGEND & DRAWING SCHEDULE

PROJECT
170 DERBY STREET, PENRITH
NSW 2750

SHEET NO.
D00

REV.
A

SCALE @ A1
NTS

NORTH

PROJECT NO.
200325

DESIGNED:
K.E.


DRAWN:
J.E.

AUTHORISED:
K.E.

PROJECT START DATE:
SEPTEMBER 2020


No.	Description	Date	Issued by	Checked by
A	ISSUED FOR D.A.	07.12.20	J.E.	K.E.

A B C D E F G H



BASEMENT STORMWATER DRAINAGE PLAN
SCALE 1: 100

No.	Description	Date	Issued by	Checked by
A	ISSUED FOR D.A.	07.12.20	J.E.	K.E.




CLIENT: **MONTESSORI ACADEMY**

ARCHITECT: **CULLEN FENG ARCHITECTS**

SMART STRUCTURES AUSTRALIA


SUIT 2.04, L2, BLDG 3,
35 WATERLOO RD., MACQUARIE PARK, NSW, 2113
info@smartstrucs.com.au | www.smartstrucs.com.au

DRAWING TITLE BASEMENT STORMWATER DRAINAGE PLAN		PROJECT 170 DERBY STREET, PENRITH NSW 2750	
SHEET NO. D01	REV. A	SCALE @ A1 AS SHOWN	NORTH
DESIGNED: K.E.	DRAWN: J.E.	AUTHORISED: K.E.	PROJECT NO. 200325
			PROJECT START DATE: SEPTEMBER 2020



GROUND FLOOR STORMWATER DRAINAGE
SCALE 1: 100

No.	Description	Date	Issued by	Checked by
A	ISSUED FOR D.A.	07.12.20	J.E.	K.E.




CLIENT: **MONTESSORI ACADEMY**

ARCHITECT: **CULLEN FENG ARCHITECTS**

SMART STRUCTURES AUSTRALIA

SUIT 2.04, L2, BLDG 3,
35 WATERLOO RD., MACQUARIE PARK, NSW, 2113
info@smartstructs.com.au | www.smartstructs.com.au


DRAWING TITLE GROUND FLOOR STORMWATER DRAINAGE PLAN		PROJECT 170 DERBY STREET, PENRITH NSW 2750	
SHEET NO. D02	REV. A	SCALE @ A1 AS SHOWN	NORTH
DESIGNED: K.E.	DRAWN: J.E.	AUTHORISED: K.E.	PROJECT NO. 200325
			PROJECT START DATE: SEPTEMBER 2020



RWT
 TWL 43.30
 AREA = 3.60m²
 AVERAGE DEPTH = 2.80m
 VOLUME PROVIDED = 10.08m³
 VOLUME REQUIRED = 10.00m³

FIRST FLOOR STORMWATER DRAINAGE PLAN
 SCALE 1:100

A No.	ISSUED FOR D.A.	Date	Issued by	Checked by
		07.12.20	J.E.	K.E.




CLIENT:
MONTESSORI ACADEMY

ARCHITECT:
CULLEN FENG ARCHITECTS

SMART STRUCTURES AUSTRALIA


SUIT 2.04, L2, BLDG 3,
 35 WATERLOO RD., MACQUARIE PARK, NSW, 2113
 info@smartstructs.com.au | www.smartstructs.com.au

DRAWING TITLE FIRST FLOOR STORMWATER DRAINAGE PLAN			PROJECT 170 DERBY STREET, PENRITH NSW 2750	
SHEET NO. D03	REV. A	SCALE @ A1 AS SHOWN	NORTH	
DESIGNED: K.E.	DRAWN: J.E.	AUTHORISED: K.E.	PROJECT NO. 200325	
			PROJECT START DATE: SEPTEMBER 2020	



ROOF STORMWATER DRAINAGE PLAN
SCALE 1: 100

No.	Description	Date	Issued by	Checked by
A	ISSUED FOR D.A.	07.12.20	J.E.	K.E.



CLIENT:
MONTESSORI ACADEMY

ARCHITECT:
CULLEN FENG ARCHITECTS

SMART STRUCTURES AUSTRALIA

SUIT 2.04, L2, BLDG 3,
35 WATERLOO RD., MACQUARIE PARK, NSW, 2113
info@smartstructs.com.au | www.smartstructs.com.au


DRAWING TITLE ROOF STORMWATER DRAINAGE PLAN		PROJECT 170 DERBY STREET, PENRITH NSW 2750	
SHEET NO. D04	REV. A	SCALE @ A1 AS SHOWN	NORTH
DESIGNED: K.E.	DRAWN: J.E.	AUTHORISED: K.E.	PROJECT NO. 200325
			PROJECT START DATE: SEPTEMBER 2020

PUMP SPECIFICATIONS

STANDARD PUMP-OUT NOTES

THE PUMP-OUT SYSTEM IS DESIGNED TO WORK IN THE FOLLOWING MANNER -

- A LOW LEVEL FLOAT SHALL BE PROVIDED TO ENSURE THAT THE MINIMUM REQUIRED WATER LEVEL IS MAINTAINED WITHIN THE SUMP AREA OF THE BELOW GROUND TANK. IN THIS REGARD THIS FLOAT WILL FUNCTION AS AN OFF SWITCH FOR THE PUMP.
- A SECOND FLOAT SHALL BE PROVIDED AT A HIGHER LEVEL, APPROXIMATELY 300mm ABOVE THE MINIMUM WATER LEVEL, WHEREBY THE PUMP WILL OPERATE & DRAIN THE TANK TO THE LEVEL OF THE LOW LEVEL FLOAT.
- A THIRD FLOAT SHALL BE PROVIDED AT A HIGH LEVEL, WHICH IS APPROXIMATELY THE ROOF LEVEL OF THE BELOW GROUND TANK. THIS FLOAT SHOULD ACTIVATE THE ALARM.
- AN ALARM SYSTEM SHALL BE PROVIDED WITH A FLASHING STROBE LIGHT & A PUMP FAILURE WARNING SIGN WHICH ARE TO BE LOCATED AT THE DRIVEWAY ENTRANCE TO THE BASEMENT LEVEL. THE ALARM SYSTEM SHALL BE PROVIDED WITH A BATTERY BACK-UP IN CASE OF POWER FAILURE.




PUMP WELL DETAILS
 AREA DRAINING TO SUMP = 89.05m²
 VOLUME BASED ON 100 YEAR ARI 2 HOUR INTENSITY
 INTENSITY = 41.8mm/hr
 $Q = 1 \times 41.8 \text{ mm/hr} \times 89.05 \text{ m}^2 / 3600 = 1.03 \text{ L/s}$
 VOLUME REQUIRED = $1.03 \times (60 \times 60 \times 2) = 7.42 \text{ m}^3$
 STORAGE PROVIDED $3.00 \times 2.50 \times 1.00 \text{ m} = 7.50 \text{ m}^3$


PUMP OUT RATE BASED ON 100 YEAR ARI 5 MIN
 INTENSITY = 243mm/hr
 $Q = 1 \times 243 \times 89.05 / 3600 = 6.01 \text{ L/s}$
 MIN. PUMP OUT RATE REQUIRED BY AS 3500.3 = 10.0 L/sec

DUAL KS-20 PUMP OR EQUIVALENT TO BE INSTALLED IN SUMP AND CONNECTED TO CONTROL PANEL WHICH WILL ALLOW FOR THE PUMPS TO OPERATE SIMULTANEOUSLY ON HIGH LEVEL ALARMS AT 5.0L/sec (PER PUMP) AT 4.60m HEAD


Type	Output		Outlet		Rated		Maximum		Weigh	Dimension		
	HP	kW	mm	Inch	Head	Capacity	Head	Capacity		L(mm)	W(mm)	H(mm)
KS-03	1/3	0.25	40	1 1/2"	3	130	8	180	9	188	141	305
KS-04	1/2	0.4	50	2"	5	150	8	220	11	208	140	359
KS-05	1/2	0.4	50	2"	5	160	10	260	14	230	156	375
KS-08	1	0.75	50	2"	6	240	13	380	21	290	180	425
KS-20	2	1.5	80	3"	10	300	16	600	31	278	182	475
KS-30	3	2.2	80	3"	10	500	18	800	42	390	250	450
KS-50	5	3.7	100	4"	10	800	21	1100	48	450	240	530
KS-75	7 1/2	5.6	100	4"	15	800	23	1300	60	550	310	590
KS-100	10	7.5	150	6"	18	900	25	1600	70	550	310	610




PUMP OUT PIT PLAN VIEW
SCALE NTS




RAINWATER TANK PLAN VIEW
SCALE NTS




SECTION THROUGH PUMP OUT PIT (A)
SCALE NTS




SECTION THROUGH RAINWATER TANK (B)
SCALE NTS




DETAIL
GRATED TRENCH DRAIN
SCALE NTS




DETAIL
STORMWATER PIT
SCALE NTS




SIDE ELEVATION
SCALE NTS



FRONT ELEVATION
SCALE NTS




PLAN VIEW
SCALE NTS



PLAN WITHOUT GRATE

STEP IRON DETAIL

SCALE NTS
NOTE: INSTALL WHERE PITS ARE DEEPER THAN 900




CLIENT: MONTESSORI ACADEMY
 ARCHITECT: CULLEN FENG ARCHITECTS



SMART STRUCTURES AUSTRALIA
 SUIT 2.04, L2, BLDG 3,
 35 WATERLOO RD., MACQUARIE PARK, NSW, 2113
 info@smartstrucs.com.au | www.smartstrucs.com.au

DRAWING TITLE STORMWATER DRAINAGE SECTIONS AND DETAILS SHEET 1		PROJECT 170 DERBY STREET, PENRITH NSW 2750	
SHEET NO. D05	REV. A	SCALE @ A1 AS SHOWN	NORTH
DESIGNED: K.E.	DRAWN: J.E.	AUTHORISED: K.E.	PROJECT NO. 200325
			PROJECT START DATE: SEPTEMBER 2020

OSD DESIGN NOTE:
 BASED ON PENRITH COUNCIL'S ON-SITE STORMWATER DETENTION TECHNICAL SPECIFICATION AN OSD SYSTEM IS REQUIRED FOR THE PROPOSED DEVELOPMENT REFER CALCULATIONS SHEET ON DWG D08 FOR FURTHER DETAILS.




OSD TANK PLAN VIEW
 SCALE NTS



OSD
 TWL 40.20
 AREA = 26.40m² + 8.10m²
 AVERAGE DEPTH = 0.66m, 0.50m
 VOLUME PROVIDED = 17.42m³ + 4.05m³ = 21.47
 VOLUME REQUIRED = 21.00m³


SECTION THROUGH OSD TANK C
 SCALE NTS



OSD
 TWL 40.20
 AREA = 26.40m² + 8.10m²
 AVERAGE DEPTH = 0.66m, 0.50m
 VOLUME PROVIDED = 17.42m³ + 4.05m³ = 21.47
 VOLUME REQUIRED = 21.00m³

SECTION THROUGH OSD TANK D
 SCALE NTS


No.	Description	Date	Issued by	Checked by
A	ISSUED FOR D.A.	07.12.20	J.E.	K.E.



CLIENT: MONTESSORI ACADEMY
 ARCHITECT: CULLEN FENG ARCHITECTS

SMART STRUCTURES AUSTRALIA
 SUIT 2.04, L2, BLDG 3,
 35 WATERLOO RD., MACQUARIE PARK, NSW, 2113
 info@smartstrucs.com.au | www.smartstrucs.com.au


DRAWING TITLE STORMWATER DRAINAGE SECTIONS AND DETAILS SHEET 2			PROJECT 170 DERBY STREET, PENRITH NSW 2750	
SHEET NO. D06	REV. A	SCALE @ A1 AS SHOWN	NORTH	PROJECT NO. 200325
DESIGNED: K.E.	DRAWN: J.E.	AUTHORISED: K.E.	PROJECT START DATE: SEPTEMBER 2020	



PRE DEVELOPMENT CATCHMENT PLAN
SCALE 1: 200

PRE DEVELOPMENT CATCHMENT ANALYSIS:


TOTAL SITE AREA:	1300.89 m ²
ROOF	213.41 m ²
HARDSTAND	432.55 m ²
LANDSCAPE	654.93 m ²



POST DEVELOPMENT CATCHMENT PLAN
SCALE 1: 200


POST DEVELOPMENT CATCHMENT ANALYSIS:

TOTAL SITE AREA:	1300.89 m ²
AREA DRAINING TO OSD	1171.97 m ²
-ROOF	290.31 m ²
-HARDSTAND	618.28 m ²
-LANDSCAPE	227.13 m ²
-DRIVEWAY	36.25 m ²
AREA BYPASSING OSD	128.92 m ²
-IMPERVIOUS	43.19 m ²
-PERVIOUS	85.73 m ²



MUSIC MODEL RESULTS

No.	Description	Date	Issued by	Checked by
A	ISSUED FOR D.A.	07.12.20	J.E.	K.E.



CLIENT: MONTESSORI ACADEMY

ARCHITECT: CULLEN FENG ARCHITECTS

SMART STRUCTURES AUSTRALIA

SUIT 2.04, L2, BLDG 3,
35 WATERLOO RD., MACQUARIE PARK, NSW, 2113
info@smartstrucs.com.au | www.smartstrucs.com.au

DRAWING TITLE PRE & POST DEVELOPMENT CATCHMENT ANALYSIS AND MUSIC MODEL RESULTS		PROJECT 170 DERBY STREET, PENRITH NSW 2750	
SHEET NO. D07	REV. A	SCALE @ A1 AS SHOWN	NORTH
DESIGNED: K.E.	DRAWN: J.E.	AUTHORISED: K.E.	PROJECT NO. 200325
			PROJECT START DATE: SEPTEMBER 2020

OSD DESIGN DETAILS:

BASED ON PENRITH COUNCIL'S ON-SITE STORMWATER DETENTION TECHNICAL SPECIFICATION AN OSD SYSTEM IS REQUIRED FOR THE PROPOSED DEVELOPMENT. DUE TO DESIGN AND SITE'S CONSTRAINTS, COUNCIL'S DEVELOPMENT TEAM WAS CONSULTED TO AGREE IF OSD SYSTEM CAN BE SIZED THROUGH A DRAINS MODELING. IT WAS AGREED WITH THE DEVELOPMENT ENGINEER, JAKE, THAT A DRAINS MODEL (ILSAX) CAN BE USED IN LIEU OF SIMPLIFIED METHOD IN DETERMINING SITE STORAGE REQUIREMENT (SSR) AND PERMISSIBLE SITE DISCHARGE (PSD).

A DRAINS MODEL ILSAX METHOD WAS USED TO SIZE THE ON-SITE DETENTION SYSTEM.

BASED ON THE DRAINS MODEL'S RESULTS (SHOWN ON THIS PAGE), WITH INCORPORATION OF A MIN 21.2m³ OF AN OSD TANK, THERE WILL BE NO INCREASE IN RUNOFF FROM THE SITE AS A RESULT OF THE DEVELOPMENT UNDER ALL DURATIONS FOR ALL THE STORMS UP TO AND INCLUDING 1% AEP EVENT.

TOTAL SITE AREA: 1300.89 m²

PRE-DEVELOPMENT CATCHMENT CONDITIONS:

IMPERVIOUS AREA = 645.96 m²
 PERVIOUS AREA = 654.93 m²

POST DEVELOPMENT CATCHMENT CONDITIONS:

TOTAL AREA DRAINING TO OSD = 1171.97m²

- ROOF AREA (IMPERVIOUS) = 290.31 m²
- DRIVEWAY AREA (IMPERVIOUS) = 36.25 m²
- HARDSTAND AREA (IMPERVIOUS) = 618.28 m²
- LANDSCAPE AREA (PERVIOUS) = 227.13 m²

TOTAL AREA BYPASSING OSD = 128.92 m²








- IMPERVIOUS AREA (BYPASSING) = 43.19 m²
- PERVIOUS AREA (BYPASSING) = 85.73 m²

BASED ON THE DESIGN POLICY THE RUN-OFF FROM THE SITE AFTER DEVELOPMENT IS NOT TO EXCEED THE RUN-OFF FROM THE TOTAL SITE PRIOR TO THE DEVELOPMENT FOR ALL STORM DURATIONS UP TO 1% AEP STORM EVENT.

ALSO THE PSD IS LIMITED TO MAXIMUM 25l/s DURING 10% AEP AS STORMWATER DISCHARGE POINT IS PROPOSED TO BE TO THE LEVEL OF KERB IN FRONT OF SITE.

ON-SITE DETENTION DRAINS DESIGN SUMMARY


STORM EVENT	PRE-DEVELOPMENT (l/s)	OSD OUTFLOW + BYPASS (l/s)	OSD VOL. (m ³)	Top Water Level (m AHD)
5 YR ARI (20% AEP)	27	21	5.5	39.7
10 YR ARI (10% AEP)	36	25	9.2	39.81
20 YR ARI (5% AEP)	44	28	12.4	39.9
50 YR ARI (2% AEP)	53	32	16.9	40.03
100 YR ARI (1% AEP)	61	35	21.1	40.15



CLIENT: MONTESSORI ACADEMY
 ARCHITECT: CULLEN FENG ARCHITECTS

SMART STRUCTURES AUSTRALIA
 SUIT 2.04, L2, BLDG 3,
 35 WATERLOO RD., MACQUARIE PARK, NSW, 2113
 info@smartstructs.com.au | www.smartstructs.com.au

DRAWING TITLE: **CALCULATIONS SHEET**
 PROJECT: 170 DERBY STREET, PENRITH NSW 2750
 SHEET NO. **D08** REV. **A** SCALE @ A1 **AS SHOWN**
 PROJECT NO. **200325**
 PROJECT START DATE: **SEPTEMBER 2020**






EROSION AND SEDIMENT CONTROL PLAN
SCALE 1: 200

EROSION CONTROL NOTES


- ALL EROSION & SEDIMENT CONTROL MEASURES ARE TO BE INSTALLED AND MAINTAINED IN ACCORDANCE WITH 'MANAGING URBAN STORMWATER, 3RD EDITION' PRODUCED BY THE NSW DEPARTMENT OF HOUSING.
 - ALL EROSION AND SILTATION CONTROL DEVICES ARE TO BE PLACED PRIOR TO THE COMMENCEMENT OF ANY CONSTRUCTION AND REMOVED REGULARLY DURING CONSTRUCTION
 - ALL TREES ARE TO BE PRESERVED UNLESS INDICATED OTHERWISE ON THE ARCHITECT'S OR LANDSCAPE ARCHITECT'S DRAWINGS. EXISTING GRASS COVER SHALL BE MAINTAINED EXCEPT IN AREAS CLEARED FOR BUILDINGS, PAVEMENTS ETC- CONTRACTOR TO MINIMISE DISTURBED AREAS.
 - INSTALL TEMPORARY SEDIMENT BARRIERS TO ALL INLET PITS LIKELY TO COLLECT SILT LADDED WATER
 - NOT WITHSTANDING DETAILS SHOWN, IT IS THE CONTRACTOR'S SOLE RESPONSIBILITY TO ENSURE THAT ALL SITE ACTIVITIES COMPLY WITH THE REQUIREMENTS OF THE CLEAN WATERS ACT.
 - ALL DISTURBED AREAS AND STOCKPILES TO BE STABILISED WITHIN 14 DAYS. ALL STOCKPILES TO BE CLEAR FROM DRAINS, GUTTERS AND FOOTPATHS.
 - TOPSOIL TO BE STRIPPED, STOCKPILED AND RE-SPREAD ON COMPLETION OF EARTHWORKS. NONE TO BE REMOVED.
 - NO DISTURBANCE OF SITE PERMITTED OTHER THAN IMMEDIATE AREA OF THE WORKS.
 - DRAINAGE IS TO BE CONNECTED TO STORMWATER SYSTEM AS SOON AS POSSIBLE.
- NON-COMPLIANCE MAY RESULT IN A \$1500 FINE

SYMBOLS



SANDBAG KERB INLET SEDIMENT TRAP


- NOTES THIS DRAWING**
- ALL DOCUMENTS WILL BE SUBMITTED TO COUNCIL FOR APPROVAL.
 - ALL SEDIMENT CONTROL MEASURES ARE TO BE IN PLACE.
 - INSTALLATION OF SILT FENCING, SEDIMENTATION BARRIERS AROUND DRAINS.
 - FENCING IS TO BE 1.8m(min) HEIGHT, PLACED AROUND THE SITE UNTIL THE WORK COMPLETE.
 - THE SITE GATES WILL BE LOCATED AT DERBY STREET.
 - THE HARDSTAND AREAS OR CATTLE GRIDS WILL BE PLACED AT THE SITE ENTRANCES AND EXITS. TO REMOVE THE BULK OF DIRT AND MUD THAT MAY ACCUMULATE ON TRUCK TYRES.
 - CONTRACTOR WILL CONDUCT REGULAR STREET SWEEPS ALONG THE ACCESS ROUTE TO ENSURE THE ROADS ADJACENT TO THE SITE ENTRANCES ARE KEPT CLEAN OF ANY DIRT AND DEBRIS.
 - REGULAR ENVIRONMENTAL INSPECTIONS WILL BE CARRIED OUT BY CONTRACTOR'S PERSONNEL TO ENSURE COMPLIANCE WITH THIS PLAN.




CATTLE GRID ALTERNATIVE




TREE PROTECTION DETAIL




GEOTEXTILE FILTER FABRIC DROP INLET SEDIMENT TRAP




SOIL STOCK PILE




SEDIMENT FENCE




SILT FENCE DETAIL




HAY BALE DETAIL



TEMPORARY CONSTRUCTION EXIT




STRAW BALE SEDIMENT FILTER



TYPICAL DETAIL OF FILTRATION UNIT

No.	ISSUED FOR D.A.	Description	Date	Issued by	Checked by
A	ISSUED FOR D.A.		07.12.20	J.E.	K.E.



CLIENT: **MONTESSORI ACADEMY**

ARCHITECT: **CULLEN FENG ARCHITECTS**

SMART STRUCTURES AUSTRALIA

SUITE 2.04, L2, BLDG 3,
35 WATERLOO RD., MACQUARIE PARK, NSW, 2113
info@smartstrucs.com.au | www.smartstrucs.com.au

DRAWING TITLE EROSION AND SEDIMENT CONTROL PLAN AND DETAILS SHEET 1		PROJECT 170 DERBY STREET, PENRITH NSW 2750	
SHEET NO. D10	REV. A	SCALE @ A1 AS SHOWN	NORTH
DESIGNED: K.E.	DRAWN: J.E.	AUTHORISED: K.E.	PROJECT NO. 200325
			PROJECT START DATE: SEPTEMBER 2020

GENERAL INSTRUCTIONS:

SWM01 THESE PLANS PRESENT A CONCEPTUAL SOIL AND WATER MANAGEMENT PLAN (SWMP) ONLY AND SHOWS A POSSIBLE WAY OF MANAGING SOIL AND EROSION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE ESTABLISHMENT AND MANAGEMENT OF THE SITE AND PREPARING A DETAILED PLAN AND OBTAINING APPROVAL FROM THE RELEVANT AUTHORITY PRIOR TO THE COMMENCEMENT OF ANY WORKS.

SWM02 THIS PLAN IS TO BE READ IN CONJUNCTION WITH THE ENGINEERING PLANS AND ANY OTHER PLANS, WRITTEN INSTRUCTIONS, SPECIFICATION OR DOCUMENTATION THAT MAY BE ISSUED AND RELATING TO DEVELOPMENT OF THE SUBJECT SITE.

SWM03 THE CONTRACTOR WILL ENSURE THAT ALL SOIL AND WATER MANAGEMENT WORKS ARE CONSISTENT WITH 'MANAGING URBAN STORMWATER - SOILS AND CONSTRUCTION' - ALSO KNOWN AS 'THE BLUE BOOK'.

SWM04 ALL BUILDERS AND SUB-CONTRACTORS SHALL BE INFORMED OF THEIR RESPONSIBILITIES IN MINIMISING THE POTENTIAL FOR SOIL EROSION AND POLLUTION TO DOWNSLOPE LANDS AND WATERWAYS.

EROSION CONTROL:

SWM05 WATER SHALL BE PREVENTED FROM ENTERING THE PERMANENT DRAINAGE SYSTEM UNTIL SEDIMENT CONCENTRATION IS LESS THEN OR EQUAL TO 50MG/L. IE THE CATCHMENT AREA HAS BEEN PERMANENTLY LANDSCAPED AND/ OR ANY LIKELY SEDIMENT HAS BEEN FILTERED THROUGH AND APPROVED STRUCTURE.

SWM06 ANY SAND USED IN THE CONCRETE CURING PROCESS (SPREAD THE SURFACE WILL BE REMOVED AS SOON AS POSSIBLE AND WITHIN 10 WORKING DAYS FROM PLACEMENT.

SWM07 ACCEPTABLE RECEPTORS WILL BE CONSTRUCTED FOR CONCRETE AND MORTAR SLURRIES, PAINTS, ACID WASHINGS, LIGHT-WEIGHT WASTE MATERIALS AND LITTER.

SWM08 'SEDIMENT' FENCING WILL BE INSTALLED AS INDICATED ON THE PLANS AND AT THE DIRECTION OF SITE SUPERINTENDENT TO ENSURE CONTAINMENT OF SEDIMENT. THE SEDIMENT FENCING WILL OUTLET OR OVERFLOW UNDER STABILISED CONDITIONS INTO THE SEDIMENT BASIN, TO SAFELY CONVEY WATER INTO A SUITABLE FILTERING SYSTEM SHOULD THE PORES IN THE FABRIC BLOCK.

SWM09 THE SEDIMENT BASINS WILL BE CONSTRUCTED WITH THE MINIMUM WET SEDIMENT CAPACITY OF CUM CUBIC METERS AND DESIGNED TO REMAIN STABLE IN AT LEAST THE 1 IN CDSE YEAR CRITICAL DURATION STORM EVENT. ARTIFICIAL FLOCCULATION OF THE FINER PARTICLES MAY NOT BE NECESSARY IN THIS INSTANCE.

SWM10 STOCKPILES SHOULD NOT BE LOCATED WITHIN 5M OF TREES AND HAZARD AREAS, INCLUDING LIKELY AREAS OF CONCENTRATED OR HIGH VELOCITY FLOWS SUCH AS WATERWAYS, DRAINAGE LINES, PAVED AREAS AND DRIVEWAYS. WHERE THEY ARE WITHIN 5M FROM SUCH AREAS, SPECIAL SEDIMENT CONTROL MEASURES SHOULD BE TAKEN TO MINIMISE POSSIBLE POLLUTION TO DOWNSTREAM WATERS. MEASURE SHOULD ALSO BE APPLIED TO PREVENT THE EROSION OF THE STOCKPILE.

SWM11 ALL CUT AND FILL BATTERS ARE TO BE SEEDED AND MULCHED WITHIN 14 DAYS OF COMPLETION OF FORMATION.

SWM12 ANY EXISTING TREES WHICH FORM PART OF THE FINAL LANDSCAPING PLAN WILL BE PROTECTED FROM CONSTRUCTION ACTIVITIES BY - A. PROTECTING THEM WITH BARRIER FENCING OR SIMILAR MATERIALS INSTALLED OUTSIDE THE DRIP LINE. B. ENSURING THAT NOTHING IS NAILED TO THEM. C. PROHIBITING PAVING GRADING SEDIMENT WASH OR PLACING OF STOCKPILES WITHIN THE DRIP LINE EXCEPT UNDER THE FOLLOWING CONDITIONS: 1. ENCROACHMENT ONLY OCCURS ON ONE SIDE AND NO CLOSER TO THE TRUNK THAN EITHER 1.5 METRES OR HALF THE DISTANCE BETWEEN THE OUTER EDGE OF THE DRIP LINE AND THE TRUNK, WHICH EVER IS THE GREATER, 2. A DRAINAGE SYSTEM THAT ALLOWS AIR AND WATER TO CIRCULATE THROUGH THE ROOT ZONE (E.G. A GRAVEL BED) IS PLACED UNDER ALL FILL LAYERS OF MORE THAN 300 MILLIMETRES DEPTH, 3. CARE IS TAKEN.

SWM13 DURING WINDY WEATHER, LARGE DISTURBED UNPROTECTED AREAS SHOULD BE KEPT MOIST (NOT WET) BY SPRINKLING WITH WATER TO KEEP DUST UNDER CONTROL.

SWM14 TEMPORARY PROTECTION FROM EROSION FORCES WILL BE UNDERTAKEN ON LANDS WHERE FINAL SHAPING HAS NOT BEEN COMPLETED BUT WORKS ARE UNLIKELY TO PROCEED FOR PERIODS OF TWO MONTHS OR MORE (EG. ON TOP SOIL STOCKPILES). THIS MAY BE ACHIEVED WITH A VEGETATIVE COVER. A RECOMMENDED LISTING OF PLANT SPECIES FOR SOIL AND WATER MANAGEMENT NOTES: TEMPORARY COVER IS - I) AUTUMN/WINTER SOWING -OATS/RYEGRASS AT 20KG/HA -JAPANESE MILLET AT 10KG/HA II) SPRING/SUMMER SOWING -JAPANESE MILLET AT 20KG/HA -OATS/RYEGRASS AT 10 KG/HA

SWM15 DIVERSION BANKS/ CHANNELS WILL BE REHABILITATED AS SOON AS POSSIBLE AND WITHIN 5 WORKING DAYS FROM THEIR FINAL SHAPING. OTHER THAN IN THE WINTER MONTHS, SUITABLE MATERIALS INCLUDE TURF GRASSES SUCH S COUCH OR KIKUYU. DURING WINTER, OR AT OTHER TIMES WHEN TEMPORARY REHABILITATION (MORE THAN 3 MONTHS) IS REQUIRED, IT IS SUGGESTED THAT HESSIAN CLOTH IS USED BUT ONLY IF TACKED WITH APPROPRIATE PEGS AND AN ANIONIC BITUMEN EMULSION. FOOT AND VEHICULAR TRAFFIC SHOULD BE KEPT AWAY FROM THESE AREAS.

SWM16 UNDERTAKE SITE DEVELOPMENT WORKS IN ACCORDANCE WITH THE ENGINEERING PLANS. WHERE POSSIBLE, PHASE DEVELOPMENT SO THAT LAND DISTURBANCE IS CONFINED TO AREAS OF WORKABLE SIZE.

CONSTRUCTION SEQUENCE

SWM17 WHERE PRACTICAL, THE SOIL EROSION HAZARD ON THE SITE SHOULD BE KEPT AS LOW AS POSSIBLE. TO THIS END, WORKS SHOULD BE UNDERTAKEN IN THE FOLLOWING SEQUENCE -

- I) INSTALL INLET SEDIMENT TRAPS TO ALL GULLY PITS FRONTING THE SITE. II) INSTALL A 1.8M CHAIN WIRE FENCE AROUND THE BOUNDARIES AND ATTACH HESSIAN CLOTH OR SIMILAR TO IT ON THE WINDWARD SIDE (TIES AT THE TOP, CENTRE AND BOTTOM AND AT 1M INTERVALS OR AS INSTRUCTED BY THE SUPERINTENDENT). III) INSTALL GEOFABRIC SEDIMENT FENCE AND SEDIMENT TRAPS AROUND ALL PERMANENT STORMWATER RETICULATION STRUCTURES AS SHOWN ON THE PLAN. IV) CONSTRUCT STABILISED CONSTRUCTION ENTRANCE AS SHOWN ON THE PLAN OR TO LOCATION AS DETERMINED BY SUPERINTENDENT. V) INSTALL DIVERSION BANKS ALONG THE BOUNDARY WHERE REQUIRED. REHABILITATE DISTURBED LANDS DOWNSLOPE FROM THE BASINS WITHIN 20 WORKING DAYS. VI) ENSURE THAT THE SEDIMENT BASIN IS DIRECTED ONTO A TURFED AREA AND DRAINS TO A SUITABLE LOCATION. A TEMPORARY STORMWATER LINE MAY BE NECESSARY TO CONVEY THE FLOWS TO THIS LOCATION. CONSTRUCT DIVERSION CHANNELS AT THE BOUNDARY TO DRAIN INTO THE SEDIMENT BASIN AS SHOWN ON PLANS. VII) AT COMPLETION STABILISE SITE AND DECOMMISSION SEDIMENT BASIN AND ALL EROSION CONTROL DEVICES.

SWM18 TEMPORARY SOIL AND WATER MANAGEMENT STRUCTURES WILL BE REMOVED ONLY AFTER THE LANDS THEY ARE PROTECTING ARE REHABILITATED.


SWM19 FINAL SITE LANDSCAPING WILL BE UNDERTAKEN AS SOON AS POSSIBLE AND WITHIN 20 WORKING DAYS FROM COMPLETION OF CONSTRUCTION ACTIVITIES.

SITE INSPECTION AND MAINTENANCE

SWM 20 AT LEAST WEEKLY AND AFTER EVERY RAIN FALL EVENT, THE CONTRACTOR WILL INSPECT THE SITE AND ENSURE THAT - I) DRAINS AND ALL SEDIMENT CONTROL DEVICES OPERATE EFFECTIVELY AND INITIATE REPAIR OR MAINTENANCE AS REQUIRED. II) RECEPTORS FOR CONCRETE AND MORTAR SLURRIES, PAINTS, ACID WASHINGS, LIGHT-WIGHT WASTE MATERIALS AND LITTER ARE TO BE EMPTIED AS NECESSARY. DISPOSAL OF WASTE SHALL BE IN A MANOR APPROVED BY THE SUPERINTENDENT. III) SPILL SAND (OR OTHER MATERIALS) IS REMOVED FROM HAZARD AREAS, INCLUDING LIKELY AREAS OF CONCENTRATED OR HIGH VELOCITY FLOWS SUCH AS WATERWAYS, GUTTERS, PAVED AREAS AND DRIVEWAYS. IV) SEDIMENT IS REMOVED FROM BASINS AND / OR TRAPS WHEN LESS THAN 20M³ OF TRAPPING CAPACITY REMAIN PER 1000M² OF DISTRIBUTED LANDS, AND OR LESS THAN 500 DEPTH REMAINS IN THE SETTLING ZONE. ANY COLLECTED SEDIMENT WILL BE DISPOSED IN AREAS WHERE FURTHER POLLUTION TO DOWN SLOPE LANDS AND WATERWAYS IS UNLIKELY. V) REHABILITATED LANDS HAVE EFFECTIVELY REDUCED THE EROSION HAZARD AND INITIATE UPGRADING OR REPAIR AS APPROPRIATE.

SWM 21 THE CONTRACTOR SHALL PROVIDE ALL MONITORING CONTROL AND TESTING.

SCALE BARS



CLIENT:

MONTESSORI ACADEMY

ARCHITECT:

CULLEN FENG ARCHITECTS



SUIT 2.04, L2, BLDG 3, 35 WATERLOO RD., MACQUARIE PARK, NSW, 2113 info@smartstructs.com.au | www.smartstructs.com.au

DRAWING TITLE

EROSION AND SEDIMENT CONTROL PLAN AND DETAILS SHEET 2

PROJECT 170 DERBY STREET, PENRITH NSW 2750

SHEET NO.

D11

REV.

A

SCALE @ A1

NTS

DESIGNED:

K.E.

DRAWN:

J.E.

AUTHORISED:

K.E.

PROJECT NO.

200325

PROJECT START DATE:

SEPTEMBER 2020