

PENRITH CITY COUNCIL

NOTICE OF DETERMINATION

DESCRIPTION OF DEVELOPMENT

Application number:	DA18/0255
Description of development:	Demolition of Existing Structures and Construction of Twelve (12) x Town Houses with Associated Basement Parking
Classification of development:	Class 2 , Class 7a

DETAILS OF THE LAND TO BE DEVELOPED

Legal description:	Lot 158B DP 12590 Lot 5 DP 25635
Property address:	11 Sydney Street, ST MARYS NSW 2760 9 Sydney Street, ST MARYS NSW 2760

DETAILS OF THE APPLICANT

Name & Address:	G M Architects Pty Ltd 330a Parramatta Road HOMEBUSH WEST NSW 2140
-----------------	--

DECISION OF CONSENT AUTHORITY

In accordance with Section 81(1) (a) of the Environmental Planning and Assessment Act 1979, consent is granted subject to the conditions listed in attachment 1.

Please note that this consent will lapse on the expiry date unless the development has commenced in that time.

Date from which consent operates	24 August 2018
Date the consent expires	24 August 2020
Date of this decision	23 August 2018

POINT OF CONTACT

If you have any questions regarding this determination you should contact:

Assessing Officer:	Gannon Cuneo
Contact telephone number:	+612 4732 7774

NOTES

Reasons

The conditions in the attached schedule have been imposed in accordance with Section 80A of the Environmental Planning and Assessment Act 1979 as amended.

Conditions

Your attention is drawn to the attached conditions of consent in attachment 1.

Certification and advisory notes

You should also check if this type of development requires a construction certificate in addition to this development consent

It is recommended that you read any Advisory Note enclosed with this notice of determination.

Review of determination

The applicant may request Council to review its determination pursuant to Section 82A of the Environmental Planning and Assessment Act 1979 within 6 months of receiving this Notice of Determination.

You cannot make this request if the development is Designated Development, Integrated Development or State Significant development or if the application was decided by Sydney West Planning Panel.

Appeals in the Land and Environment Court

The applicant can appeal against this decision in the Land and Environment Court within six (6) months of receiving this Notice of Determination.

You cannot appeal if a Commission of Inquiry was held for the subject development application, or if the development is a State Significant Development.

An appeal to the Land and Environment Court is made by lodging an application to the Court in accordance with the Rules of the Court.

Designated development

If the application was for designated development and a written objection was made in respect to the application, the objector can appeal against this decision to the Land and Environment Court within 28 days after the date of this notice. The objector cannot appeal if a Commission of Inquiry was held.

If the applicant appeals against this decision, objector(s) will be given a notice of the appeal and the objector(s) can apply to the Land and Environment Court within 28 days after the date of this appeal notice to attend the appeal and make submissions at that appeal.

Sydney West Planning Panels

If the application was decided by the Sydney West Planning Panel, please refer to Section 18 of the Greater Sydney Commission Act 2015 and Section 23H of the Environmental Planning and Assessment Act, 1979 (as amended) for any further regulations.

ATTACHMENT 1: CONDITIONS OF CONSENT

General

- 1 The development must be implemented substantially in accordance with the plans stamped approved by Council, the application form, the BASIX Certificate numbered 907405M and any supporting information received with the application, except as may be amended in red on the attached plans and by the following conditions.

Plan:	Reference:	Rev	Author:	Dated:
Basement 1	17839-08 A104	-	GM Architects	26/06/18
Ground Floor	17839-08 A105	-	GM Architects	26/06/18
Level 1	17839-08 A106	-	GM Architects	26/06/18
Roof	17839-08 A107	-	GM Architects	26/06/18
Elevations	17839-08 A108	-	GM Architects	26/06/18
Elevations	17839-08 A109	-	GM Architects	26/06/18
Sections	17839-08 A110	-	GM Architects	26/06/18
Demolition	17839-08 A116	-	GM Architects	26/06/18
Waste Management	17839-08 A117	-	GM Architects	26/06/18
Landscape 1	LA. 1.01	B	Site Design+ Studios	13/03/18
Landscape 2	LA. 1.02	B	Site Design+ Studios	13/03/18
Landscape 3	LA. 1.03	B	Site Design+ Studios	13/03/18
Landscape 4	LA. 1.04	B	Site Design+ Studios	13/03/18
Plant Schedule, Details and Specifications	LA. 2.00	B	Site Design+ Studios	13/03/18
Stormwater Concept Plan Basement Level 1 of 2	171808/101	B	Australian Consulting Engineers	30/05/18
Stormwater Concept Plan Basement Level 2 of 2	171808/102	B	Australian Consulting Engineers	30/05/18
Stormwater Concept Plan Ground Level	171808/103	B	Australian Consulting Engineers	30/05/18
OSD Details and Calculations	171808/104	B	Australian Consulting Engineers	30/05/18
Miscellaneous Details	171808/105	B	Australian Consulting Engineers	30/05/18

2 The work must be carried out in accordance with the requirements of the Building Code of Australia. If the work relates to a residential building and is valued in excess of \$20,000, then a contract of insurance for the residential development shall be in force in accordance with Part 6 of the Home Building Act 1989.

{Note: Residential building includes alterations and additions to a dwelling, and structures associated with a dwelling house/dwelling such as a carport, garage, shed, rural shed, swimming pool and the like}.

3 **The development shall not be used or occupied until an Occupation Certificate has been issued.**

4 **Prior to the issue of an Occupation Certificate**, a lighting system shall be installed for the development to provide uniform lighting across common areas and driveways. Exterior lighting shall be located and directed in such a manner so as not to create a nuisance to surrounding land uses. The lighting shall be the minimum level of illumination necessary for safe operation. The lighting shall be in accordance with AS 4282 "Control of the obtrusive effects of outdoor lighting" (1997).

5 The finishes of all structures and buildings are to be maintained at all times and any graffiti or vandalism immediately removed/repaired.

6 A **Construction Certificate** shall be obtained prior to commencement of any building works.

7 **Prior to the issue of a Construction Certificate**, plans are to be amended as follows:

- The building length of Units 10, 11 and 12 shall be reduced to provide a 6 metre rear setback in accordance with Penrith Development Control Plan 2014;
- The Waste Collection Area and Bulky Households Goods Area are to provide wash facilities through the use of a centralised mixing valve and hose cock. Respective drainage and water proofing to be installed to support the use of hose facilities;
- The wall height of the screening surrounding the Waste Collection Area and Bulky Goods Bay to not exceed 1.4m above natural ground level; and
- The door of the Waste Collection Room to open outwards 180 degrees and provide an unobstructed opening of 1.2m wide. A latch device is to be installed to allow the door to be held open to permit collection by Councils waste collection contractors.

8 **Prior to the issue of an Occupation Certificate**, the certifying authority shall ensure the following:

- The developer is to enter into a formal agreement with Penrith City Council for the utilisation of Councils Waste Collection Service. This is to include Council being provided with indemnity against claims for loss and damage.

Demolition

9 The existing structures on the subject site are to be demolished as part of the approved work.

10 All demolition works are to be conducted in accordance with the provisions of AS 2601-1991 "The Demolition of Structures". **Prior to demolition**, all services shall be suitably disconnected and capped off or sealed to the satisfaction of the relevant service authority requirements.

All demolition and excavated material shall be disposed of at a Council approved site or waste facility. Details of the proposed disposal location(s) of all excavated material from the development site shall be provided to the Principal Certifying Authority **prior to commencement of demolition**.

- 11 **Prior to commencement of demolition works on site**, a portaloos with appropriate washing facilities shall be located on the site and the Principal Certifying Authority is to be satisfied that:
- Measures are in place so as to comply with the WorkCover Authority's "Short Guide to Working with Asbestos Cement" and
 - The person employed to undertake the works is a licensed asbestos removal contractor and is holder of a current WorkCover Asbestos Licence.

Any demolition works involving the removal of all asbestos shall only be carried out by a licensed asbestos removal contractor who has a current WorkCover Asbestos Licence.

All asbestos laden waste, including asbestos cement flat and corrugated sheeting must be disposed of at a tipping facility licensed by the Environmental Protection Authority to receive asbestos wastes.

Environmental Matters

- 12 Dust suppression techniques are to be employed during demolition and construction to reduce any potential nuisances to surrounding properties.
- 13 Mud and soil from vehicular movements to and from the site must not be deposited on the road.
- 14 No fill material is to be imported to the site without the prior approval of Penrith City Council in accordance with Sydney Regional Environmental Plan No.20 (Hawkesbury- Nepean River) (No.2-1997). No recycling of material for use as fill material shall be carried out on the site without the prior approval of Council.
- 15 All waste materials stored on-site are to be contained within a designated area such as a waste bay or bin to ensure that no waste materials are allowed to enter the stormwater system or neighbouring properties. The designated waste storage areas shall provide at least two waste bays / bins so as to allow for the separation of wastes, and are to be fully enclosed when the site is unattended.
- 16 All excavated material and other wastes generated as a result of the development are to be re-used, recycled or disposed of in accordance with the approved waste management plan.

Waste materials not specified in the approved waste management plan are to be disposed of at a lawful waste management facility. Where the disposal location or waste materials have not been identified in the waste management plan, details shall be provided to the Certifying Authority as part of the waste management documentation accompanying the Construction Certificate application.

All receipts and supporting documentation must be retained in order to verify lawful disposal of materials and are to be made available to Penrith City Council on request.

- 17 Councils bin infrastructure and waste collection service will be provided / commenced for the development upon the completion of all on-site waste collection infrastructure and the attainment of an Occupation Certificate.

BCA Issues

- 18 All aspects of the building design shall comply with the applicable performance requirements of the Building Code of Australia so as to achieve and maintain acceptable standards of structural sufficiency, safety (including fire safety), health and amenity for the on-going benefit of the community. Compliance with the performance requirements can only be achieved by:
- (a) complying with the deemed to satisfy provisions, or
 - (b) formulating an alternative solution which:
 - complies with the performance requirements, or
 - is shown to be at least equivalent to the deemed to satisfy provision, or
 - (c) a combination of (a) and (b).

It is the owner's responsibility to place on display, in a prominent position within the building at all times, a copy of the latest fire safety schedule and fire safety certificate/ statement for the building.

Utility Services

- 19 A Section 73 Compliance Certificate under the Sydney Water Act 1994 shall be obtained from Sydney Water. The application must be made through an authorised Water Servicing Coordinator. Please refer to "Your Business" section of Sydney Water's website at www.sydneywater.com.au then the "e-developer" icon, or telephone 13 20 92.

The Section 73 Compliance Certificate must be submitted to the Principal Certifying Authority **prior to the issue of an Occupation Certificate**.

- 20 **Prior to the issue of a Construction Certificate**, a written clearance is to be obtained from Endeavour Energy stating that electrical services have been made available to the development or that arrangements have been entered into for the provision of services to the development.

In the event that a pad mounted substation is necessary to service the development, Penrith City Council shall be consulted over the proposed location of the substation before the Construction Certificate for the development is issued as the location of the substation may impact on other services and building, driveway or landscape design already approved by Council.

- 21 **Prior to the issue of a Construction Certificate**, the Principal Certifying Authority shall be satisfied that telecommunications infrastructure may be installed to service the premises which complies with the following:
- The requirements of the Telecommunications Act 1997;
 - For a fibre ready facility, the NBN Co's standard specifications current at the time of installation; and
 - For a line that is to connect a lot to telecommunications infrastructure external to the premises, the line shall be located underground.

Unless otherwise stipulated by telecommunications legislation at the time of construction, the development must be provided with all necessary pits and pipes, and conduits to accommodate the future connection of optic fibre technology telecommunications.

Prior to the issue of an Occupation Certificate, written certification from all relevant service providers that the telecommunications infrastructure is installed in accordance with the requirements above and the applicable legislation at the time of construction, must be submitted to the Principal Certifying Authority.

22 **Prior to the issue of an Occupation Certificate**, any service pits or infrastructure located within 1 metre of the vehicular crossing are to be relocated to the satisfaction of Council and the relevant services authority.

Construction

23 Stamped plans, specifications, a copy of the development consent, the Construction Certificate and any other Certificates to be relied upon shall be available on site at all times during construction.

The following details are to be displayed in a maximum of 2 signs to be erected on the site:

- the name of the Principal Certifying Authority, their address and telephone number,
- the name of the person in charge of the work site and telephone number at which that person may be contacted during work hours,
- that unauthorised entry to the work site is prohibited,
- the designated waste storage area must be covered when the site is unattended, and
- all sediment and erosion control measures shall be fully maintained until completion of the construction phase.

Signage but no more than 2 signs stating the above details is to be erected:

- at the commencement of, and for the full length of the, construction works onsite, and
- in a prominent position on the work site and in a manner that can be easily read by pedestrian traffic.

All construction signage is to be removed when the Occupation Certificate has been issued for the development.

24 Prior to the commencement of construction works:

(a) Toilet facilities at or in the vicinity of the work site shall be provided at the rate of one toilet for every 20 persons or part of 20 persons employed at the site. Each toilet provided must be:

- a standard flushing toilet connected to a public sewer, or
- if that is not practicable, an accredited sewage management facility approved by the council, or
- alternatively, any other sewage management facility approved by council.

(b) All excavations and backfilling associated with the erection or demolition of a building must be executed safely and in accordance with the appropriate professional standards. All excavations associated with the erection or demolition of a building must be properly guarded and protected to prevent them from being dangerous to life or property.

(c) If an excavation associated with the erection or demolition of a building extends below the level of the base of the footings of a building on an adjoining allotment of land, the person causing the excavation to be made:

- must preserve and protect the building from damage, and
- if necessary, must underpin and support the building in an approved manner, and
- must, at least 7 days before excavating below the level of the base of the footings of a building on an adjoining allotment of land, give notice of intention to do so to the owner of the adjoining allotment of land and furnish particulars of the excavation to the owner of the building being erected or demolished. The owner of the adjoining allotment of land is not liable for any part of the cost of work carried out for the purposes of this condition, whether carried out on the allotment of land being excavated or on the adjoining allotment of land, (includes a public road and any other public place).

(d) If the work involved in the erection or demolition of a building is likely to cause pedestrian or vehicular traffic in a public place to be obstructed or rendered inconvenient, or involves the enclosure of a public place, a hoarding or fence must be erected between the work site and the public place:

- if necessary, an awning is to be erected, sufficient to prevent any substance from, or in connection with, the work falling into the public place,
- the work site must be kept lit between sunset and sunrise if it is likely to be hazardous to persons in the public place, and
- any such hoarding, fence or awning is to be removed when the work has been completed.

25 The building shall be set out by a registered surveyor. A Survey Certificate shall be undertaken and submitted to the Principal Certifying Authority when the building is constructed to ground floor slab level.

26 **Prior to the issue of an Occupation Certificate**, clothes drying facilities are to be installed in a location screened from public view.

27 Demolition and construction works that are carried out in accordance with an approved consent that involve the use of heavy vehicles, heavy machinery and other equipment likely to cause offence to adjoining properties shall be restricted to the following hours in accordance with the NSW Environment Protection Authority Noise Control Guidelines:

- Mondays to Fridays, 7am to 6pm
- Saturdays, 7am to 1pm (if inaudible on neighbouring residential premises), otherwise 8am to 1pm
- No work is permitted on Sundays and Public Holidays.

Other construction works carried out inside a building/tenancy and do not involve the use of equipment that emits noise are not restricted to the construction hours stated above.

The provisions of the Protection of the Environment Operations Act, 1997 in regulating offensive noise also

apply to all construction works.

Engineering

- 28 All roadworks, stormwater drainage works, associated civil works and dedications, required to effect the consented development shall be undertaken at no cost to Penrith City Council.
- 29 An Infrastructure Restoration Bond is to be lodged with Penrith City Council for development involving works around Penrith City Council's Public Infrastructure Assets. The bond is to be lodged with Penrith City Council prior to commencement of any works on site or prior to the issue of any Construction Certificate, whichever occurs first. The bond and applicable fees are in accordance with Council's adopted Fees and Charges.

An application form together with an information sheet and conditions are available on Council's website.

Contact Penrith City Council's City Works Department on (02) 4732 7777 or visit Penrith City Council's website for more information.

- 30 **Prior to the issue of any Construction Certificate**, a Section 138 Roads Act applications, including payment of application and inspection fees, shall be lodged and approved by Penrith City Council (being the Roads Authority for any works required in a public road). These works may include but are not limited to the following:
- Vehicular crossings (including kerb reinstatement of redundant vehicular crossings)
 - Concrete footpaths and or cycleways
 - Road opening for utilities and stormwater (including stormwater connection to Penrith City Council roads and other Penrith City Council owned drainage)
 - Road occupancy or road closures
 - The placement of hoardings, structures, containers, waster skips, signs etc. in the road reserve
 - Temporary construction access

All works shall be carried out in accordance with the Roads Act approval, the development consent, including the stamped approved plans, and Penrith City Council's specifications, guidelines and best engineering practice.

- Contact Penrith City Council's City Works Department on (02) 4732 7777 or visit Penrith City Council's website for more information.
- Where Penrith City Council is the Certifying Authority for the development, the Roads Act approval for the above works may be issued concurrently with the Construction Certificate.
- Separate approvals may also be required from the Roads and Maritime Services for classified roads.
- All works associated with the Roads Act approval must be completed prior to the issue of any Occupation Certificate or Subdivision Certificate as applicable.
- On completion of any awning over the road reserve, a certificate from a practising structural engineer certifying the structural adequacy of the awning is to be submitted to Council before Council will inspect the works and issue its final approval under the Roads Act

- 31 The stormwater management system shall be provided generally in accordance with the MUSIC modeling and associated concept plan/s lodged for development approval, prepared by Australian Consulting Engineers reference 171808 drawings 000 to 105, issue B dated 30 May 2018 **as amended in red**.

Engineering plans and supporting calculations for the stormwater management systems are to be prepared by a suitably qualified person and shall accompany the application for a Construction Certificate.

Prior to the issue of a Construction Certificate, the Certifying Authority shall ensure that the stormwater management system has been designed in accordance with Council's Stormwater Drainage for Building Developments and Water Sensitive Urban Design Policy.

- 32 **Prior to the issue of any Construction Certificate**, the Certifying Authority shall ensure that the stormwater drainage system for the basement car park has been designed in accordance with the requirements for pumped systems in AS3500.3 (or as amended) (Plumbing and Drainage – Stormwater Drainage).
- 33 **Prior to the issue of any Construction Certificate**, the Certifying Authority shall ensure that vehicular access, circulation, manoeuvring, pedestrian and parking areas associated with the subject development are in accordance with AS 2890.1, AS2890.2, AS2890.6 and Penrith City Council's Development Control Plan.
- 34 **Prior to the issue of a Construction Certificate** the Certifying Authority shall ensure that a Geotechnical investigation, report and strategy has been conducted to ensure stability of the Council infrastructure and surrounding developments. The geotechnical investigation, report and strategy shall comply with the recommendations contained in the technical direction GTD 2012/001 prepared by the Road and Maritime Services as amended.

The development shall undertake a dilapidation report for all surrounding buildings and Council owned infrastructure that confirms that no damage occurs due to the excavations associated with the development. If Council is not the Certifying Authority the dilapidation report shall be submitted to Council prior to Construction Certificate and then updated and submitted **prior to the issue of any Occupation Certificate** confirming no damage has occurred.

- 35 **Prior to commencement of works** sediment and erosion control measures shall be installed in accordance with the approved Construction Certificate and to ensure compliance with the Protection of the Environment Operations Act 1997.

The erosion and sediment control measures shall remain in place and be maintained until all disturbed areas have been rehabilitated and stabilised.

- 36 **Prior to commencement of any works** associated with the development, a Traffic Control Plan, including details for pedestrian management, shall be prepared in accordance with AS1742.3 "Traffic Control Devices for Works on Roads" and the Roads and Maritime Services' publication "Traffic Control at Worksites" and certified by an appropriately accredited Roads and Maritime Services Traffic Controller.

Traffic control measures shall be implemented during the construction phase of the development in accordance with the certified plan. A copy of the plan shall be available on site at all times.

- A copy of the Traffic Control Plan shall accompany the Notice of Commencement to Penrith City Council.
- Traffic control measures may require road occupancy / road closure approvals issued under Section 138 of the Roads Act by Penrith City Council prior to the issue of a Construction Certificate.

- 37 All existing (aerial) and proposed services for the development, including those across the frontage of the development are to be located or relocated underground in accordance with the relevant authorities regulations and standards.

38 **Prior to the issue of any Occupation Certificate**, the Principal Certifying Authority shall ensure that all works associated with a S138 Roads Act approval or S68 Local Government Act approval have been inspected and signed off by Penrith City Council.

39 **Prior to the issue of an Occupation Certificate**, works-as-executed drawings, final operation and maintenance management plans and any other compliance documentation shall be submitted to the Principal Certifying Authority in accordance with Penrith City Council's Engineering Construction Specification for Civil Works, WSUD Technical Guidelines and Stormwater Drainage for Building Developments.

An original set of works-as-executed drawings and copies of the final operation and maintenance management plans and compliance documentation shall also be submitted to Penrith City Council with notification of the issue of the Occupation Certificate where Council is not the Principal Certifying Authority.

40 **Prior to the issue of an Occupation Certificate** the Principal Certifying Authority shall ensure that the stormwater management systems (including on-site detention and water sensitive urban design):

- Have been satisfactorily completed in accordance with the approved Construction Certificate and the requirements of this consent.
- Have met the design intent with regard to any construction variations to the approved design.
- Any remedial works required to be undertaken have been satisfactorily completed.

Details of the approved and constructed system/s shall be provided as part of the works-as-executed drawings.

41 **Prior to the issue of an Occupation Certificate** a restriction as to user and positive covenant relating to the stormwater management systems (including on-site detention and water sensitive urban design) shall be registered on the title of the property. The restriction as to user and positive covenant shall be in Penrith City Council's standard wording as detailed in Penrith City Council's Stormwater Drainage for Building Development.

42 The stormwater management systems shall continue to be operated and maintained in perpetuity to the satisfaction of Council in accordance with the final operation and maintenance management plan. Regular inspection records are required to be maintained and made available to Council upon request. All necessary improvements are required to be made immediately upon awareness of any deficiencies in the treatment measure/s

43 All car spaces are to be dedicated for the parking of vehicles only and not be used for storage of materials/products/waste materials etc.

44 The required sight lines around the driveway entrances are not to be compromised by landscaping, fencing or signage.

45 All vehicles are to enter/exit the site in a forward direction.

46 **Prior to the issue of any Construction Certificate**, details are to be submitted to and approved by Council for a traffic signal system allowing vehicles to enter/leave the basement without conflict with oncoming vehicles.

Landscaping

47 All landscape works shall be constructed in accordance with the stamped approved Landscape Plan and Chapter C6 of Penrith Development Control Plan 2014.

Landscaping shall be maintained:

- in accordance with the approved plan, and
- in a healthy state, and in perpetuity by the existing or future owners and occupiers of the property.

If any of the vegetation comprising that landscaping dies or is removed, it is to be replaced with vegetation of the same species and, to the greatest extent practicable, the same maturity as the vegetation which died or was removed.

48 Upon completion of the landscape works associated with the development and **prior to the issue of an Occupation Certificate** for the development, an Implementation Report must be submitted to the Principal Certifying Authority attesting to the satisfactory completion of the landscaping works for the development. The report is to be prepared by a qualified landscape professional.

An Occupation Certificate should not be issued until such time as a satisfactory Implementation Report has been received. If Penrith City Council is not the Principal Certifying Authority, a copy of the satisfactory Implementation Report is to be submitted to Council together with the Occupation Certificate for the development.

49 No trees are to be removed, ringbarked, cut, topped or lopped or wilfully destroyed (other than those within the proposed building footprint or as shown on the approved plans) without the prior consent of Penrith City Council and in accordance with Council's Tree Preservation Order and Policy.

50 **Prior to the issue of a Construction Certificate,**

- Landscape plans shall be amended to provide the amendments as marked in red on the stamped approved landscape plan; and
- The certifying authority shall ensure that satisfactory arrangements have been made for planting and drainage along boundaries, over the basement and associated structures. Planter boxes are to be of a volume that provides suitable area for the approved tree species to thrive.

51 All boundary retaining walls and fencing required to be repaired or replaced as a result of the development are to be constructed at the full cost of the developer. All retaining walls are to be of masonry construction.

Section 94

- 52 This condition is imposed in accordance with Penrith City Council's Section 94 Contributions Plan(s) for Cultural Facilities. Based on the current rates detailed in the accompanying schedule attached to this Notice, **\$3,739.00** is to be paid to Council prior to a Construction Certificate being issued for this development (the rates are subject to quarterly reviews). If not paid within the current quarterly period, this contribution will be reviewed at the time of payment in accordance with the adopted Section 94 plan. The projected rates of this contribution amount are listed in Council's Fees and Charges Schedule. Council should be contacted prior to payment to ascertain the rate for the current quarterly period. The S94 invoice accompanying this consent should accompany the contribution payment. The Section 94 Contributions Plan for Cultural Facilities may be inspected at Council's Civic Centre, 601 High Street, Penrith.
- 53 This condition is imposed in accordance with Penrith City Council's Section 94 Contributions Plan(s) for District Open Space. Based on the current rates detailed in the accompanying schedule attached to this Notice, **\$34,567.00** is to be paid to Council prior to a Construction Certificate being issued for this development (the rates are subject to quarterly reviews). If not paid within the current quarterly period, this contribution will be reviewed at the time of payment in accordance with the adopted Section 94 plan. The projected rates of this contribution amount are listed in Council's Fees and Charges Schedule. Council should be contacted prior to payment to ascertain the rate for the current quarterly period. The S94 invoice accompanying this consent should accompany the contribution payment. The Section 94 Contributions Plan for District Open Space may be inspected at Council's Civic Centre, 601 High Street, Penrith.
- 54 This condition is imposed in accordance with Penrith City Council's Section 94 Contributions Plan(s) for Local Open Space. Based on the current rates detailed in the accompanying schedule attached to this Notice, **\$12,496.00** is to be paid to Council prior to a Construction Certificate being issued for this development (the rates are subject to quarterly reviews). If not paid within the current quarterly period, this contribution will be reviewed at the time of payment in accordance with the adopted Section 94 plan. The projected rates of this contribution amount are listed in Council's Fees and Charges Schedule. Council should be contacted prior to payment to ascertain the rate for the current quarterly period. The S94 invoice accompanying this consent should accompany the contribution payment. The Section 94 Contributions Plan for Local Open Space may be inspected at Council's Civic Centre, 601 High Street, Penrith.

Certification

- 55 Prior to the commencement of any earthworks or construction works on site, the proponent is to:
- (a) employ a Principal Certifying Authority to oversee that the said works carried out on the site are in accordance with the development consent and related Construction Certificate issued for the approved development, and with the relevant provisions of the Environmental Planning and Assessment Act and accompanying Regulation, and
 - (b) submit a Notice of Commencement to Penrith City Council.

The Principal Certifying Authority shall submit to Council an "Appointment of Principal Certifying Authority" in accordance with Section 81A of the Environmental Planning and Assessment Act 1979.

Information to accompany the Notice of Commencement

Two (2) days before any earthworks or construction/demolition works are to commence on site (including the clearing site vegetation), the proponent shall submit a "Notice of Commencement" to Council in accordance with Section 81A of the Environmental Planning and Assessment Act 1979.

- 56 An Occupation Certificate is to be obtained from the Principal Certifying Authority on completion of all works and prior to the occupation of the development.

The Certificate shall not be issued if any conditions of this consent, but not the conditions relating to the operation of the development, are outstanding.

A copy of the Occupation Certificate and all necessary documentation supporting the issue of the Certificate is to be submitted to Penrith City Council, if Council is not the Principal Certifying Authority.

SIGNATURE

Name:	Gannon Cuneo
Signature:	

For the Development Services Manager