LENDLEASE

Jordan Springs East Stage 3C Road Safety Audit - Concept Design

JULY 2019 PUBLIC



Document Set ID: 8836444 Version: 1, Version Date: 03/09/2019



Jordan Springs East Stage 3C

Road Safety Audit - Concept Design

LENDLEASE

PUBLIC PROJECT NO 2197037A DATE: JULY 2019

WSP LEVEL 27, 680 GEORGE STREET SYDNEY NSW 2000 GPO BOX 5394 SYDNEY NSW 2001

TEL: +61 2 9272 5100 FAX: +61 2 9272 5101 WSP.COM

REV	DATE	DETAILS
	29/5/2019	Draft
А	16/07/2019	Final

	NAME	DATE	SIGNATURE
Prepared by:	Qian Liu Nicholas Reedy	16/07/2019	Q. 1. A.
Reviewed by:	Ryan Miller	16/07/2019	R. Miller
Approved by:	Ryan Miller	16/07/2019	R. Miller

This document may contain confidential and legally privileged information, neither of which are intended to be waived, and must be used only for its intended purpose. Any unauthorised copying, dissemination or use in any form or by any means other than by the addressee, is strictly prohibited. If you have received this document in error or by any means other than as authorised addressee, please notify us immediately and we will arrange for its return to us.

LENDLEASE
PUBLIC
PROJECT NO 2197037A OUR REF: 2197037A-ITP-REP-030-REVA.DOCX
JULY 2019



TABLE OF CONTENTS

1	SUMMARY	3
2	INTRODUCTION	4
2.1	Audit scope	4
2.2	Proposed design	4
2.3	Audited documentation	5
2.4	Procedures and reference material	6
2.5	Audit team	6
2.6	Responding to the audit	6
3	ROAD SAFETY AUDIT PROGRAM	7
3.1	Commencement meeting	7
3.2	Site inspection	7
3.3	Completion meeting	7
4	ROAD SAFETY AUDIT FINDINGS	8
4.1	The risk assessment system	8
4.1.1	Estimated crash frequency	8
4.1.2	Estimated crash severity	
4.1.3	Deemed level of risk	9
4.2	Road Safety Audit findings	10
5	FORMAL STATEMENT	19



_					
	CT	OE	$T\Delta$		
	ı 🦠 I	() 		$\boldsymbol{\Join}$	_ ~

TABLE 2.1	SCHEDULE OF SUPPLIED DOCUMENTS	5
TABLE 4.1	CRASH FREQUENCY	8
TABLE 4.2	CRASH SEVERITY	8
TABLE 4.3	LEVEL OF RISK	9
TABLE 4.4	ROAD SAFETY AUDIT FINDINGS	10
LIST OF F	FIGURES	
FIGURE 21	LOCATION OF STAGE 4C IN TOPDAN SPRING FAST	5

LIST OF APPENDICES

Appendix A Supplied Audit documents

Document Set ID: 8836444 Version: 1, Version Date: 03/09/2019

1 SUMMARY

Audited Project:	Jordan Springs East Stage 3C Concept Design Road Safety Audit		
Audited for:	Lendlease		
Address:	Level 2, 88 Phillip Street Parramatta NSW 2150		
Telephone:	02 9277 2566		
Project Manager:	Gareth Williams		
	Development Manager, NSW/ACT Communities		
	<u>Gareth.williams@lendlease.com</u>		
Auditors:	Ryan Miller (Level 3), Qian Liu (Level 2), Nicholas Reedy (Active Observer)		
Audit Type:	Concept Design		
Commencement Meeting:	NA		
Audit Date:	8-24 May 2019		
Completion Meeting:	ТВА		
Previous Audit:	None		

This Road Safety Audit has been commissioned by Lendlease and assessed the road design of Stage 3C in Jordan Springs East.

The audit identified eight medium risk safety issues related to the road design. The auditors also identified three 'note only' items. These issues were identified during the audit and are for the attention of the design team. There is no obligation to respond to these issues.

2 INTRODUCTION

2.1 Audit scope

The purpose of this concept design audit is to identify potential road safety issues for road users based upon the road design associated with the development of Jordan Springs East Stage 3C. The road design drawings have been prepared by Cardno for Lendlease.

2.2 Proposed design

Jordan Springs East is located within the Penrith City Council Local Government Area (LGA) and forms part of the St Mary's development site. It is bounded by existing residential development in the suburbs of Werrington County and Werrington Downs to the south, land zoned for Regional Open Space to the east, and land zoned for Regional Park to the north and west. There is also an area zoned for Drainage that adjoins the northern boundary of the precinct.

Jordan Springs East covers an area of approximately 133.1 hectares and is envisaged to hold approximately 1,400 dwellings across a total of 1,238 lots to accommodate a population between 3,900 and 4,300. It is also envisaged to accommodate approximately 760 jobs in light industrial and light manufacturing sectors.

The delivery of the Jordan Springs East Master Plan is staged. The Precinct Plan amendment (2016), currently under consideration by the Council, estimates the total yield from Jordan Springs East will be 1,436 residential dwellings, with approximately 38 hectares of employment land use.

Stage 3C proposes to consist of 59 low-density residential dwellings located towards the east of the precinct. The location of Stage 3C in the Jordan Springs East development site is presented in Figure 2.1.

WSP JULY 2019 PAGE 4



Figure 2.1 Location of Stage 3C in Jordan Spring East

2.3 Audited documentation

The following drawings prepared by Cardno were provided to the audit team:

Table 2.1 Schedule of Supplied Documents

Drawing number/ Report name	Revision	Description
CV-CARDNO-ST03C-1001	2 - 20/12/2018	Cover Sheet & Drawing Schedule
CV-CARDNO-ST03C-1011	2 - 20/12/2018	General Notes and Legends
CV-CARDNO-ST03C-1021	2 - 20/12/2018	Context Plan
CV-CARDNO-ST03C-1031	2 - 20/12/2018	General Arrangement Plan
CV-CARDNO-ST03C-1041	2 - 20/12/2018	Development Application Staging and Road Hierarchy Plan
CV-CARDNO-ST03C-1101	2 - 20/12/2018	Erosion and Sedimentation Control Plan
CV-CARDNO-ST03C-1131	2 - 20/12/2018	Erosion and Sedimentation Control Details
CV-CARDNO-ST03C-1251	2 - 20/12/2018	Typical Road Cross Sections and Pavement Details
CV-CARDNO-ST03C-1301	2 - 20/12/2018	Civil Works and Stormwater Drainage Plan
CV-CARDNO-ST03C-1351	2 - 20/12/2018	Road Longitudinal Sections Road 027, 028 and 028a

Drawing number/ Report name	Revision	Description
CV-CARDNO-ST03C-1601	2 - 20/12/2018	Civil Works Details Sheet 1
CV-CARDNO-ST03C-1602	2 - 20/12/2018	Civil Works Details Sheet 2
CV-CARDNO-ST03C-1701	2 - 20/12/2018	Pavement, Signage and Linemarking Plan
CV-CARDNO-ST03C-2201	2 - 20/12/2018	Stormwater Drainage Details Sheet 1
CV-CARDNO-ST03C-2202	2 - 20/12/2018	Stormwater Drainage Details Sheet 2
CV-CARDNO-ST03C-2301	2 - 20/12/2018	Internal Stormwater Catchment Plan

The design drawings are attached in Appendix A.

2.4 Procedures and reference material

The procedures used are those described in the *Guidelines for Road Safety Audit Practices* (Roads and Maritime Services, 2011), the *Guide to Road Safety: Part 6 Managing Road Safety Audits* (Austroads, Edition 1.0, 2019), and the *Guide to Road Safety: Part 6A Implementing Road Safety Audits* (Austroads, Edition 1.2, 2019). Other specific documents and manuals referred to during this audit were:

- Roads and Traffic Authority 1988, Road Design Guide
- Austroads 2019, Guide to Road Design: Set
- Austroads 2019, Guide to Traffic Management: Set
- Austroads 2017, Cycling Aspects of Austroads Guides
- Penrith City Council, Design Guidelines for Engineering Works for Subdivisions and Developments, November 2013
- Penrith City Council, Engineering Construction Specification for Civil Works, June 2016.

2.5 Audit team

The audit team comprised the following members:

- Ryan Miller, Level 3 lead road safety auditor
- Qian Liu, Level 2 road safety auditor
- Nick Reedy, Active observer.

2.6 Responding to the audit

An audit provides an opportunity for an independent team to highlight potential road safety problems and have them formally considered by the Project Manager in conjunction with all other project considerations. The responsibility of responding to the findings of a road safety audit rests with the Designer and/or the Project Manager, not with the Auditor(s). The Designer and/or Project Manager is under no obligation to accept the audit findings. It is also noted that it is not the role of the Auditor(s) to agree to, or approve the Project Manager's responses to the audit.

3 ROAD SAFETY AUDIT PROGRAM

3.1 Commencement meeting

A formal commencement meeting was not held on this audit. However, email correspondence took place between Dane Bryan (ADW Johnson) and WSP audit team on Wednesday 8 May 2019, outlining the audit scope and relevant audit materials.

3.2 Site inspection

The audit team did not conduct a site visit as a part of the audit. The site is currently inaccessible for such a visit to be undertaken.

3.3 Completion meeting

A completion meeting will be held as advised by the client.

PROJECT NO 2197037A
JORDAN SPRINGS EAST STAGE 3C
ROAD SAFETY AUDIT - CONCEPT DESIGN
LENDLEASE

WSP JULY 2019 PAGE 7

4 ROAD SAFETY AUDIT FINDINGS

4.1 The risk assessment system

Each hazard has been recorded and assessed in accordance with the *Guide to Road Safety:* Part 6A Implementing Road Safety Audits (Austroads, Edition 1.2, 2019). The guide recommends a risk matrix be used to determine the level of risk associated with each hazard. This matrix is described below.

4.1.1 Estimated crash frequency

The probable frequency of an incident occurring as a direct result of the hazard was determined using the criteria displayed in Table 4.1.

Table 4.1 Crash frequency

Frequency	Description			
Frequent	nce or more per week			
Probable	Once or more per year (but less than once a week)			
Occasional	Once every five or ten years			
Improbable	Less often than once every ten years			

Source: Austroads 2019, Guide to Road Safety Part 6A: Implementing Road Safety Audits

4.1.2 Estimated crash severity

The likely severity of the incident which occurred as a direct result of hazard was determined using the criteria in Table 4.2.

Table 4.2 Crash severity

Severity	Description	Examples	
Catastrophic Likely multiple deaths		High-speed, multi-vehicle crash on a freeway Car runs into crowded bus stop Bus and petrol tanker collision Collapse of a bridge or tunnel	
Serious	Likely death or serious injury	High or medium-speed vehicle collision High or medium-speed collision with a fixed roadside object Pedestrian or cyclist struck by a car	
Minor Likely minor injury		Some low-speed vehicle collisions Cyclist falls from bicycle at low speed Left-turn rear-end crash in a slip lane	
Limited	Likely trivial injury or property damage only	Some low-speed vehicle collisions Pedestrian walks into object (no head injury) Car reverses into post	

Source: Austroads 2019, Guide to Road Safety Part 6A: Implementing Road Safety Audits

WSP JULY 2019 PAGE 8 PROJECT NO 2197037A

JORDAN SPRINGS EAST STAGE 3C

ROAD SAFETY AUDIT - CONCEPT DESIGN

LENDLEASEPUBLIC

4.1.3 Deemed level of risk

The risk matrix in Table 4.3 was used to assess the level of risk for each hazard. The matrix uses the Frequency and Severity mentioned above to determine the likely level of risk for each hazard.

Table 4.3 Level of risk

	Frequent	Probable	Occasional	Improbable
Catastrophic	Intolerable	Intolerable	Intolerable	High
Serious	Intolerable	Intolerable	High	Medium
Minor	Intolerable	High	Medium	Low
Limited	High	Medium	Low	Low

Source: Austroads 2019, Guide to Road Safety Part 6A: Implementing Road Safety Audits

4.2 Road Safety Audit findings

The audit findings are documented in Table 4.4 which provides:

- Specific details of each of the audit findings identified during the audit
- A risk level rating for each of the audit findings.

In accordance with Roads and Maritime preferred practice, this road safety audit does not include recommended actions.

Table 4.4 Road Safety Audit findings

No.	Drawings/Location/ Road safety category	Description of findings	Risk rating (Frequency/ Severity)	Designer responses
1	CV-CARDNO-ST03C-1701 Road 027 Road Alignment	Parking is permitted on the inside of the curve for northbound vehicles (on Road 027). A parked car in this area restricts the visibility of oncoming southbound traffic. There increases the likelihood of head on collisions due to northbound vehicles manouvring to avoid parked cars, turning into the path of oncoming traffic. This is compunded by the narrow road width (8 m) which would need to allow for parked cars and two way articulation. TRANSITION ROLL KERB & GUITTER OVER 1m REGIO OPEN S STOPPING ALLOWED ON INSIDE OF CURVE COULD OBSTRUCT STOPPING SIGNITY OF TRANSITION ROLL KERB & GUITTER OVER 1m REGIO OPEN S TRANSITION ROLL KERB & GUITTER OVER 1m REGIO OPEN S STOPPING ALLOWED ON INSIDE OF CURVE COULD OBSTRUCT STOPPING SIGNITY OF PAVING DETAILS	Medium (Occasional/ Minor)	Noted - No parking signs to be provided.


WSP JULY 2019 PAGE 10

No.	Drawings/Location/ Road safety category	Description of findings	Risk rating (Frequency/ Severity)	Designer responses
2	CV-CARDNO-ST03C-1701 Road 027 Road Alignment	Lot 3340 is located on the inside curve for northbound vehicles (on Road 027). This provides poor sight distance for egress increasing the likelihood of vehicle collisions. AS2890.1 CL3.2.4 requires 45 m sight distance for a 50 km/h design speed. Approximately 30 m is provided at this location without the sight envelop crossing future private property.	Medium (Occasional/ Minor)	Horizontal curve radius in accordance with Penrith City Council design guidelines. No stopping signs to be provided as per Item No. 1.

No.	Drawings/Location/ Road safety category	Description of findings	Risk rating (Frequency/ Severity)	Designer responses
3	CV-CARDNO-ST03C-1701, CV-CARDNO-ST03C-1351	There is a sharp, 46 m radius horizontal curve on Road 027 (CH384.565–CH426.097). It is assumed that there is adverse crossfall in this location. This radius is likely to increase the likelihood of collisions due to northbound vehicles understeering the corner and colliding with oncoming traffic. Austroad Guide to Road Design Part 3 Section 7.states a minimum radius of 60 m is required for 3% super elevation and a design speed of 50 km/h.	Medium (Occasional/ Minor)	Horizontal curve radius in accordance with Penrith City Council design guidelines. As agreed with Penrith City Council, superelevation is not required on local streets given the low speed environment.

No.	Drawings/Location/ Road safety category	Description of findings	Risk rating (Frequency/ Severity)	Designer responses
4	CV-CARDNO-ST03C-1701 Corner of Roads 028A and 028	Where Road 028A intersects with Road 028, no provision of pram ramp has been made. This would result in access difficulty for less abled people or even tripping over.	Medium (Probable/ Limited)	Noted - Pedestrian crossing to be provided.
	Pedestrian/cyclist infrastructure	3309 3306 3307 3308 3308 3300 3300 3300 3300 3300		

No.	Drawings/Location/ Road safety category	Description of findings	Risk rating (Frequency/ Severity)	Designer responses
5	CV-CARDNO-ST03C-1701, CV-CARDNO-ST03C-1301, CV-CARDNO-ST03C-1251 Adjacent to the 90-degree angle parking Pedestrian/cyclist infrastructure	The path adjacent to the angle parking is narrow. Whilst this path is not dedicated for footpath use, pedestrians, particularly people in wheelchairs or with prams may find it difficult to access the parked vehicles. Any tow bar that overhangs this narrow path also could lead to pedestrian tripping overs. There is 1 in 6 batter adjacent to the path which appears not to be protected by any barrier. Pedestrians could fall off the batter may lead to injuries. V8 VILLAGE CENTRE LOCAL STREET PAVEMENT TYPE 2 SCALE 1:100 ROADS: 027 (CH 325-385)	Medium (Probable/ Limited)	Pedestrian paths are to be provided within the regional open space as part of a separate package of works.



PROJECT NO 2197037A

JORDAN SPRINGS EAST STAGE 3C

ROAD SAFETY AUDIT - CONCEPT DESIGN

LENDLEASE

WSP JULY 2019 PAGE 15

No.	Drawings/Location/ Road safety category	Description of findings	Risk rating (Frequency/ Severity)	Designer responses
6	CV-CARDNO-ST03C-1701 Road 027 Pedestrian/cyclist infrastructure	No allocation for disabled parking or pram ramps have been provided for on street parking provisions. This area is designated as Village centre which may make access for people with disabilities difficult. AS2890 CL4.5.1 states that a propotion of all parking should be allocated for people with disabilities.	Medium (Probable/ Limited)	Parking for people with disabilities is to be provided within stage 3D works.
7	CV-CARDNO-ST03C-1601 GPT maintenance access area Heavy vehicle infrastructure	The GPT maintenance bay is located at the road curve where driver's sight line to the approaching traffic from the north may be limited. This could result in vehicular collisions involving service vehicles.	Medium (Occasional/ Minor)	Drivers sights lines are unobstructed.

No.	Drawings/Location/ Road safety category	Description of findings	Risk rating (Frequency/ Severity)	Designer responses
8	CV-CARDNO-ST03C-1701 The southern end of Road 028 Pedestrian/cyclist infrastructure	There is no signposting to indicate the start of the shared path, facing north. Pedestrians along the footpaths of Road 028 who are not aware of the cyclists' presence, may not be able to safely transition onto the shared path. This could lead to cyclists colliding with pedestrians.	Medium (Occasional/ Minor)	Noted – Signage to be added.

No.	Drawings/Location/ Road safety category	Description of findings	Risk rating (Frequency/ Severity)	Designer responses
9	Swept paths	Swept paths for service vehicle (i.e. garbage truck) access throughout the development have not been provided for this audit. Swept path assessment should be undertaken to achieve a design of traffic devices that would ensure safe navigation, whilst managing a low-speed environment for local roads. Insufficient navigation space may lead to an increased risk of side-swipe collisions.	NOTE ONLY	
10	Drainage	No drainage report/flow depths/ponding levels are provided. Longitudinal grades at the following locations are less than 1%: — Road 027 - CH 282 to CH 497. Water on the road surface may increase the likelihood of a crash by causing aquaplaning, or reducing the friction between the pavement and a vehicle tyre. This may affect vehicles' stopping distance and directional control.	NOTE ONLY	
11	Lighting	Lighting plans have not been provided for this audit. Inadequate lighting at any designated pedestrian crossing points and intersections have the potential to increase the crash risk.	NOTE ONLY	

5 FORMAL STATEMENT

The findings and opinions in this report are based on examination of the design drawings as well as the specific road and environs, and might not address all concerns existing at the time of the audit. The Auditors have endeavoured to identify features of the design and/or the road that could be modified or removed to improve safety. It should be noted that although every effort has been made to identify potential safety hazards, no guarantee can be made that every deficiency has been identified. It must also be recognised that safety cannot be guaranteed since no road can be regarded as safe. While every effort has been made to ensure the accuracy of this report, it is made available strictly on the basis that anyone relying on it does so at their own risk, without any liability to the Auditors.

Ryan Miller

Level 3 Road Safety Auditor

Identification number: RSA-02-0223

Signature date: 29/05/2019

Nick Reedy Active observer

Identification number: RSA-02-1428

Signature date: 29/05/2019

Qian Liu

Level 2 Road Safety Auditor Identification number: RSA-02-1291

Signature date: 29/05/2019

APPENDIX A

SUPPLIED AUDIT DOCUMENTS

WSP JULY 2019 PAGE 20 PROJECT NO 2197037A JORDAN SPRINGS EAST STAGE 3C ROAD SAFETY AUDIT - CONCEPT DESIGN LENDLEASEPUBLIC



Cardno (NSW/ACT) Pty Ltd | ABN 95 001 145 035
Suite 3.01, Level 3, 3 Horwood Place
Parramatta, NSW 2150
Tel: 02 9496 7700 Fax: 02 9439 5170
Web: www.cardno.com.au

JORDAN SPRINGS EAST STAGE 3C - CIVIL WORKS DEVELOPMENT APPLICATION





SCHEDULE OF DRAWINGS

DRAWING No.

CV-CARDNO-ST03C-1001

CV-CARDNO-ST03C-1011

CV-CARDNO-ST03C-1021

CV-CARDNO-ST03C-1021

DESCRIPTION

COVER SHEET & DRAWING SCHEDULE

GENERAL NOTES & LEGENDS

CONTEXT PLAN

V-CARDNO-ST03C-1031 GENERAL ARRANGEMENT PLAN

CV-CARDNO-ST03C-1101 EROSION AND SEDIMENTATION CONTROL PLAN
CV-CARDNO-ST03C-1131 EROSION AND SEDIMENTATION CONTROL DETAILS

CV-CARDNO-ST03C-1131 EROSION AND SEDIMENTATION CONTROL DETAILS
CV-CARDNO-ST03C-1251 TYPICAL ROAD CROSS SECTIONS AND PAVEMENT DETAILS
CV-CARDNO-ST03C-1301 CIVIL WORKS AND STORMWATER DRAINAGE PLAN
CV-CARDNO-ST03C-1351 ROAD LONGITUDINAL SECTIONS ROAD 027, 028 & 028A

CV-CARDNO-ST03C-1601 CIVIL WORKS DETAILS SHEET 1
CV-CARDNO-ST03C-1602 CIVIL WORKS DETAILS SHEET 2
CV-CARDNO-ST03C-1701 PAVEMENT, SIGNAGE & LINEMARKING PLAN
CV-CARDNO-ST03C-2201 STORMWATER DRAINAGE DETAILS SHEET 1
CV-CARDNO-ST03C-2202 STORMWATER DRAINAGE DETAILS SHEET 2
CV-CARDNO-ST03C-2301 INTERNAL STORMWATER CATCHMENT PLAN

© Cardno Limited All Rights Reserved
This document is produced by Cardno Limited solely
for the benefit of and use by the client in accordance
with the terms of the retainer. Cardno Limited does no
and shall not assume any responsibility or liability
whatsoever to any third party arising out of any use o
reliance by third party on the content of this documen

d. ly ee	Drawn MCD Checked DAC Designed BJD	06 06
or nt.	Verified Approved	

| Date | 06.08.18 | Date | CV-CARDNO-ST03C-1001 | 2

GENERAL

- 1. ALL WORKS TO BE CONSTRUCTED IN ACCORDANCE WITH PENRITH CITY COUNCIL ENGINEERING CONSTRUCTION SPECIFICATION FOR CIVIL WORKS.
- 2. PENRITH CITY COUNCIL STANDARD DETAILS TO BE USED AT ALL

SITEWORKS NOTES

- 1. ORIGIN OF LEVELS:- REFER SURVEY NOTES.
- . CONTRACTOR MUST VERIFY ALL DIMENSIONS AND EXISTING LEVELS ON SITE PRIOR TO COMMENCEMENT OF WORK. ANY DISCREPANCIES TO BE REPORTED TO CARDNO.
- MAKE SMOOTH CONNECTION WITH EXISTING WORKS AND SURFACES.
- 4. ALL TRENCH BACKFILL MATERIAL SHALL BE COMPACTED TO THE SAME DENSITY AS THE ADJACENT MATERIAL.
- 5. ALL SERVICE TRENCHES UNDER VEHICULAR PAVEMENTS SHALL BE BACKFILLED WITH SAND TO 300mm ABOVE PIPE. WHERE PIPE IS UNDER PAVEMENTS BACKFILL REMAINDER OF TRENCH TO UNDERSIDE OF PAVEMENT WITH SAND OR APPROVED GRANULAR MATERIAL COMPACTED IN 150mm LAYERS TO MINIMUM 98% MODIFIED MAXIMUM DRY DENSITY IN ACCORDANCE WITH AS 1289 5.2.1. (OR A DENSITY INDEX OF NOT LESS
- 6. PROVIDE 10mm WIDE EXPANSION JOINTS BETWEEN BUILDINGS AND ALL CONCRETE OR UNIT PAVEMENTS.
- 7. ASPHALTIC CONCRETE SHALL CONFORM TO R.M.S. SPECIFICATION R116.
- 3. ALL BASECOURSE MATERIAL SHALL BE IGNEOUS ROCK QUARRIED MATERIAL TO COMPLY WITH R.M.S. FORM 3051, COMPACTED TO MINIMUM 98% MODIFIED DENSITY IN ACCORDANCE WITH AS 1289 5.2.1 FREQUENCY OF COMPACTION TESTING SHALL NOT BE LESS THAN 1 TEST PER 50m³ OF BASECOURSE MATERIAL PLACED.
-). ALL SUB-BASE COURSE MATERIAL SHALL BE IGNEOUS ROCK QUARRIED MATERIAL TO COMPLY WITH R.M.S. FORM 3051, AND COMPACTED TO MINIMUM 95% MODIFIED DENSITY IN ACCORDANCE WITH A.S 1289 5.2.1 FREQUENCY OF COMPACTION TESTING SHALL NOT BE LESS THAN 1 TEST PER 100m³ OF SUB-BASE COURSE MATERIAL PLACED.
- 10. AS AN ALTERNATIVE TO THE USE OF IGNEOUS ROCK AS A SUB-BASE MATERIAL IN (9) A CERTIFIED RECYCLED CONCRETE MATERIAL COMPLYING WITH R.M.S. FORM 3051 WILL BE CONSIDERED. SUBJECT TO MATERIAL SAMPLES AND APPROPRIATE CERTIFICATIONS BEING PROVIDED TO THE SATISFACTION OF PENRITH CITY COUNCIL AND THE SUPERINTENDENT.
- 11. A HANDRAIL OR SAFETY BARRIER IS TO BE PROVIDED AT THE TOP OF ALL HEADWALLS AND RETAINING WALLS GREATER THAN 1m HIGH IN ACCORDANCE WITH THE LENDLEASE GMR'S.

BULK EARTHWORKS NOTES

- ORIGIN OF LEVELS: REFER SURVEY NOTES
- STRIP ALL TOPSOIL/ORGANIC MATERIAL FROM CONSTRUCTION AREA AND STOCK PILE AS DIRECTED BY SUPERINTENDENT FOR FUTURE REUSE.
- EXCAVATED MATERIAL TO BE USED AS STRUCTURAL FILL PROVIDED THE PLACEMENT MOISTURE CONTENT OF THE MATERIAL IS +/- 2% OF THE OPTIMUM MOISTURE CONTENT.
- 4. COMPACT FILL AREAS AND SUBGRADE TO NOT LESS THAN:

LOCATION STANDARD DRY DENSITY (AS 1289 E 5.1.1.)

UNDER BUILDING SLABS ON GROUND UNDER ROADS AND CARPARKS

LANDSCAPED AREAS UNLESS NOTED OTHERWISE 98%

- 5. FOR NON COHESIVE MATERIAL, COMPACT TO 75% DENSITY INDEX.
- 6. BEFORE PLACING FILL, PROOF ROLL EXPOSED SUBGRADE WITH AN 8 TONNE (MIN) DEADWEIGHT SMOOTH DRUM VIBRATORY ROLLER TO DETECT THEN REMOVE SOFT SPOTS (AREAS WITH MORE THAN 2mm MOVEMENT UNDER ROLLER).
- . FREQUENCY OF COMPACTION TESTING SHALL BE NOT LESS THAN:-(A) 1 TEST PER 1,000m³ OF FILL PLACED PER LAYER OF FILL.
- (B) 3 TESTS PER VISIT

COMPACTED AS SPECIFIED

20.12.18 REISSUED FOR COORDINATION

DRAFT - ISSUED FOR COORDINATION

Description

- (C) 1 TEST PER 1000m² OF EXPOSED SUBGRADE "LEVEL 1" TESTING
- B. FILLING TO BE PLACED IN MAXIMUM 300mm LOOSE LAYERS AND

SHALL BE TESTING IN ACCORDANCE WITH AS 3798 (1996).

). NO FILLING SHALL TAKE PLACE TO EXPOSED SUBGRADE UNTIL THE AREA HAS BEEN PROOF ROLLED IN THE PRESENCE OF A SUITABLY QUALIFIED GEOTECHNICAL ENGINEER AND APPROVAL GIVEN IN WRITING THAT FILLING CAN PROCEED.

EROSION AND SEDIMENT CONTROL

NOTES

GENERAL INSTRUCTIONS

- THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR THE CONTROL OF EROSION AND SEDIMENTATION TO THE SATISFACTION OF COUNCIL, NSW OFFICE OF WATER, SYDNEY WATER, THE OFFICE OF ENVIRONMENT AND HERITAGE, AND LENDLEASE'S REPRESENTATIVE, TO THIS END. THE EROSION AND SEDIMENTATION CONTROLS SHOWN ON THE DRAWINGS SHALL ONLY BE USED AS A GUIDE BY THE CONTRACTOR, AND REPRESENT THE MINIMUM REQUIREMENT ONLY.
- THE CONTRACTOR SHALL ENSURE THAT ALL SOIL AND WATER MANAGEMENT WORKS ARE LOCATED AS DOCUMENTED OR AS OTHERWISE
- DIRECTED BY THE SUPERINTENDENT. ALL WORK SHALL BE GENERALLY CARRIED OUT IN ACCORDANCE WITH a. LOCAL AUTHORITY REQUIREMENTS
- b. EPA REQUIREMENTS c. NSW DEPARTMENT OF HOUSING MANUAL "MANAGING URBAN

MAINTAIN THE EROSION CONTROL DEVICES TO THE SATISFACTION OF THE

- STORMWATER, SOILS AND CONSTRUCTION", 4th EDITION, MARCH 2004.
- SUPERINTENDENT AND THE LOCAL AUTHORITY. WHEN STORMWATER PITS ARE CONSTRUCTED. PREVENT SITE RUNOFF

ENTERING UNLESS SEDIMENT FENCES ARE ERECTED AROUND PITS.

CONTRACTOR IS TO ENSURE ALL EROSION & SEDIMENT CONTROL DEVICE ARE MAINTAINED IN GOOD WORKING ORDER AND OPERATE EFFECTIVELY. REPAIRS AND OR MAINTENANCE SHALL BE UNDERTAKEN AS REQUIRED. PARTICULARLY FOLLOWING STORM EVENTS.

LAND DISTURBANCE

- WHERE PRACTICAL, THE SOIL EROSION HAZARD ON THE SITE WILL BE KEPT AS LOW AS POSSIBLE. TO THIS END, WORKS SHOULD BE UNDERTAKEN IN THE FOLLOWING SEQUENCE:
- a. INSTALL A SEDIMENT FENCE ALONG THE BOUNDARIES AS SHOWN ON PLAN, REFER DETAIL.
- b. CONSTRUCT STABILISED CONSTRUCTION ENTRANCE TO LOCATION AS DETERMINED BY SUPERINTENDENT/ENGINEER. REFER DETAIL. c. INSTALL SEDIMENT BASIN AS SHOWN ON PLAN (D) INSTALL SEDIMENT
- TRAPS AS SHOWN ON PLAN. d. UNDERTAKE SITE DEVELOPMENT WORKS IN ACCORDANCE WITH THE ENGINEERING PLANS. WHERE POSSIBLE, PHASE DEVELOPMENT SO THAT LAND DISTURBANCE IS CONFINED TO AREAS OF WORKABLE SIZE.

EROSION CONTROL

- DURING WINDY WEATHER, LARGE, UNPROTECTED AREAS WILL BE KEPT MOIST (NOT WET) BY SPRINKLING WITH WATER TO KEEP DUST UNDER CONTROL.
- FINAL SITE LANDSCAPING WILL BE UNDERTAKEN AS SOON AS IS PRACTICABLE AFTER THE COMPLETION OF CONSTRUCTION ACTIVITIES.

SEDIMENT CONTROL

- STOCKPILES WILL NOT BE LOCATED WITHIN 2 METRES OF HAZARD AREAS. INCLUDING LIKELY AREAS OF CONCENTRATED OR HIGH VELOCITY FLOWS SUCH AS WATERWAYS. WHERE THEY ARE BETWEEN 2 AND 5 METRES FROM SUCH AREAS, SPECIAL SEDIMENT CONTROL MEASURES SHOULD BE TAKEN TO MINIMISE POSSIBLE POLLUTION TO DOWNSLOPE WATERS, E.G. THROUGH INSTALLATION OF SEDIMENT FENCING.
- . ANY SAND USED IN THE CONCRETE CURING PROCESS (SPREAD OVER THE SURFACE) WILL BE REMOVED AS SOON AS POSSIBLE AND WITHIN 10 WORKING DAYS FROM PLACEMENT
- . WATER WILL BE PREVENTED FROM ENTERING THE PERMANENT DRAINAGE SYSTEM UNLESS IT IS RELATIVELY SEDIMENT FREE, I.E. THE CATCHMENT AREA HAS BEEN PERMANENTLY LANDSCAPED AND/OR ANY LIKELY SEDIMENT HAS BEEN FILTERED THROUGH AN APPROVED STRUCTURE.
- 2. TEMPORARY SOIL AND WATER MANAGEMENT STRUCTURES WILL BE REMOVED ONLY AFTER THE LANDS THEY ARE PROTECTING ARE REHABILITATED.
- 3. ACCEPTABLE RECEPTORS WILL BE PROVIDED FOR CONCRETE AND MORTAR SLURRIES, PAINTS, ACID WASHINGS, LIGHT-WEIGHT WASTE MATERIALS AND LITTER.
- 4. ANY EXISTING TREES WHICH FORM PART OF THE FINAL LANDSCAPING PLAN WILL BE PROTECTED FROM CONSTRUCTION ACTIVITIES BY:
- a. PROTECTING THEM WITH BARRIER FENCING OR SIMILAR MATERIALS INSTALLED OUTSIDE THE DRIP LINE
- b. ENSURING THAT NOTHING IS NAILED TO THEM
- c. PROHIBITING PAVING, GRADING, SEDIMENT WASH OR PLACING OF STOCKPILES WITHIN THE DRIP LINE EXCEPT UNDER THE FOLLOWING CONDITIONS.
- (I) ENCROACHMENT ONLY OCCURS ON ONE SIDE AND NO CLOSER TO THE TRUNK THAN EITHER 1.5 METRES OR HALF THE DISTANCE BETWEEN TH OUTER EDGE OF THE DRIP LINE AND THE TRUNK, WHICH EVER IS THE GREATER
- (II) A DRAINAGE SYSTEM THAT ALLOWS AIR AND WATER TO CIRCULATE THROUGH THE ROOT ZONE (E.G. A GRAVEL BED) IS PLACED UNDER ALL FILL LAYERS OF MORE THAN 300 MILLIMETRES DEPTH
- (III) CARE IS TAKEN NOT TO CUT ROOTS UNNECESSARILY NOR TO COMPACT THE SOIL AROUND THEM.

EPA AND COUNCIL REQUIREMENTS MUST BE ADHERED TO REGARDING LEVEL OF NOISE AND WORKING HOURS TO ENSURE THAT RESIDENTS AND OTHER APPLICABLE NEIGHBORS TO THE SITE ARE NOT DISTURBED UNREASONABLY. THE GENERATION OF NOISE MUST BE MINIMISED.

BJD

BJD

Des. Verif. Appd.

ARM

DUST MUST BE MINIMISED TO ENSURE THERE IS NO HEALTH RISK OR LOSS OF AMENITY.

STAGING OF WORKS

STRIPPING WORKS ARE TO BE STAGED TO MINIMISE EXTENT OF EXPOSED AREA. WEATHER CONDITIONS TO BE ASSESSED PRIOR TO UNDERTAKING STRIPPING

STOCKPILE PROTECTION

SEDIMENT RETENTION STRUCTURES TO BE PLACED DOWNSLOPE OF ANY STOCKPILES. STOCKPILE IN PLACE > 28 DAYS TO BE TEMPORARILY GRASSED.

VEHICLE AND ROAD MANAGEMENT

SITE ACCESS TO BE RESTRICTED TO ALLOCATED TRUCK ROUTES. EXTERNAL ROADS TO BE SWEPT REGULARLY FOR DURATION OF WORKS.

EXISTING UNDERGROUND SERVICES NOTES

THE LOCATIONS OF UNDERGROUND SERVICES SHOWN IN THIS SET OF DRAWINGS HAVE BEEN PLOTTED FROM SURVEY INFORMATION AND SERVICE AUTHORITY INFORMATION. THE SERVICE INFORMATION HAS BEEN PREPARED ONLY TO SHOW THE APPROXIMATE POSITIONS OF ANY KNOWN SERVICES AND MAY NOT BE AS CONSTRUCTED OR ACCURATE. CARDNO CAN NOT GUARANTEE THAT THE SERVICES INFORMATION SHOWN ON THESE DRAWINGS ACCURATELY INDICATES THE PRESENCE OR ABSENCE OF SERVICES OR THEIR LOCATION AND WILL ACCEPT NO LIABILITY FOR INACCURACIES IN THE SERVICES INFORMATION SHOWN FROM ANY CAUSE WHATSOEVER.

CONTRACTORS SHALL TAKE DUE CARE WHEN EXCAVATING ONSITE INCLUDING HAND EXCAVATION WHERE NECESSARY. CONTRACTORS ARE TO CONTACT THE RELEVANT SERVICE AUTHORITY PRIOR TO COMMENCEMENT OF EXCAVATION WORKS. CONTRACTORS ARE TO UNDERTAKE A SERVICES SEARCH, PRIOR TO COMMENCEMENT OF WORKS ON SITE. SEARCH RESULTS ARE TO BE KEPT ON SITE AT ALL TIMES.

STORMWATER DRAINAGE NOTES

- STORMWATER DESIGN CRITERIA: (A) AVERAGE RECURRENCE INTERVAL:
- 5 YEAR ARI PIPED DRAINAGE 100 YEAR ARI OVERLAND FLOW
- (B) RAINFALL INTENSITIES: TIME OF CONCENTRATION:
- 5 YEAR ARI= 126mm/hr 100 YEAR ARI= 219mm/hr

5 MINUTES

- PIPES 375 DIA. AND LARGER TO BE REINFORCED CONCRETE CLASS '2' APPROVED SPIGOT AND SOCKET WITH RUBBER RING JOINTS. U.N.O.
- PIPES 300 DIA AND LESS SHALL BE DWV GRADE (CLASS SN8) uPVC WITH SOLVENT WELDED JOINTS.
- . EQUIVALENT STRENGTH FRC PIPES MIN CLASS 3 MAY BE USED SUBJECT TO PRIOR APPROVAL BY PENRITH CITY COUNCIL.
- ALL PIPES ARE TO BE UNIFORMLY SUPPORTED ALONG THE LENGTH OF THE BARREL BY SUITABLE FILL MATERIAL. REFER TO BEDDING SUPPORT
- PIPES WITH SOCKETS SHALL BE LAID IN BEDDING WHERE SUITABLE RECESSES HAVE BEEN PROVIDED TO ENSURE PIPES DO NOT BEAR ON THEIR SOCKETS.
- PIPES TO BE INSTALLED TO TYPE HS1 SUPPORT IN ACCORDANCE WITH AS 3725 (2007) IN ALL CASES BACKFILL TRENCH WITH SAND TO 300mm ABOVE PIPE. WHERE PIPE IS UNDER PAVEMENTS BACKFILL REMAINDER OF TRENCH TO UNDERSIDE OF PAVEMENT WITH SAND OR APPROVED GRANULAR MATERIAL COMPACTED IN 150mm LAYERS TO MINIMUM 98% STANDARD MAXIMUM DRY DENSITY IN ACCORDANCE WITH AS 1289 5.2.1. (OR A DENSITY INDEX OF NOT LESS THAN 75).
- REFER TO AS/NZS 3725:2007 TABLE B1 FOR REQUIRED FILL DEPTHS ABOVE PIPE BARREL PRIOR TO USE OF COMPACTION MACHINERY OR TRAVERSING OF PIPES BY GENERAL SITE EQUIPMENT.
- WHERE WORKING METHODS REQUIRE HIGHER CLASS PIPE, THE CONTRACTOR SHALL REFER TO AS 3725 (2007) TO DETERMINE THE APPROPRIATE PIPE CLASS. PROPOSED PIPE CLASS SHALL BE REVIEWED BY CARDNO PRIOR TO INSTALLATION.
- 0. ALL INTERNAL WORKS WITHIN PROPERTY BOUNDARIES ARE TO COMPLY WITH THE REQUIREMENTS OF AS 3500.3 (2015).
- 1. THE USE OF PRECAST PITS IS ONLY PERMITTED WITH THE PRIOR APPROVAL OF PENRITH CITY COUNCIL.
- 2. ENLARGERS, CONNECTIONS AND JUNCTIONS TO BE PREFABRICATED FITTINGS WHERE PIPES ARE LESS THAN 300 DIA.
- 13. WHERE SUBSOIL DRAINS PASS UNDER FLOOR SLABS AND VEHICULAR PAVEMENTS, UNSLOTTED uPVC DWV SEWER GRADE PIPE IS TO BE USED.
- SHOWN ARE NOT TO BE REDUCED WITHOUT APPROVAL. 5. GRATES AND COVERS SHALL CONFORM TO AS 3996. MINIMUM CLASS C.

14. CARE IS TO BE TAKEN WITH LEVELS OF STORMWATER LINES. GRADES

6. ALL BOX CULVERTS SHALL BE STRUCTURALLY DESIGNED BY THE MANUFACTURER AND DELIVERED TO SITE AS FIT FOR PURPOSE.

UNLESS NOTED OTHERWISE.

7. AT ALL TIMES DURING CONSTRUCTION OF STORMWATER PITS. ADEQUATE SAFETY PROCEDURES SHALL BE TAKEN TO ENSURE AGAINST THE POSSIBILITY OF PERSONNEL FALLING DOWN PITS.

STORMWATER DRAINAGE NOTES

CONTINUED

18. ALL EXISTING STORMWATER DRAINAGE LINES AND PITS THAT ARE TO REMAIN ARE TO BE INSPECTED AND CLEANED. DURING THIS PROCESS ANY PART OF THE STORMWATER DRAINAGE SYSTEM THAT WARRANTS REPAIR SHALL BE REPORTED TO THE SUPERINTENDENT/ENGINEER FOR FURTHER DIRECTIONS.

TELSTRA - DUTY OF CARE NOTE

TELSTRA'S PLANS SHOW ONLY THE PRESENCE OF CABLES AND PLANT. THEY ONLY SHOW THEIR POSITION RELATIVE TO ROAD BOUNDARIES. PROPERTY FENCES ETC. AT THE TIME OF INSTALLATION AND TELSTRA DOES NOT WARRANT OR HOLD OUT THAT SUCH PLANS ARE ACCURATE THEREAFTER DUE TO CHANGES THAT MAY OCCUR OVER TIME. DO NOT ASSUME DEPTH OR ALIGNMENT OF CABLES OR PLANT AS THESE VARY SIGNIFICANTLY. THE CONTRACTOR HAS A DUTY OF CARE WHEN EXCAVATING NEAR TELSTRA CABLES AND PLANT. BEFORE USING MACHINE EXCAVATORS TELSTRA PLANT MUST FIRST BE PHYSICALLY EXPOSED BY SOFT DIG POTHOLING TO IDENTIFY IT'S LOCATION TELSTRA WILL SEEK COMPENSATION FOR DAMAGES CAUSED TO IT'S PROPERTY AND LOSSES CAUSED TO TELSTRA AND IT'S

SURVEY NOTES

THE EXISTING SITE CONDITIONS SHOWN ON THE FOLLOWING DRAWINGS HAVE BEEN INVESTIGATED BY RPS GROUP PLC (FORMERLY WHELANS INSITES), BEING REGISTERED SURVEYORS. THE INFORMATION IS SHOWN TO PROVIDE A BASIS FOR DESIGN. CARDNO DOES NOT GUARANTEE THE ACCURACY OR COMPLETENESS OF THE SURVEY BASE OR ITS SUITABILITY AS A BASIS FOR CONSTRUCTION DRAWINGS.

SHOULD DISCREPANCIES BE ENCOUNTERED DURING CONSTRUCTION BETWEEN THE SURVEY DATA AND ACTUAL FIELD DATA, CONTACT CARDNO.

THE FOLLOWING NOTES HAVE BEEN TAKEN DIRECTLY FROM THE ORIGINAL SURVEY DOCUMENTS. ORIGIN OF MGA BASED SITE CO-ORDINATES FROM PM 147113 AND

147113 HAVE BEEN ADOPTED AS 292202.160E 6266005.820N

- PLANE DISTANCES HAVE BEEN USED. CO-ORDINATES FOR PM 147113 WERE DEDUCED BY WHELANS FROM SUROUNDING SSM & PM'S ON PUBLIC RECORD. CO-ORDINATES FOR PM
- 3. CONTOUR INTERVAL 0.25m

CUSTOMERS.

- 4. LEVELS ARE BASED ON AUSTRALIAN HEIGHT DATUM (AHD) USING SSM 79753 WITH RL OF 19.758 (ACC 2) LOCATED ON LINKS ROAD.
- FEATURES SHOWN INCLUDING TREES AND LEVELS ARE TO BE USED ONLY FOR CONCEPT PLANNING DESIGN. DATA SHOWN SHOULD NOT BE USED FOR CONSTRUCTION PURPOSES. PRIOR TO CONSTRUCTION ANY FEATURE OR LEVEL SHOULD BE VERIFIED IF THE LOCATION OR HEIGHT
- 6. TREES SHOWN HAVE A TRUNK DIAMETER OF 300MM OR GREATER.

IS TO HAVE SIGNIFICANT IMPACT ON DESIGN OR CONSTRUCTION.

TREE CAPTURE CONFIDENCE INTERVAL OF 99%

ROOF WATER KERB OUTLETS

- KERB OUTLETS TO BE PROVIDED IN ACCORDANCE WITH PENRITH CITY COUNCILS CIVIL WORKS SPECIFICATION AT EACH LOT WHERE
- 2. KERB OUTLETS ARE TO BE CONSTRUCTED AT THE SAME TIME KERBS ARE POURED.

INTERALLOTMENT DRAINAGE IS NOT PROVIDED

ALIGNMENT OF KERB OUTLET PIPE TO BE ADJUSTED ON SITE TO AVOID SERVICE CLASHES.

STREET FURNITURE

- ALL LIGHT POLES, STREET NAMES AND BUS SHELTERS IN THIS SUBDIVISION WILL BE GALVANISED BLACK POWDER COATED TO THE SATISFACTION OF PENRITH CITY COUNCIL. FURTHER THAT THESE LIGHT POLES WILL COMPLY WITH COUNCIL'S SPECIFICATIONS.
- ALL LIGHT POLES ARE TO BE TYPE 'MACARTHUR'. REFER ELECTRICAL DESIGN DRAWINGS.

REINFORCEMENT NOTES

- REINFORCEMENT IS REPRESENTED DIAGRAMMATICALLY. IT IS NOT NECESSARILY SHOWN IN TRUE PROJECTION.
- SPLICES IN THE REINFORCEMENT SHALL BE MADE ONLY IN THE POSITIONS SHOWN. THE WRITTEN APPROVAL OF THE ENGINEER SHALL BE OBTAINED FOR ANY OTHER SPLICES. WHERE THE LAP LENGTH IS NOT SHOWN IT SHALL BE SUFFICIENT TO DEVELOP THE FULL STRENGTH OF THE REINFORCEMENT.
- WELDING OF REINFORCEMENT WILL NOT BE PERMITTED UNLESS SHOWN ON THE STRUCTURAL DRAWINGS OR APPROVED IN WRITING BY THE
- **REINFORCEMENT SYMBOLS -**
- N DENOTES GRADE 400N TEMPCORE DEFORMED BARS TO AS 1302 R - DENOTES GRADE 250R HOT ROLLED PLAIN BARS TO AS 1302 SL - DENOTES HARD-DRAWN WIRE REINFORCING FABRIC TO AS 1304
- W DENOTES HARD-DRAWN PLAIN WIRE TO AS 1303 REINFORCEMENT COGS AND EXTENSIONS TO BE IN ACCORDANCE WITH
 - NUMBER OF BARS IN GROUP -BAR GRADE AND TYPE NOMINAL BAR SIZE IN mm
- THE FIGURES FOLLOWING THE FABRICS SYMBOL 'SL' IS THE REFERENCE NUMBER FOR FABRIC TO AS 1304. ALL REINFORCEMENT FABRIC SHALL COMPLY WITH AS1303 AND AS1304 AND SHALL BE SUPPLIED AS FLAT SHEETS.
 - 25 MIN. TYPICAL FABRIC LAP
- BUNDLED BARS SHALL BE TIED TOGETHER AT 30 BAR DIAMETER CENTRES WITH 3 WRAPS OF WIRE. PLACE SUFFICIENT BAR CHAIRS UNDER BOTTOM REINFORCING RODS AND TOP CROSSRODS IN SLABS TO ALLOW THEM TO BE SUPPORTED IN THEIR CORRECT POSITIONS DURING CONCRETING (NOT GREATER

FABRIC SHALL BE LAPPED 2 TRANSVERSE WIRES PLUS 50mm.

- THAN 900mm CENTRES BOTH WAYS) REINFORCEMENT LAYERS DENOTED THUS UNO -TT - DENOTES TOP BARS LAID LAST IN TOP - DENOTES TOP BARS LAID FIRST IN TOP B - DENOTES BOTTOM BARS LAID SECOND IN BOTTOM
- BB DENOTES BOTTOM BARS LAID FIRST IN BOTTOM WHERE TRANSVERSE TIE BARS ARE NOT SHOWN PROVIDE N12-300 SPLICED WHERE NECESSARY AND LAP WITH MAIN BARS 450mm UNLESS NOTED OTHERWISE.
- MINIMUM LAP LENGTHS UNLESS NOTED OTHERWISE SHALL BE -500 FOR N12 BARS 600 FOR N16 BARS
- 900 FOR N20 BARS 1000 FOR N24 BARS 1200 FOR N28 BARS 1500 FOR N32 BARS

1800 FOR N36 BARS

CONCRETE NOTES

- ALL WORKMANSHIP AND MATERIALS SHALL BE IN ACCORDANCE WITH AS 3600 CURRENT EDITION WITH AMENDMENTS, EXCEPT WHERE VARIED BY THE CONTRACT DOCUMENTS.
- CONCRETE QUALITY ALL REQUIREMENTS OF THE CURRENT ACSE CONCRETE SPECIFICATION DOCUMENT 1 SHALL APPLY TO THE FORMWORK, REINFORCEMENT AND

С	CONCRETE UNLESS NOTED OTHERWISE.					
	ELEMENT	AS 3600 F'c MPa	SPECIFIED	NOMINAL		
		AT 28 DAYS	SLUMP	AGG. SIZE		
	VEHICULAR BASE	32	60	20		
	KERBS AND PATHS	25	80	20		
	PITS, FOUNDATIONS &	40	80	20		
	CHIVERT BASE SLARS					

- CEMENT TYPE SHALL BE (ACSE SPECIFICATION) TYPE SL - PROJECT CONTROL TESTING SHALL BE CARRIED OUT IN ACCORDANCE WITH
- NO ADMIXTURES SHALL BE USED IN CONCRETE UNLESS APPROVED IN WRITING BY CARDNO.
- CLEAR CONCRETE COVER TO ALL REINFORCEMENT FOR DURABILITY SHALL BE 40mm TOP AND 70mm FOR EXTERNAL EDGES UNLESS NOTED OTHERWISE ALL REINFORCEMENT SHALL BE FIRMLY SUPPORTED ON MILD STEEL
- ALTERNATE INTERSECTIONS. THE FINISHED CONCRETE SHALL BE A DENSE HOMOGENEOUS MASS, COMPLETELY FILLING THE FORMWORK, THOROUGHLY EMBEDDING THE REINFORCEMENT AND FREE OF STONE POCKETS. ALL CONCRETE INCLUDING SLABS ON GROUND AND FOOTINGS SHALL BE COMPACTED AND CURED IN ACCORDANCE WITH R.T.A. SPECIFICATION R83.

GREATER THAN 1m CENTRES BOTH WAYS. BARS SHALL BE TIED AT

PLASTIC TIPPED CHAIRS, PLASTIC CHAIRS OR CONCRETE CHAIRS AT NOT

EXTENT OF WORKS EXISTING STAGING BOUNDARY TREES TO BE REMOVED AS PART OF BULK EARTHWORKS PACKAGE. TREES TO BE RETAINED LOT NUMBERS **KERB & GUTTER** K&G REFER PENRITH CITY COUNCIL STANDARD DETAIL. **ROLL KERB & GUTTER** RK&G REFER PENRITH CITY COUNCIL STANDARD DETAIL. DISH DRAIN DD REFER PENRITH CITY COUNCIL STANDARD DETAIL KERB ONLY KO REFER PENRITH CITY COUNCIL STANDARD DETAIL. PRAM RAMP REFER PENRITH CITY COUNCIL FOR DETAIL. INDICATIVE GARAGE/DRIVEWAY **LOCATION ONLY** STORMWATER PIPELINE STORMWATER DRAINAGE PITS CONCRETE HEADWALL DRAINAGE LINE No. 4\2 DRAINAGE PIT No. **ROOF WATER KERB OUTLET**

PROPOSED WORKS LEGEND

SITE BOUNDARY

BATTER SLOPE

— · · − 100.0 · − · · — PROPOSED CONTOURS

EXISTING WORKS LEGEND TRANSGRID PYLON EXISTING CONTOURS -··- 10 0.0 · - · · -TRANSGRID EASEMENT TRANSGRID OVERHEAD ______ e ____ ELECTRICAL **EXISTING SEWER**

EXISTING WATER COURSES AS

SCOUR PROTECTION

PER 1:10000 TOPOGRAPHIC MAPS



© Cardno Limited All Rights Reserved. This document is produced by Cardno Limited solely for the benefit of and use by the client in accordance with the terms of the retainer. Cardno Limited does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.



Suite 3.01, Level 3, 3 Horwood Place

Parramatta, NSW 2150

Tel: 02 9496 7700 Fax: 02 9439 5170


Web: www.cardno.com.au


06.08.18 06.08.18 Verified Approved


LENDLEASE 06.08.18 JORDAN SPRINGS EAST FOR INFORMATION ONLY STAGE 3C - CIVIL WORKS NOT TO BE USED FOR CONSTRUCTION PURPOSES DEVELOPMENT APPLICATION AHD GENERAL NOTES & LEGENDS CV-CARDNO-ST03C-1011 06.08.18


06.08.18


Date











lendlease

© Cardno Limited All Rights Reserved.

This document is produced by Cardno Limited solely for the

benefit of and use by the client in accordance with the terms of the retainer. Cardno Limited does not and shall not

assume any responsibility or liability whatsoever to any third

party arising out of any use or reliance by third party on the

content of this document.

Date 06.08.18 Client LENDLEASE Drawn MCD **Cardno**[®] Project JORDAN SPRINGS EAST FOR INFORMATION ONLY
NOT TO BE USED FOR CONSTRUCTION PURPOSES 06.08.18 Date 06.08.18 STAGE 3C - CIVIL WORKS **Shaping the Future** DEVELOPMENT APPLICATION Verified Date Cardno (NSW/ACT) Pty Ltd | ABN 95 001 145 035 AHD AS SHOWN A1 **EROSION AND SEDIMENTATION CONTROL** Suite 3.01, Level 3, 3 Horwood Place Approved Parramatta, NSW 2150 DETAILS CV-CARDNO-ST03C-1131 Tel: 02 9496 7700 Fax: 02 9439 5170 Web: www.cardno.com.au 06.08.18

STAPLES ON TOP EDGE TO HOLD CLOTH

SEDIMENT FENCE

(GEOTEXTILE FILTER FABRIC & STRAW BALE)

NOT TO SCALE

CHECK DAM - STRAW BALE

ALLOW SUFFICIENT

SPILLWAY CAPACITY

1.2m STAR PICKET DRIVEN 0.6m INTO THE GROUND

GRAVEL (OPTIONAL)

DRAINAGE AREA 0.8ha MAX

SPILLWAY AT LEAST 0.15m BELOW SIDES

HEIGHT 0.6M MAX

DISTURBED

AREA

ANGLE FIRST STAKE TOWARDS PREVIOUSLY LAID STRAW BALE

— NYLON OR WIRE BINDINĞS

UNDISTURBED

AREA

06.08.18

Date

20.12.18 REISSUED FOR COORDINATION

DRAFT - ISSUED FOR COORDINATION


Description


BJD

BJD

Des. Verif. Appd.


ARM






PAVEMENT TYPE 2

SCALE 1:100




V8 VILLAGE CENTRE LOCAL STREET PAVEMENT TYPE 2 SCALE 1:100

ROADS: 027 (CH 325-385)







PAVEMENT TYPE 2

7mm SINGLE COAT FLUSH SEAL BASE COURSE DGB20 COMPACTED TO MINIMUM MODIFIED DENSITY RATIO OF 98% SUB BASE DGS40 COMPACTED TO MINIMUM MODIFIED DENSITY RATIO OF 95%


50mm AC10 WEARING COURSE (2x25mm AC10) FINAL 25mm LAYER TO BE CONSTRUCTED AFTER

ROADS: 027 (CH301-325, CH385-425, CH467-478)

COMPACTED SUBGRADE TO MINIMUM DENSITY RATIO OF 100%

ASSUMED CBR: REFER TABLE BELOW ASSUMED ESA: 5x10⁴

PAVEMENT 2 DESIGN				
DESIGN SUBGRADE	CBR 3%	CBR 5%		
WEARING SURFACE	50mm AC10	50mm AC10		
SINGLE COAT FLUSH SEAL	7mm	7mm		
BASECOURSE	150mm	150mm		
SUBBASE	275mm	175mm		
TOTAL THICKNESS	475mm	375mm		




NOTES

APPROVAL.

STREET SCAPES SHOWN ARE INDICATIVE ONLY AND SUBJECT TO DETAILED LANDSCAPING DESIGN AND

NOTE PROVIDE TCJ AT 4m SPACING. EVERY THIRD JOINT TO BE DEJ. REFER DRAWING 1601 FOR JOINT DETAILS




NOTES 1. SAWCUT PATH OR TROWELLED DUMMY JOINT AT 2m SPACING. 2. EVERY THIRD JOINT TO BE FULL DEPTH DOWELLED EXPANSION JOINT. 3. REFER DRAWING 1601 FOR JOINT DETAILS.


BJD

BJD

Des. Verif. Appd.



ARM



lendlease

© Cardno Limited All Rights Reserved. This document is produced by Cardno Limited solely for the benefit of and use by the client in accordance with the terms of the retainer. Cardno Limited does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.



	Shaping the Future
Cardno (NSW	ACT) Pty Ltd ABN 95 001 145 035
Suite 3.	01, Level 3, 3 Horwood Place
F	Parramatta, NSW 2150
Tel: 02 9	9496 7700 Fax: 02 9439 5170
W	eb: www.cardno.com.au


			SCALE 1:100	@A1
wn CD	06.08.18	Client LENDLEASE		
ecked AC signed JD	Date 06.08.18 Date 06.08.18	Project JORDAN SPRINGS EAST STAGE 3C - CIVIL WORKS	Status FOR INFORMATION NOT TO BE USED FOR CONSTR	
ified	Date	DEVELOPMENT APPLICATION Title TYPICAL ROAD CROSS SECTIONS	Datum Scale AHD AS SH	HOWN Size A1
proved		AND PAVEMENT DETAILS	Drawing Number CV-CARDNO-ST03C-	Revision
RM	06.08.18		0 0/1/10/00	1201 2

Date


20.12.18 REISSUED FOR COORDINATION

06.08.18 DRAFT - ISSUED FOR COORDINATION

Description




EXISTING LEVELS SHOWN ARE PRE BULK EARTHWORKS. PRIOR TO THE COMMENCEMENT OF CIVIL WORKS, THE BULK EARTHWORKS CONTRACTOR WILL COMPLETE BULK EARTHWORKS OPERATIONS, WHICH INCLUDES FINISHED SURFACE LEVELS EXCEPT FOR AREAS WITHIN THE ROAD THE RESERVE. IN AREAS OF FILL, THE CIVIL CONTRACTOR WILL RECEIVE SUB-GRADE LEVEL +100mm. IN AREAS OF CUT, THE CIVIL CONTRACTOR WILL RECEIVE SUB-GRADE LEVELS. STAGE 5B WORKS STAGE 3D WORKS R300 HORIZONTAL 35m VC 15m VC VC LENGTH -0.7% **GRADE** DATUM RL 13 WAE LEVEL DESIGN LEVEL **EXISTING SURFACE** CHAINAGE 299.t 300.(281. 282. 285. **ROAD 027 LONGITUDINAL SECTION** 1:100 VERT. R150.3 R20 HORIZONTAL HORIZONTAL VC LENGTH VC LENGTH -1.4% GRADE GRADE DATUM RL 12 DATUM RL 13 WAE LEVEL WAE LEVEL 20.880 20.882 20.882 20.893 20.968 21.001 DESIGN LEVEL DESIGN LEVEL EXISTING SURFACE 18.999 18.990 18.988 18.981 18.991 18.964 EXISTING SURFACE CHAINAGE CHAINAGE 11.820 14.320 15.000 19.320 **ROAD 028A LONGITUDINAL SECTION** ROAD 028 LONGITUDINAL SECTION 1:500 HORI. 1:100 VERT. 1:500 HORI. 1:100 VERT. SCALE 1:500 Date 06.08.18 Client LENDLEASE **Cardno**[®] © Cardno Limited All Rights Reserved. Project JORDAN SPRINGS EAST 06.08.18 lendlease This document is produced by Cardno Limited solely for the STAGE 3C - CIVIL WORKS NOT TO BE USED FOR CONSTRUCTION PURPOSES benefit of and use by the client in accordance with the 06.08.18 DEVELOPMENT APPLICATION terms of the retainer. Cardno Limited does not and shall no Verified assume any responsibility or liability whatsoever to any third Cardno (NSW/ACT) Pty Ltd | ABN 95 001 145 035 AS SHOWN AHD ROAD LONGITUDINAL SECTIONS Suite 3.01, Level 3, 3 Horwood Place party arising out of any use or reliance by third party on the BJD REISSUED FOR COORDINATION Parramatta, NSW 2150 content of this document. ROAD 027, 028 & 028A BJD ARM DRAFT - ISSUED FOR COORDINATION 06.08.18 CV-CARDNO-ST03C-1351 Tel: 02 9496 7700 Fax: 02 9439 5170 Des. Verif. Appd. Web: www.cardno.com.au 06.08.18 Date Description




GPT MAINTENANCE ACCESS AREA

ROAD 027


SCALE 1:250




TRANSVERSE CONTRACTION JOINT (TCJ)



DETAIL A



DOWELED EXPANSION JOINT (DEJ) SCALE 1:10



CONCRETE GPT MAINTENANCE BAY PLAN SCALE 1:100

© Cardno Limited All Rights Reserved.

This document is produced by Cardno Limited solely for the benefit of and use by the client in accordance with the terms of the retainer. Cardno Limited does not and shall not

assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.





Cardno (NSW/ACT) Pty Ltd ABN 95 001 145 035
Suite 3.01, Level 3, 3 Horwood Place
Parramatta, NSW 2150
Tel: 02 9496 7700 Fax: 02 9439 5170
Web: www.cardno.com.au

		00,122 1.200	
06.08.18	Client LENDLEASE		
Date 06.08.18 Date 06.08.18	Project JORDAN SPRINGS EAST STAGE 3C - CIVIL WORKS	Status FOR INFORMA NOT TO BE USED FOR COM	
Date	DEVELOPMENT APPLICATION Title CIVIL WORKS DETAILS		Scale Size A1
	SHEET 1	Drawing Number	Revision
00.00.40	SHEET	CV-CARDNO-ST	03C-1601 2


						Γ
						İ
						İ
						İ
						İ
						İ
2	20.12.18	REISSUED FOR COORDINATION	BJD		ARM	
1	06.08.18	DRAFT - ISSUED FOR COORDINATION	BJD		ARM	
Rev.	Date	Description	Des.	Verif.	Appd.	

lendlease






TRENCH EXCAVATION
SCALE 1:25







TYPICAL SURFACE UTILITY LAYOUT
(LIGHT COLUMN AND ELECTRICAL PILLAR)



				!	
2	20.12.18	REISSUED FOR COORDINATION	BJD		ARM
1	06.08.18	DRAFT - ISSUED FOR COORDINATION	BJD		ARM
lev.	Date	Description	Des.	Verif.	Appd.

lendlease


© Cardno Limited All Rights Reserved.


This document is produced by Cardno Limited solely for the benefit of and use by the client in accordance with the terms of the retainer. Cardno Limited does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.





Cardno (NSW/ACT) Pty Ltd ABN 95 001 145 035
Suite 3.01, Level 3, 3 Horwood Place
Parramatta, NSW 2150
Tel: 02 9496 7700 Fax: 02 9439 5170
Web: www.cardno.com.au


	SOALL	. 1.25		WA1	
Date Client 06.08.18	LENDLEASE				
ed Date 9	JORDAN SPRINGS EAST STAGE 3C - CIVIL WORKS	FOR INFORMATION NOT TO BE USED FOR CONSTRUCT			
Date Till	DEVELOPMENT APPLICATION CIVIL WORKS DETAILS		Scale Size AS SHOWN	A1	
ed	SHEET 2	Drawing Number CV-CARDNO-ST	03C-1602	Revision 2	



















INTERALLOTMENT DRAINAGE PIT

SCALE 1:20





NON PENRITH CITY COUNCIL STANDARD STORMWATER PIT

IMPORTANT NOTE: PIT STANDARD DETAILS

PENRITH COUNCIL STANDARD GRATED GULLY PITS DETAIL, SD2001 TO BE USED FOR PIT DETAILS WHERE:

A. PIT INTERNAL WIDTH IN ANY DIRECTION IS LESS THAN OR EQUAL TO 1200mm, AND B. PIT DEPTH FROM SETOUT POINT TO INVERT IS LESS THAN OR EQUAL TO 2000mm.

FOR PITS WIDER THAN 1200mm AND/OR DEEPER THAN 2000mm REFER TO THE BELOW TABLE AND DETAILS.

NON PCC STORMWATER PIT REINFORCEMENT SCHEDULE						JLE	
PIT DIMENSIONS(mm)		WALL DIMEN	IENSIONS(mm) VERTICAL		HORIZONTAL	BASE	
LENGTH 'X','Y'	DEPTH 'H'	BASE THICKNESS 'D'	WALL THICKNESS 'W'	REINFORCEMENT		REINFORCEMENT	
1200 <x,y<3300< td=""><td>2000<h<3900< td=""><td>230</td><td>230</td><td>N12-200 E.F.</td><td>N12-200 E.F.</td><td>N12-200 E.F.</td></h<3900<></td></x,y<3300<>	2000 <h<3900< td=""><td>230</td><td>230</td><td>N12-200 E.F.</td><td>N12-200 E.F.</td><td>N12-200 E.F.</td></h<3900<>	230	230	N12-200 E.F.	N12-200 E.F.	N12-200 E.F.	
X,Y<1200	H<6000	230	230	N16-250 E.F.	N16-250 E.F.	N16-250 E.F.	

NOTES:

- PIT REINFORCEMENT TO BE SELECTED USING MAXIMUM PIT DIMENSION.
- MINIMUM COVER TO REINFORCING AND CONCRETE STRENGTH AS SPECIFIED ON SHEET 1011.


DEFLECTION ANGLE GREATER THAN 45° (SIDE OF PIT)

PIT ALIGNMENT REQUIREMENTS

TYPICAL DETAILS OF STORMWATER PIPE OR CULVERT ALIGNMENTS THROUGH STORMWATER PITS. STORMWATER PIPE OR CULVERT ALIGNMENTS NOT SHOWN SHOULD BE CONSTRUCTED SIMILARLY IN ORDER TO STREAMLINE FLOWS FROM UPSTREAM TO DOWNSTREAM AND MINIMISE HEADLOSS.

	LENGTH 'X','Y'	DEPTH 'H'	THICKNESS 'D'	WALL THICKNESS 'W'	REINFORCEMENT	REINFORCEMEN	
	1200 <x,y<3300< td=""><td>2000<h<3900< td=""><td>230</td><td>230</td><td>N12-200 E.F.</td><td>N12-200 E.F.</td></h<3900<></td></x,y<3300<>	2000 <h<3900< td=""><td>230</td><td>230</td><td>N12-200 E.F.</td><td>N12-200 E.F.</td></h<3900<>	230	230	N12-200 E.F.	N12-200 E.F.	
	X,Y<1200	H<6000	230	230	N16-250 E.F.	N16-250 E.F.	
NOTE: DIT DEINIGODOEMENT TO DE SELECTED LISING MAZIMLIM DIT DIMENSIONI							

NOTE: PIT REINFORCEMENT TO BE SELECTED USING MAXIMUM PIT DIMENSION





© Cardno Limited All Rights Reserved. This document is produced by Cardno Limited solely for the benefit of and use by the client in accordance with the terms of the retainer. Cardno Limited does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.



Cardno (NSW/ACT) Pty Ltd ABN 95 001 145 035
Suite 3.01, Level 3, 3 Horwood Place
Parramatta, NSW 2150
Tel: 02 9496 7700 Fax: 02 9439 5170
Web: www.cardno.com.au

			SUALE 1.20	WA1
rawn MCD	Date 06.08.18	Client LENDLEASE		
necked DAC	Date 06.08.18	Project JORDAN SPRINGS EAST	Status FOR INFORM	MATION ONLY
esigned BJD	Date 06.08.18	OTAGE OF OTTIE WORKS		ONSTRUCTION PURPOSES
erified	Date	DEVELOPMENT APPLICATION Title STORMWATER DRAINAGE DETAILS	Datum AHD	Scale Size A1
pproved		STORMWATER DRAINAGE DETAILS SHEET 2	Drawing Number	Revision
ARM	06.08.18	•··· = · ·	CV-CARDNO-S1	Γ03C-2202 2

Document Set ID: 8836444 Version: 1, Version Date: 03/09/2019

