

SWP Ref: 1505626 Date: 25 July 2016

SWP Ref: 1505626

OPERATIONAL ENVIRONMENTAL MANAGEMENT PLAN (OEMP)

65-73 Dunheved Circuit, St Marys NSW 2760

Lot 1 DP 117580

Revision History

Revision	Date	Reason for Issue
A	25/07/2015	Issued for Development Application
<u>u</u>		









SWP Ref: 1505626 Date: 25 July 2016

Contents

1.]	Introduction	3
	1.1. 1.2.	Background	3
	0	ocationperational Activitiesours of Operation	5
,	1.3.	OEMP Context	5
	Α	pplicable Legislation	5
	1.4.	OEMP Objectives	7
2.	I	Environmental Management Program	7
	2.1. 2.2. 2.3. 2.1. 2.2. 2.3.	Operational Phase Environmental Issues Roles and Responsibility Complaints Response Procedure Non Conformance Register Regular Document Review	
3.	ı	Implementation	10
	3.1. 3.1.		
	N Tı	ir quality Control Measuresoise Management Control Measuresransport and Traffic Management and Site Access Control Measures/aste Management Control Measures	12 13
4.	(Closure	16







SWP Ref: 1505626 Date: 25 July 2016

Introduction 1.

1.1. Background

The Operation Environmental Management Plan (OEMP) has been prepared in assisting the Development Application (DA) for the establishment of a landscape supplies production facility at Lot 1, 65-73 Dunheved Circuit, St Marys NSW 2760.

This OEMP aims to provide clear direction on the selection and implementation of appropriate environmental control and monitoring techniques for the facility's operations.

In order to ensure that the facility operates with the least environmental impact, this OEMP addresses the following relevant environmental issues:

- Air quality Dust Management
- Noise Management
- Transport and Traffic Management and Site Access
- Waste Management







SWP Ref: 1505626 Date: 25 July 2016

1.2. Project Description

Location

The proposed landscape supplies production facility is located on Lot 1, 65-73 Dunheved Circuit, St Marys NSW 2760 as shown on the locality in *Figure 1*.

The site is located within Precinct 1 of the Dunheved/ St Marys Industrial Area and is zoned General Industrial IN1.

Current surrounding area contains a mix of industrial, manufacturing, storage and transport type industries.



Figure 1- Site Locality Proposed of Landscape Supplies Production Facility







SWP Ref: 1505626 Date: 25 July 2016

Operational Activities

The proposed facility receives and processes Virgin Excavated Natural Materials (VENM), predominantly sandstone into certified civil landscape materials.

The proposed facility utilises heavy plant equipment including trucks, excavator and a 50 tonne J1175 mobile crusher as part of its operations in processing the VEMN.

The proposed facility anticipates a transportation total of 1000 tonnes of material per day equating to approximately 40 truck movements per day.

Hours of Operation

The proposed facility's normal hours of operation is between 6.00am to 7.00pm, 6 days, Monday – Saturday.

During peak operations, site activity may extend to 24 hours, however traffic movement is not anticipated outside the normal hours of operations.

At no time on Sundays or public holidays would the facility operate.

1.3. OEMP Context

Applicable Legislation

Table 1 defines the relevant legislation that applies to the operation of the proposed facility. In the event of any inconsistency arising between the implementation of the OEMP, and state or local government regulations, the regulatory requirements take priority.







SWP Ref: 1505626 Date: 25 July 2016

Table 1 - Applicable Legislations

Legislations	Intent	Regulatory authority	
Environmental	To assess the impact of the	NSW Department of	
Planning and	development proposal on the	Planning and	
Assessment Act 1979	environment.	Infrastructure.	
Protection of Environment	To regulate activities so as	NSW Environment	
Operations Act 1997	to prevent pollution of the environment.	Protection Authority.	
Protection of the	Details the requirements a	New South Wales	
Environment Operations	business is required to	Environment Protection	
(Clean Air) Regulations	adhere to with the aim of	Authority.	
2010	ensuring the long-term		
	quality of natural air.		
Protection of the	Details the requirements	New South Wales	
Environment Operations	that a business is required	Environment Protection	
(Noise Control)	to adhere to with the aim of	Authority.	
	minimising and controlling		
- Protection of the	Gives specific details as to	New South Wales	
Environment Operations	how businesses should	Environment Protection	
(Waste) Regulation 2005	manage any waste or by-	Authority.	
Environmental	products generated during		
Management Program	business activities.		







SWP Ref: 1505626 Date: 25 July 2016

1.4. OEMP Objectives

The objectives of the OEMP are to:

- Manage site activities effectively;
- Identify all appropriate environmental safeguards and demonstrate how they will be implemented on-site;
- Enable adverse impacts on the environment to be minimised;
- · Meet all requirements of relevant legislations
- Monitor and manage environmental impacts.

2. Environmental Management Program

2.1. Components of the OEMP

Environmental issues identified in this OEMP are specific to the operational phase of the proposed facility. The OEMP has been prepared in an issues-based format that nominate for each environmental issue or impacting activity, the tasks that are required to be addressed during the operational phases of the proposed facility covering:

- Environmental issue.
- Environmental objectives.
- Control measures.
- Responsibility.
- Monitoring.
- Reporting.
- Performance Indicators.
- Corrective Action.

2.2. Operational Phase Environmental Issues

Environmental issues identified in this OEMP are included for the operation phase of the proposed facility. The operation phase OEMP issues are detailed in Table 2. Table 2 provides each environmental aspect.







SWP Ref: 1505626 Date: 25 July 2016

Table 2 - Operational Phase Environmental Issues

Activities	Environmental aspect(s)	Potential Environmental Impact(s)	
Truck movement	Noise Management	Generation of dust impacting nearby occupants	
	Air Quality	Generation of dust impacting nearby occupants	
Loading/Unloading	Noise Management	Noise nuisance to surrounding occupants	
Trucks	Air Quality	Generation of dust impacting nearby occupants	
	Traffic Management	 Congestion causes operational delays. Congestion becomes a human health hazard (air quality) Congestion causes injury or loss of life 	
Crushing Raw	Noise Management	Noise nuisance to surrounding occupants	
Materials	Air Quality	Generation of dust impacting nearby occupants	
Staff and Contractors Waste Disposal	Waste Management	 Litter entering surrounding environment Recyclable not being recycled On-site build-up of litter resulting in a health, fire or safety hazard 	

2.3. Roles and Responsibility

All relevant staff employed and contractors appointed by the proposed facility shall be formally advised of their obligations under the OEMP and informed of the significance of the OEMP.

It is the responsibility of the Site Supervisor to ensure all staff and contractors adhere to their environmental obligations.

It is the responsibility of the Site Supervisor to ensure all performance indicators are within the acceptable limits in accordance with the relevant legislations.







SWP Ref: 1505626 Date: 25 July 2016

2.1. Complaints Response Procedure

All complaints and enquiries will be recorded in a Complaints Register. The information recorded in this register will include:

- date and time of the contact or complaint;
- means by which the contact or complaint was made (telephone, mail or email);
- any personal details of the individual who provided the information or complaint, or if no details were provided, a note to that effect;
- the nature of the comment or complaint;
- · record of operational and meteorological condition contributing to the comment or complaint;
- any action(s) taken by the proposed facility in relation to the comment or complaint; including any follow-up contact with the individual who provided the information or complaint;
- if no action was taken by the proposed facility in relation to the comment or complaint, the reason(s) why no action was taken.

The General Manager and Site Supervisor will be responsible the Complaints Register is kept up to date.

2.2. Non Conformance Register

A Non-Conformance Register will be maintained which contains all corrective action notices.

2.3. Regular Document Review

The currency of all copies of the OEMP shall be reviewed annually to ensure that current versions of the OEMP are available to staff and contractors and obsolete versions are removed to avoid errors and confusion.







SWP Ref: 1505626 Date: 25 July 2016

3. **Implementation**

3.1. Risk Assessment

A risk assessment has been undertaken of the potential environmental impacts from the facility's operational activities to ensure that the appropriate environmental assessment, conditions of approval, and any other site investigations are effectively translated into operation at the proposed facility.

The risk assessment process is based on the Australian Standard, (AS/NZS 4360:2004) Risk Management and (ISO14001), which provides qualitative measures in estimating the consequence or impact of an event, against the likelihood of occurrence. Each risk was assessed as being low (L), medium (M) or high (H) in terms of both consequence and likelihood. The Risk Analysis Matric shown in Table 3 was applied to assess the priority of the various hazards identified.

Table 3 - Risk Management

	Consequences					
Likelihood	Insignificant	Insignificant Minor Moderate Major Catastrophic				
Almost Certain	L	М	Н	Н	Н	
Likely	L	М	Н	Н	Н	
Moderate	L	М	Н	Н	Н	
Unlikely	L	L	L	М	Н	
Rare	L	L	L	М	М	







SWP Ref: 1505626 Date: 25 July 2016

3.1. OEMP Environmental Impacts and Control Measures

Air quality Control Measures

Air Quality - Dust Mana	gement			
Potential Impact	Generation of dust impacting nearby occupants Risk Rating L			
Operational Objective	Minimise impacts on air quality			
	To ensure compliance with the following legislation: Protection of the Environment Operations Act 1997 Protection of the Environment Operations (Clean Air) Regulations 2010 The following legislation:			
Management Strategies	The following practices and procedures will be adopted to ensure that dust levels are adequately controlled:			
	 Installation of automatic water spray dust control system along the boundary of the site. 			
	 Minimising traffic movements on exposed areas; 			
	Dampening of stockpiles;			
	 Removing mud from vehicles on rumble grid before leaving the site 			
	 Providing awareness training in the importance of minimising dust generation at its source. 			
Monitoring	Dust monitoring will be conducted visually throughout the day by a Site Supervisor in charge on the day.			
	The Site Supervisor will have access to dust gauges which will be used in assisting management of dust on the site.			
Reporting	All incidents of pollution will be reported to the Site Supervisor.			
Performance Indicators	No valid air quality/ dust complaints received in relation to operation of the facility			
Corrective Action	 In the event the above management strategies are inadequate, additional dust suppressant measures will be implemented such as additional water spraying activity. 			







SWP Ref: 1505626 Date: 25 July 2016

 Non-conformance with this plan shall be documented and a corrective action request (CAR) issued. All CARs shall be included in the non-conformance register.

Noise Management Control Measures

Noise Management				
Potential Impact	Noise nuisance to	Risk Rating	L	
	surrounding occupants			
Operational Objective	Minimise operational nois	•		
	To ensure compliance wi	th the following le	gislation:	
	 Protection of the Environment Operations Act 1997 The Protection of the Environment Operations (Noise Control) Regulation 2008 NSW Industrial Noise Policy (1999) 			
Control Measures	The following practices and procedures will be adopted to ensure that noise levels are adequately controlled:			
	Establish a soft la boundary	ındscape buffer ar	rea along the northern	
	Minimising traffic	movements		
	Limit truck air breaks			
	 Perform facility operations during normal hours of operation 			
	The following practices and procedures will be adopted to ensure t noise levels are adequately controlled:		I be adopted to ensure that	
	 Regular inspections of noise levels will be conducted in the early stages of the facility operation to confirm the quantity noise pollution 			
Monitoring	 Site supervisors is to ensure noise levels are with the noise level limits using sound measuring equipment in accordance with Australian Standard 1259 Acoustics - Sound Level Meters as a Type 1. Measurement should be done in accordance with the procedures of Australian Standard 1055 – Acoustics-Description and Measurement of Environmental Noise. 			
Reporting	All incidents of pollution will be reported to the Site supervisor.			
Performance Indicators	No valid noise complaints received in relation to operation of the facility.			







SWP Ref: 1505626 Date: 25 July 2016

No exceedance of the noise limits of 70 dB specified and local legislations for industrial areas.	
Corrective Action	 Non-conformance with this plan shall be documented and a corrective action request (CAR) issued. All CARs shall be included in the non-conformance register.

Transport and Traffic Management and Site Access Control Measures

Transport and Traffic N	lanagement and Site Access	
Potential Impact	a) Congestion causes Risk Rating L	
	operational delays.	
	b) Congestion becomes a	
	human health hazard (air	
	quality)	
	c) Congestion causes injury or H	
	loss of life	
Operational Objective	Ensure safe and efficient access of general traffic the proposed facility	to and from
Control Measures	The following practices and procedures will be adopted t traffic are adequately controlled:	o ensure that
	 Provide a six (6) space carpark for staff and contri 	ractors.
	 The loading and unloading activities will take place in the facil only. 	
	 Truck drivers will be given specific instructions for loading/unloading activities on site. 	
	 Ensure that all truck drivers are aware of the access requirements 	
	 Ensure that all truck drivers are aware of procedures once or site 	
	 Ensure that the necessary permits and licenses are obtained if equipment deliveries using oversized vehicles are required. 	
Monitoring	The Site Supervisor is to monitor compliance and effectiveness of the control measured implemented for traffic and undertake appropriate mitigation procedures to address any deviations.	
Reporting	All incidents will be reported to the Site supervisor.	
Performance Indicators	No valid traffic complaints	







SWP Ref: 1505626 Date: 25 July 2016

	No traffic accidents on or relevant to the site.	
Corrective Action	 Non-conformance with this plan shall be documented and a corrective action request (CAR) issued. All CARs shall be included in the non-conformance register. 	

Waste Management Control Measures

Waste management e			
Waste Management			
Potential Impact	 Litter entering surrounding environment 	Risk Rating	L
	 Recyclable not being recycled. 		L
	 On-site build-up of litter resulting in a health, fire or safety hazard. 		L
Operational Objective	 To minimise waste generated at the site and reduce to volute of waste requiring disposal to landfill. To prevent disposal of waste from site to receiving environments. To maintain the site in a neat and tidy state without build-uplitter. To ensure compliance with the following legislation: Protection of the Environment Operations Act 1997 (POE Act) Protection of the Environment Operations (Waste) Regulations 		ving hout build-up of ation: t 1997 (POEO
Management	The following practices and procedures will be adopted to reduce the		
Strategies	amount of waste being disposed of at	: landfill:	
 The site will include two (2) 240L separate collection I designated for general waste and recycling of recyclin paper/cardboard, glass, PET plastic and aluminium of the bins will be collected and emptied every two (2) verification will be given to the waste management outlined in the Waste Avoidance and Resource Recovery — Avoidance. Resource recovery Disposal. Ensure that a dedicated storage area for the separations. 		recycling of nium cans. (o (2) weeks. gement hierarchy Recovery Act	
	collection and recycling of was and contractors and for collect provided and maintained.	ste with good acc tion by recycling	ess by all staff companies is
	 Between collection periods, al generated upon the site shall 		







SWP Ref: 1505626 Date: 25 July 2016

	securely fitting lids so that the contents are not able to leak or overflow.
Monitoring	 Monitor quantities (volume and/or weight) of waste recovery during early stages of operation to determine whether collection frequencies are adequate. Regular inspection of the surrounding areas shall be undertaken to ensure no waste has escaped from the proposed facility.
Reporting	 All accidental waste discharged into the surrounding areas of the proposed facility will be reported to the Site Supervisor. Failure of any aspect of the waste management system shall result in a review of the reasons for the failure and the implementation of corrective actions.
Performance Indicators	 Visual inspection of on-site storage and permanent drains shall be used to assess compliance with waste management plan. The following shall indicate a failure and the need for corrective action:
	 presence of litter on the property; presence of litter in adjacent environments; and presence of pests or nuisance species.
	Compliance with the Work Health and Safety Act 2011, regulations for waste management and public health and the guidelines for relevant statutory authorities.
Corrective Action	Should extensive littering occur, a review of the waste management systems will be undertaken and appropriate measures (e.g. bin placement, education) shall be implemented, such as provision of additional waste containers (either general or specific purpose) or an increase in the frequency of waste collection.







SWP Ref: 1505626 Date: 25 July 2016

4. Closure

We trust this OEMP provides a clear direction on the selection and implementation of appropriate environmental control and monitoring techniques for the operation of proposed facility with the least environmental impact and in accordance with relevant environmental legislations.

Should you require further information or clarification on the matter, please do not hesitate to contact the undersigned.

Yours Faithfully,

Silver Wolf Projects Pty Ltd

Prepared by:

Jimmy Tran
Structural/Civil Engineer
B.Eng (Civil) B.Bus (Finance) Grade IE Aust.

LE CONTRACT

Reviewed, Issued & Approved by:

Deniz Bekir
Principal Engineer/Building Consultant
B.E. (Civil)(Hons) Certificate IV Building Studies
MIE Aust. CPEng NER RPEQ EC (VIC BPB)
Unrestricted Demolition Supervisors Certificate
NSW Building Contractors Lic No. 161767C







